

STACK

LONGHOUSE

13


PIAZZA



SOUTH BANK

Festival of Empire ...

40 years ago




1911 — a colourful year of splendour and pageantry. A coronation year — that saw the opening of the Festival of Empire at the Crystal Palace. In gaily decorated pavilions visitors viewed with wonder the riches and wealth of the exhibits that had come from every part of the Empire.

Well known to the public for quality and durability, Nine Elms Paint and Distemper were extensively used throughout the Exhibition.

Today as then,

Nine Elms Pure Paint Products are used wherever high quality paint is demanded. For many generations, discriminating paint users have found that the consistently high standard of these paints has more than met their every need. Today — the NINE ELMS reputation for quality has become an established tradition.

T. & W. Farmiloe's
NINE ELMS PURE PAINT PRODUCTS



ROCHESTER ROW, WESTMINSTER, LONDON, S.W.1. Phone: VICTORIA 4480



**Sheet Lead, Lead Pipe, Brasswork
and Sanitary Fittings**



A TRADE MARK AS
GOOD AS A BOND

Farmiloe's reputation for quality has been won and is maintained by combining expert knowledge and the finest materials available. Our Technical Department is at your disposal for advice and information.

SHEET LEAD and **LEAD PIPE** for all purposes and to any appropriate B.S. specification.
SILVER, COPPER/LEAD PIPE to B.S.S. 1085.
LEAD TAPE and **WIRE**.
COMPO PIPE, LEAD TRAPS and **BENDS**.
SOLDERS; plumbers: *Tinnans' & Bloo* pipe to B.S.S. 219.

LEAD WASHERS for galvanised iron roofing.
BRASSWORK, *Cast Plumbers' Brasswork* to Architects' specification. Large size valves of all kinds. $\frac{1}{2}$ " to 3". Stopcocks and $\frac{1}{2}$ " to 4" Ball valves a speciality.
SANITARY EARTHENWARE and **FIRECLAY** and all complementary fittings.




T. & W. FARMILOE LTD., ROCHESTER ROW, WESTMINSTER, LONDON, S.W.1. 'Phone: VICTORIA 4488

ROOF STRUCTURE Royal Festival Hall



Architects to the London County Council:
Robert H. Mathew, A.R.I.B.A., and staff.
Consulting Engineers:
Scotts and Wilton, M.M.Inst.C.E.
General Contractors:
Holland & Hannen and Cubitts Ltd.

Steelwork by
REDPATH BROWN
AND CO. LTD., ALBEMARLE STREET,
LONDON, W.1.



Lansbury Neighbourhood, London County Council Stepney/Poplar Reconstruction Area—Shopping Centre and Market Place.

The Festival of Britain **EXHIBITION OF ARCHITECTURE**

This London County Council development is the first stage of a shopping centre and market place to serve Lansbury and other adjoining neighbourhoods in the Stepney/Poplar reconstruction area. It consists of 38 arcaded shops, 39 maisonettes, 4 flats and 2 public houses, with ancillary garages, etc., grouped on two sides of a market place for 136 stalls and a covered market. The market place is being constructed on behalf of the Poplar Metropolitan Borough Council.

The illustration shows SISALKRAFT 60/60 (heavy) grade Reinforced Waterproof Building Paper used for sarking under random slating, as specified.

Photograph by courtesy of Robert H. Matthew, Esq., A.R.I.B.A., Architect to the Council, and Frederick Gibberd, Esq., F.R.I.B.A., M.T.P.I., Appointed Architect. Contractors: Leslie & Co. Ltd. Roofing Contractors: E. F. Williams, Ltd.

Sole Distributors for British Sisalkraft Ltd.


J.H. SANKEY & SON, LTD.

ALDWYCH HOUSE, ALDWYCH, LONDON, W.C.2.

SISALKRAFT
TRADE MARK

Tel.: Holborn 6949. 'Grams: Brickwork, Estrand, London

an engineering triumph— the 'Talgo' points the way to still greater developments...



The "Talgo"
The new aluminium train
designed for service in Spain.

Nowadays we have hardly time to marvel at our own achievements before some new, some greater project is under way. Progress is inevitable. Just as inevitable as the fact that aluminium is part of this process of progress. It is happening all the time, and all the time aluminium is enabling it to happen. Engineers, technicians and designers are finding that the metal that helps them most is aluminium.

Progress has brought ever-increasing new uses of aluminium. Keeping pace with these developments requires adequate supplies of this light metal, produced in the most economical manner through an integration of the many stages of production from the mining of bauxite, shipping of raw materials and generating of hydro-electric power, to the ultimate extraction and fabrication of the metal—all assisted by research, technical and commercial services. This co-ordination is achieved through Aluminium Limited, the Canadian Parent Company, whose subsidiaries are located chiefly in the British Commonwealth.

ALUMINIUM UNION LIMITED

AN ALUMINIUM LIMITED COMPANY

THE ADELPHI, STRAND, LONDON, W.C.2

PRINCIPAL BRITISH COMMONWEALTH DISTRIBUTOR OF ALUMINIUM

FESTIVAL OF FENESTRATION

We all like light and sunshine. The Festival architects have worked on this principle. Windows and glass are all round the visitor to the South Bank wherever he walks. Many of these windows were produced by Williams and Williams, notably in the Transport Pavilion. This building, designed by Rodney Thomas of Arcon, is housing the nostalgic Schneider Trophy Seaplane, early and modern locomotives and other exhibits relating to travel. It is an interesting example of how Williams and Williams have been able to co-operate with architects to produce glazing of such outstanding design.

The great 45ft. x 100ft. opening windows of the Transport Pavilion are one of the exhibition's most interesting architectural features. The structural steelwork forms four bays, the two in the centre opening to allow ventilation to the building. Williams and Williams steel sash windows have been used on both the fixed and opening bays. Note how horizontal plate glass at the bottom of each bay contrasts with the upward sweep of the glazing above.

Biggest panes of glass in the Pavilion In the side of the main structure, below the tall side windows, there are Williams and Williams steel sash windows containing 6' 6" x 20ft. single panes of $\frac{1}{4}$ " polished glass.

Glazing as a means of contrast The architect has, in the north wing of the Transport Pavilion, used various forms of windows to form contrasts. It is a method of using windows that is novel and interesting (top left).

Three ranges of Aluminex Patent Glazing over 100ft. long and 15ft. deep surmount a long pressed Aluminium window from the Rofen Factory of Williams and Williams, which is 6ft. deep. The slim tracery of Aluminex is admirably offset against this horizontal range of glass. Butting on to the Aluminex, is a range of steel sash windows. It is glazed in foot squares of reeded glass and is in crisp contrast to the Aluminex beside it.

Teleflex gearing on the Pavilion Teleflex gearing is installed on the range of Aluminex mentioned above. One hand control completely opens the three ranges of Aluminex in 15 seconds. The actual weight of Aluminex on the single hand operated control is three tons.



At the rear of the Pavilion there is a stretch of universal steel casement which illustrates the use of Teleflex with ordinary steel windows (bottom left). Opening lights, staggered into alternate lines of seven and eight are hand controlled, as on the Aluminex stretch, from one single point. Teleflex gear can of course operate on single lines, or even one light instead of in series, as in this building.

The curved windows on the approach ramp totalling an overall length of 132ft. with the height varying from 20ft. to 28ft. were also constructed by Williams and Williams.

Williams and Williams Limited

Makers of Metal Windows, Doors and Aluminex Patent Glazing
RELANCE WORKS · CHESTER

Architects: ARCON. Contractors: RICHARD COSTAIN LTD. Main Consulting Engineers: FREEMAN FOX & PARTNERS. Consulting Engineer to Architect: FELIX J. SAMUELY in collaboration with H. GOTTFELDT







"..... I shall always be grateful that the Architect had the foresight to

SEND FOR THIS BOOK

before planning my kitchen. I now have a perfect kitchen with styled sink unit, cupboards and cupboards, cooker, refrigerator and domestic boiler all to match."

"English Rose" Kitchen Equipment is of Aluminium construction with stainless steel continuous work top, and shows many economies over conventional kitchen and larder arrangement.

Ask for publication E.R.4. — free upon request.

C.S.A. INDUSTRIES LTD., WARWICK.
London Showrooms : 229-231, Regent Street, W.1.

Telephone : MAYfair 9975



English Rose
REGD TRADE MARK
KITCHEN EQUIPMENT


The "Sapphire"
Fully Patented
Balanced Flue Gas Heater
as installed in
Guy's Hospital, London



A TYPICAL "SAPPHIRE" INSTALLATION
IN THE NURSES' RESIDENCE
BY THE COURTESY OF GUY'S HOSPITAL
AND THE SOUTH EASTERN GAS BOARD

Full information upon request from sole manufacturers
Cowper Penfold and Company Limited
6, Basil Street, Knightsbridge, London S.W.3.

Telephones: Kensington 3677-8-9



In character, manners, and style, the supreme
excellence is simplicity . . . in interior decoration
this is most readily achieved by the
use of Walpamur Quality Paints.



THE WALPAMUR CO LTD • DARWEN AND LONDON

W107

FRANKIPILES

for major and minor projects



Messrs. Fisons Ltd., Immingham.

Founded on 5,734 Frankipiles.

Consulting Engineers: Messrs. Maunsell, Posford & Pavry.

FRANKIPILES CARRY MORE TONS PER PILE


THE FRANKI COMPRESSED PILE CO., LTD.

39, Victoria Street, London, S.W.1.

'Phone: ABBey 6006-9.

'Grams: Frankipile, Sowest, London.

SOUTH AFRICA: Franki Piling Co. of S.A. (Pty.) Ltd., Durban & Capetown.



MATHER & PLATT LTD
MANCHESTER, 10

M&P Fire Doors halt blaze

On the night of March 24th, 1950, Mather & Platt Fire Doors checked the spread of fire at premises occupied jointly by a firm of raincoat manufacturers and a firm of food manufacturers. The installation of Fire Doors and one steel rolling shutter built to F.O.C. requirements had been completed only three months previously.

**80,000 Coats
destroyed
in adjoining
premises**

Press reports say that "Within a few minutes flames had swept the length of the 100 yards by 75 yards building, destroying 80,000 raincoats being made up for Government orders." The party wall which separated the premises of the food manufacturers from those of the raincoat manufacturers was pierced by a series of openings, protected by Mather & Platt Fire Doors and a Steel Rolling Shutter. The Doors and Shutter fulfilled their purpose perfectly. The fire was completely checked at the party wall.

**Mather & Platt
FOC Shutter
guarding a
vital stairway**

A special problem was presented by a flight of steps leading down from the first floor of the gutted building to the ground floor of the building which remains intact. It was solved by the installation on one side of the wall of a steel rolling shutter built to F.O.C. requirements, and on the other a Fire Resisting Door. The Steel Rolling Shutter held the fire in check at this point.



CELOTEX LOOKS BACK AT THE GREAT EXHIBITION 1851

The Buildings Court

"One of the most interesting and important departments in the Great Exhibition was that . . . known as the Buildings Court which contained a great variety of ornamental works, chiefly of an architectural character, and also samples of cements, artificial stone and other compounded materials intended to be used as substitutes for stone and marble" (*Contents of the Crystal Palace* London 1852). In these days, the phrase 'and other

materials' would no doubt include Celotex, but Celotex is not a substitute for stone or marble, nor indeed, for anything else. It is a modern building material in its own right, with its own outstanding qualities, chief among which are structural strength and a high degree of thermal insulation.

CELOTEX

CELOTEX LIMITED, NORTH CIRCULAR ROAD, STONEBRIDGE PARK, LONDON, N.W.10

HEATING · SANITATION

ARTHUR

SCULL

& SON LTD.

*Festival Gardens
Battersea Park*

*Contractors for Plumbing,
Cold Water, Hot Water and
Specialized Fire Protection Service.*

BRISTOL LONDON CARDIFF
TRINIDAD MALTA EAST AFRICA

CLAY YESTERDAY . . . CLAY TODAY . . . CLAY TOMORROW

*The Temple of Heraeum
at Olympia*



Clay LASTS

Many instances of the use of Clay by the early Greeks have been found. A notable example is the Heraeum at Olympia, a building of great antiquity where Clay Bricks were used extensively and the roof was entirely of Terra-Cotta.

The Greeks used Clay Roofing Tiles . . . so did the Romans and today the Clay Tile is still unsurpassed as a roofing medium.

Fired to high temperatures, weatherproof, and available in a wide range of styles and in a variety of permanent colours, Acme Clay Roofing Tiles are made from the famous Etruria Marls of North Staffordshire. Whatever the Building project there is an Acme Tile to suit the most exacting requirements. Acme Tiles enable the uniformity of housing schemes to be maintained yet provide for the exact taste of the individual.

The Acme Catalogue, giving full information of the complete range of Acme Clay Roofing Tiles is available on request.

For enduring beauty . . . specify



ACME CLAY ROOFING TILES

*The ACME Range of
Roofing Tiles includes*

ACME M. M.
ROOFING TILES
ACME SANDSTORM
ROOFING TILES
ACME CENTURY
HANDMADE SANDEFACED
also
ACME
RED FLOOR QUARRIES

G. H. DOWNING & CO. LTD., Dept. C.2, BRAMPTON HILL, NEWCASTLE-UNDER-LYME, STAFFS.
Telephone: Newcastle-under-Lyme 65381

L.G.B.



An iron-bellied pot

IN THE YEAR 1709 Abraham Darby, having taken out a patent for "a New Invention for Casting Iron-Bellied Pots in Sand without Loam or Clay," started his foundry at Coalbrookdale in Shropshire, and it was from Coalbrookdale that the foundry industry spread to the Falkirk area in Scotland.

Today, in Scotland, the Allied Ironfounders group includes such famous names as the Falkirk Iron Company, founded in 1810; the Callendar Abbots Foundry; M. Cockburn; Dobbie Forbes; the Forth & Clyde & Sunnyside Iron Companies; and McDowall Steven. The *auld alliance* between Falkirk and Coalbrookdale still lives, for the Coalbrookdale foundry is now one of the twenty-two leading firms which constitute Allied Ironfounders Ltd.

The fine products of these Scottish foundries are known throughout the world. They include Falkirk Heavy Duty Equipment, as installed in the New House of Commons, Cockburn Luxury Baths, and the Rayburn and the Truburn


Cookers. Among the Heating Stoves are such household names as Otto, Diana, Apollo, Jupiter. Open Fires include the New Marathon, Haddon, New Zenith and Vector. Then, again, there is the vast range of rainwater and soil pipes. Indeed, there is hardly a home in the whole of Great Britain which is not indebted for some of its comfort, and its happiness, to the Scottish foundries which are members of Allied Ironfounders Limited.




Falkirk Heavy Duty Equipment



ALLIED IRONFOUNDERS LTD. Mortimer House, Mortimer Street, London, W.1



BEACON UNIVERSAL WINDOWS



Installed at TYNE PLYWOOD FACTORY

Architects: Messrs. Jack Cotton, Ballard and Blow, Birmingham.

Contractors: Sir Robert McAlpine & Sons Ltd.

JOHN THOMPSON BEACON WINDOWS
LIMITED



Ettingshall, Wolverhampton & Imperial House, Kingsway, London, W.C.2

Telephone: BILSTON 41121

Telephone: TEMPLE BAR 3216

SEE OUR EXHIBIT AT THE BUILDING CENTRE, 9 CONDUIT STREET, LONDON, W.1.

TRANSFORMATION IN TILES



Pilkington's

PILKINGTON'S TILES LIMITED

CLIFTON JUNCTION, NEAR MANCHESTER. Phone : SWinton 2024-5-6

London Office: 27b Old Gloucester Street, Holborn, W.C.2. Phone: HOLborn 2961-2

Adamsez Ltd

54 VICTORIA ST. S.W.1

WORKS : SCOTSWOOD-ON-TYNE

The "BEAN" Drinking Fountain






CHUBB and the Festival of Britain

Chubb Treasury Door, selected by The Council of Industrial Design for exhibition in the Power and Production Pavilion, South Bank, London. The illuminated showcase, containing coins, notes and cheques, was arranged by the London Bankers.

CHUBB & SONS LOCK & SAFE CO LTD 40-42 OXFORD STREET LONDON W1




1.



2.



3.



4.

a good name for Building & Civil Engineering



5.

1. St. Mary's Church, Erdington, Birmingham. Wood and Kendrick and Edwin F. Reynolds, F.R.I.B.A.
2. Prudential Buildings, Birmingham. The Estate Dept., Prudential Assurance Co. Ltd.
3. Odeon Theatre, York. Harry W. Weedon, F.R.I.B.A. and Partners.
4. Convalescent Home, Kewstoke, Weston-super-Mare. W. H. Martin, L.R.I.B.A.
5. The Good Companions, Sheldon, Birmingham. S. N. Cooke and Partners.

It's a good job
it's
Bryants

C. BRYANT & SON LTD. WHITMORE ROAD, B'HAM, 10. Telephone: VICTORIA 2333-8. London Office: 66 VICTORIA STREET, S.W.1.

L.G.B.



SEMTEX

At the *FESTIVAL of BRITAIN*

SOUTH BANK

TELECINEMA: Fleximer flooring in cloakrooms and toilets
Semastic Decorative Tiles in the projection room
Fleximer underlay to carpet in the auditorium

Architect: **WELLS COATES, F.R.I.B.A.**
Contractors: **HOLLAND & HANNEN and CUBITTS LTD.**

TELEVISION: Fleximer flooring in entrance hall and exhibition area

Architect: **WELLS COATES, F.R.I.B.A.**
Contractors: **HOLLAND & HANNEN and CUBITTS LTD.**

THE PEOPLE OF BRITAIN: Decorative linoleum floor in exhibition area

Architect: **JAMES GARDENER, O.B.E., R.D.I., F.S.I.A.**
Contractors: **DAVID ESDALE & CO. LTD.**

HOMES AND GARDENS: Semastic Decorative Tiles in the Rural Kitchen
Vinyl Tiles in the breakfast bar

Designers: **MARCUS LATIMER & WALTERS, M/M.S.I.A.**
Contractors: **WESTMINSTER JOINERY CO. LTD.**

Vinyl Tiles in Hobbies sections
Designers: **ROBERT NICHOLSON, M.S.I.A.**
ROGER NICHOLSON, A.R.C.A.

Contractors: **WESTMINSTER JOINERY CO. LTD.**

PANTECHNICON: Semastic Decorative Tiles on vertical panelling

Architects: **PATIENCE CLIFFORD & NEVILLE CONDER, A/A.R.I.B.A.**
Contractors: **RUSSELL BROS. (Paddington) LTD.**

THE NEW SCHOOLS: Semastic Decorative Tiles in display tray

Architects: **PATIENCE CLIFFORD & NEVILLE CONDER, A/A.R.I.B.A.**
Contractors: **KIRK & KIRK LTD.**

POWER AND PRODUCTION: Display panels of vinyl tiles in the Plastics Section of the Hall of Industry

Designer: **GEORGE FEJER, M.S.I.A., F.R.S.A.**

BRITISH SEASIDE: Resilient mortar for special mosaic

Designer: **J. DAWSON BINNS, A.R.C.A.**

CHARING CROSS STATION

REFRESHMENT ROOM: Terrazzo tiles and Semastic Decorative Tiles

EXHIBITION OF SCIENCE

South Kensington

RESTAURANT: Crystal pattern decorative floor in new vinyl material. A commercial example of latest development in the new high-polymer synthetic resins as demonstrated in the exhibition

Architect: **BRIAN PEAKE, F.R.I.B.A., A.A.Dip., M.S.I.A.**
Contractors: **HIGGS & HILL LTD. and RUSSELL BROTHERS (Paddington) LTD.**

EXHIBITION AREA: Semastic Decorative Tiles throughout

Architect: **BRIAN PEAKE, F.R.I.B.A., A.A.Dip., M.S.I.A.**
Contractors: **HIGGS & HILL LTD., and RUSSELL BROTHERS (Paddington) LTD.**

EXHIBITION OF ARCHITECTURE

Poplar

OLD PEOPLE'S HOMES: Semastic Decorative Tiles

(Laid in association with Hollis Brothers Ltd. of London)

Architects: **BOOTH & LEDEBOER, A/A.R.I.B.A.**
Contractors: **C. MISKIN & SONS LTD.**

PLEASURE GARDENS

TEA BAR: Semastic Decorative Tiles

(Laid in association with Hollis Brothers Ltd. of London)

Architects: **K. DALGLIESH & R. K. PULLEN F/R.I.B.A., A.A.Dip.**
Contractors: **DOWSETT ENGINEERING CONSTRUCTION CO. LTD.**

HAMLEY'S TOY SHOP: Linoleum flooring

EXHIBITION OF INDUSTRIAL POWER

Kelvin Hall, Glasgow

MACHINE SHOP: Industrial fleximer flooring

PUBLIC CIRCULATION AREA: Fleximer flooring

Architect: **ALBERT SMITH, F.S.I.A.**
Contractor: **ARMSTRONG WRIKDALE ORGANISATION**

FESTIVAL SHIP "CAMPANIA"

EXHIBITION AREA: Semastic Decorative Tiles throughout

Architect: **VICTOR BRUCE**
Contractors: **CAMMELL LAIRD & CO. LTD.**

WEATHER DECKS: Fleximer surfacing throughout

SEMTEX LIMITED

A DUNLOP COMPANY

Specialist Flooring Contractors


185-187-189 FINCHLEY RD., LONDON, N.W.3

158/C1C

Good design in the electrical installation

MEMERA

This MEM consumer's service unit is housed in neat metal cases of matched design, simple to install, easy to wire and absolutely safe. It offers the choice of cartridge fuses or rewirable fuses—a very attractive feature from the contractor's standpoint. The units can be mounted in a great variety of ways to suit each particular installation. And extensions and alterations are the simplest of matters.



Memspel and Memspan are MEM's latest designs of switchfuse and splitter for domestic installations. They are neater and more compact than anything yet produced and are free of crevices which could harbour dust. These units are available in metal-clad or all-insulated form and will take either cartridge or rewirable fuses. The electrical contractor has welcomed this equipment with enthusiasm because it brings him for the first time a single pole and neutral gear designed specially for the job.

MEM

Switch, fuse and motor control gear, electric fire and localised lighting equipment

Send for the new MEM Switchcraft catalogue List No. 311.

AND NOW

MEMSPEL



AND

MEMSPAN

WIDLAND ELECTRIC MANUFACTURING CO. LTD., TYSELEY, BIRMINGHAM

Branches in London and Manchester



BRITAIN ON SHOW

Wherever visitors go during this Festival of Britain Year, they see the part played by "International" paints—particularly in factories, large and small.

Manufactured products, machinery, Registered

steelwork and general schemes are completed with "International" paints, because they give a superior and lasting finish.

Consult "International" for industrial



paints of all kinds.

on all occasions use

International Paints

INTERNATIONAL PAINTS LTD.



GROSVENOR GARDENS HOUSE, LONDON, S.W.1.

Telephone: VIctoria 3161 (10 lines)

Also at Glasgow • Felling-on-Tyne • Liverpool • Cardiff • Southampton • West Hartlepool, etc.



BY APPOINTMENT
TO THE LATE
KING GEORGE V.



Heywood's flexible organisation brings the same skill and experience to every glazing job, be it large area coverage or small. The impressive total of over 80 million square feet of patent glazing in over 60 years' experience indicates a service which is co-operative, and efficient. The installation of new machinery has now made it possible to offer immediate service on all contracts.

Heywood's technical representatives are available in all areas should you wish to consult them.

W.H. **Heywood**

AND COMPANY LIMITED
HUDDERSFIELD

Telephone - Huddersfield 6594 (4 lines)

Branches at LONDON: 54 Victoria Street, Westminster, S.W.1. MANCHESTER: 19 Old Millgate.
NEWCASTLE-ON-TYNE: 57 Cathedral Buildings. BELFAST: E. H. Pearce and Son, Ltd., 29/33
Laganview Street, and LEICESTER, COVENTRY, LIVERPOOL, BIRMINGHAM, BRISTOL, NOTTINGHAM,
PLYMOUTH, DUBLIN, GLASGOW and EDINBURGH

n.d.h.

NEWALLS

Sprayed LIMPET ASBESTOS

SOLIOS



COUNCIL CHAMBER
BELFAST CITY HALL

The ceiling illustrated has been treated with Sprayed Limpet Asbestos to reduce reverberation, and shows the excellent finish which can be obtained by this method of acoustic treatment.

Sprayed Limpet Asbestos is used wherever a sound absorbent surface is required, and because of its fire-proof and vermin-proof qualities, it is especially suitable for use in Hospitals, Offices, Swimming Baths, and in other places where reverberation is excessive.

Newalls Sprayed Limpet Asbestos is also widely used for acoustic correction in Cinemas, Churches and other Auditoria.

Newalls Insulation Co. Ltd. maintain a fully equipped sound laboratory for the investigation of problems connected with the use of acoustic materials.



NEWALLS


Insulation Co. Ltd.

HEAD OFFICE: WASHINGTON, COUNTY DURHAM
A MEMBER OF THE TURNER AND NEWALL ORGANISATION.

Offices and Depots at: LONDON, GLASGOW, MANCHESTER, NEWCASTLE, BIRMINGHAM, BELFAST, BRISTOL and CARDIFF


Building in Ireland?

Structural Steelwork and Steel Windows by Smith & Pearson Ltd.




An Extension to the Gresham Hotel, Dublin.

Architects: Downes & Meehan



Rotunda Hospital, Dublin: New Pediatric Unit. Architect: Alan Hope, B.Arch., A.R.I.B.A.



Newcastle Sanatorium, Co. Wicklow.


Architect: Alfred Phillips, M.R.I.A.I.

SMITH & PEARSON

SMITH & PEARSON LTD., NEWCOMEN WORKS, OSSORY RD., DUBLIN

STRUCTURAL ENGINEERS AND MAKERS OF FINE STEEL WINDOWS, GATES AND RAILINGS

Ode to an artificial Violet



Shelley, Wordsworth and Keats *might* have written odes to artificial flowers—but it hardly seems likely. Ingenious as they are, flowers of paper and silk have little to inspire the poet.

It's much the same with substitutes for wood. Wood is a natural *living* material with a character all its own. No two pieces of timber are ever exactly alike. Each is a thing of beauty in itself.

All very well, you may think—but what about the timber supply situation? Well, there are certain shortages still—but on the other hand there is a steady expansion in the supply of timber, and many hardwoods are being imported which can be obtained without licence. There may be one exactly fitted to the job you have in mind. Why not drop a line to the Timber Development Association and find out?

There's nothing like **WOOD**

ISSUED BY THE TIMBER DEVELOPMENT ASSOCIATION • 21 COLLEGE HILL • LONDON • EC4
and at Leeds, Leicester, Manchester, Bristol & Glasgow


CRITTALL WINDOWS

IN THE
FESTIVAL YEAR



THE PAVILION OF POWER AND PRODUCTION, SOUTH BANK

GEORGE GRENFELL BAINES, A.R.I.B.A.,
in collaboration with
H. J. REIFENBERG, Dipl. Ing. Arch., Architects
FELIX J. SAMUELY, B.Sc. (Eng.), Consulting Engineer




An interesting mullion detail: extruded aluminium sections are used as cladding to the structural steelwork and form fixed frames to carry the glass; the detail shown is half full size.

THE CRITTALL MANUFACTURING CO. LTD - BRAINTREE - ENGLAND



Controlled comfortable conditions are assured in industrial buildings by BRIGHTRAD Radiant Panels. Designed for surface temperatures of 200°–250°F. these panels give a pleasant working environment. They make for economy in maintenance and running costs.



The BRIGHTRAD Panel consists of a sinuous steam coil, with steel web plates continuously welded between the coils, the whole forming a ribbed panel.

Write for our booklet:—Heating and Air Treatment in Industry.

BRIGHTSIDE

THE BRIGHTSIDE FOUNDRY & ENGINEERING CO. LTD. SHEFFIELD

and at BIRMINGHAM BRISTOL LIVERPOOL LONDON MANCHESTER
NEWCASTLE PORTSMOUTH EDINBURGH GLASGOW BELFAST

BP 25



Wherever you go at the
FESTIVAL OF BRITAIN

★

in the

FESTIVAL HALL

TELECINEMA

RIVER-SIDE RESTAURANT

EXHIBITION OF ARCHITECTURE

LAND TRAVELLING EXHIBITION

PLEASURE GARDENS

AND ABOARD THE CAMPANIA

you will find seating upholstered with
DUNLOPILLO

Dunlop Rubber Co. Ltd. (Dunlopillo Div.) Rice Lane, Walton, Liverpool 9
 London: 19/20, New Bond Street, W.1

FOUNDERS OF THE LATEX FOAM INDUSTRY

An exhibition "British Achievements Made possible by Dunlop", to which
 all members of the public are cordially invited, is being held at the
 Dunlop Showrooms at 19/20 New Bond Street, W.1 during the Festival.

ID/C.

WHEN THE STRUCTURAL STEEL IS BY

**BOULTON
AND PAUL**

IT'S A FIRST CLASS JOB

At Boulton & Paul we are equipped to see a job through from start to finish—from drawing board to fabrication in our shops, to the steel framework erected on the site by our own men. In a Factory Building completed this year for The Daimler Company Limited at Coventry, 400 tons of steel were used.

Architect: Laurence Williams, F.R.I.B.A.

Contractors: Messrs. Higgs & Hill Limited.



● NORWICH • LONDON • BIRMINGHAM

CRC 115E

FERRO-CONCRETE & STONE

(NORTH NOTTS.) LTD.

MODERN STRUCTURAL PRECAST REINFORCED CONCRETE

PERMANENT STRUCTURES.
PAINTING & MAINTENANCE
COSTS ENTIRELY ELIMINATED

FOR
FACTORIES
WAREHOUSES
GARAGES
CHURCHES
PUBLIC-
HALLS
FARM
BUILDINGS
 ETC.



WAREHOUSE AT SHEFFIELD—TWIN SPAN 80'-0" WIDE—
165'-0" LONG. CARRYING OVERHEAD CRANES

ENGINEER :
Ralph Paulger, M.I.Struct.E



TRIPLE-SPAN FACTORY AT MILFORD, DERBY
CARRYING OVERHEAD TRAVELLING CRANE

ENGINEER : Ralph Paulger, M.I.Struct.E.

ALSO-
 SLEEPERS,
 FLOOR
 BEAMS,
 LIGHTING
 POLES,
 CAST
 STONE,
 ETC.

WE DESIGN, MANUFACTURE & ERECT
 FRAMED BUILDINGS UP TO 60'-0" SPAN, AS ILLUSTRATED, ALSO
 IN NORTH-LIGHT CONSTRUCTION. ENQUIRIES TO :

FERRO-CONCRETE & STONE (NORTH NOTTS.) LTD., LOUND, RETFORD

TELEPHONE RANSKILL 212

... it's

KWIKFORM

... *Specialisation in
concrete formwork*



The Two-Component System ensures ease of erection, ease of striking and the utmost economy in usage and maintenance.

Suspended Formwork

Wall Formwork

The adaptable concrete formwork. Designed to meet the widest possible variety of uses; double or single facework; columns; beams; battered retaining walls, etc. etc. Illustrations by courtesy of G. E. & W. WINCOTT LTD.




Kwik
ideal
circu
cour

Barrel Roof Construction is simplified by the use of Kwikform Flexible Formwork. Minimum constructional times—true clean soffit—maximum unobstructed working space—adaptability to any radius—absolute rigidity of form with complete independence of surrounding work.



Illustration left shows the result of concrete poured directly on the "Kwikform" Flexible Formwork. Milk Distribution Centre for Midland Counties Dairy Ltd. Architects: Messrs. Harry W. Weedon & Partners. Contractors: Messrs. C. Bryant & Son Ltd., Birmingham 10.

Kwikform Flexible Formwork is ideal for the construction of circular tanks. Illustration is by courtesy of Pre-Load (G.B.) Ltd.



KWIKFORM LTD.

Descriptive literature of all Kwikform equipment and terms of purchase or hire, available on request.

KWIKFORM LIMITED, Waterloo Rd., Birmingham 25.
London Office: 66, Victoria Street, S.W.1.

BACK TO ITS OLD SPLENDOUR



"The Chamber of the House of Lords"




and **TRANSLUCENT REFLECTORS** by

HOLOPHANE LTD

SCIENTIFIC LIGHTING ENGINEERS

ELVERTON STREET • LONDON • S.W.1

THE FESTIVAL OF BRITAIN EXHIBITION OF INDUSTRIAL POWER, KELVIN HALL, GLASGOW



WRIDALE

built it

From designing and building Advertising Displays in 1926, "Wridale" have progressed through a quarter of a century, until to-day they are amongst the foremost builders of spectacular displays in Britain. "Wridale built it" is synonymous with speed, efficiency and quality. We are justifiably proud in having been associated with the Festival of Britain Exhibition of Industrial Power in the Kelvin Hall, Glasgow—one of the biggest single contracts ever entrusted to one firm—a testimonial in itself.

ARMSTRONG & CO. (WRIDALE) LTD.

London Office: 26 OLD BROMPTON ROAD, S.W.7.
Works: Mount Pleasant, Ashton-under-Lyne, Lancs.

Telephone: KEN. 0025
Telephone: Ash. 3004

WRIDALE
PLANNED
DISPLAY

Where are the BRICKS going?

4: POWER STATIONS

The new generating stations are of massive proportions and necessarily conspicuous. They have received much thought from the aesthetic standpoint, and the bricks used have been carefully selected to harmonise with their surroundings.


The high-priority requirements of the British Electricity Authority, added to the urgent demands for Houses and Flats, Schools, Office Blocks, Industrial and many other types of building, have taxed the resources of the brick industry. Production is increasing in the face of many difficulties, and a steady improvement in the supply position is assured.



Above: Portion of Croydon Power Station, under construction.
Architect: Robert Atkinson, F.R.I.B.A.



Left: Stourport 'B' Power Station.
Architects: Farmer & Dark, F/R.I.B.A.



Below: Staythorpe Power Station.
Architect: T. Cecil Howitt, D.S.O., O.B.E., F.R.I.B.A.

BRICK

The Modern Building Material

Photographs
by courtesy of
British Electricity Authority

Issued by
The National Federation of Clay
Industries, Drayton House, W.C.1



LEAD PIPES
FOR OTHER THAN CHEMICAL
PURPOSES

BS.602

SILVER COPPER
LEAD PIPES TO

BS.1085

BS.1178

LEAD SHEET & STRIP
FOR BUILDING PURPOSES

BS.334

CHEMICAL LEAD
(SHEET & PIPE) FOR TYPES A & B

As in the past, British Lead Mills Ltd. are always in a position to supply their high quality Lead to British Standard Specification. The British Lead Mills supply CHEMICAL LEAD and ANTIMONIAL LEAD SHEET and PIPE, also WASHERS, STAMPINGS, STRIP ROD and OTHER SECTIONS. Advice on all matters appertaining to Lead is gladly given by the firm's Technical Department. Please write to the London Office.

THE HALL-MARK OF HIGH QUALITY LEAD



BRITISH LEAD MILLS LTD., Dashwood House, Old Broad Street, London, E.C.2.

Works : Welwyn Garden City, Tel : London Wall 2632-3. Grams : Britledmil, Ave., London.

**BRADFORDS
ARE
SPECIALISTS IN
CONCRETE DESIGN
AND
CONSTRUCTION**



**HOLLOW-BLOCK FLOORS
CAST STONE
GRANOLITHIC PAVING
STAIRCASES
PRE-CAST CONCRETE FLOORS
PRE-CAST CONCRETE UNITS**



F O U N D E D I N 1 8 9 8



ROYAL FESTIVAL CONCERT HALL

Bradfords were responsible for:
Granolithic finish to staircases.
Granolithic paving to car park.
Granolithic paving to basement.



F. BRADFORD & CO. LTD., ANGEL ROAD, LONDON, N.18 (TOTtenham 4267)

By appointment to H.M. King George VI



Suppliers of Wallpaper and Paint


SANDERSON

WALLPAPERS
and
PAINTS

ARTHUR SANDERSON AND SONS LIMITED

52/53 Berners Street, London, W.1. Tel. : Museum 7800

6/7 Newton Terrace, Glasgow, C.3. Tel. : Douglas 3374



★ A copy of this brochure, describing the exhibits we have supplied for the Woodworking Section in the Power and Production Pavilion will be sent on request.

WILLIAM
MALLINSON
& SONS LTD.

TIMBER AND VENEER MERCHANTS AND PLYWOOD MANUFACTURERS

130-150 HACKNEY ROAD
LONDON, E.2

Telephones : Shoreditch 8888-8811

Telegrams : "Almoner," London

NT6506

WHEN YOU HAVE CAREFULLY WEIGHED UP
THE RELATIVE ACOUSTIC MERITS FROM THE SOUND
OF THE
CORNET, FLUTE, HARP, SACKBUT, PSALTERY, DULCIMER
AND ALL KINDS OF MUSICK EMANATING FROM
THE ROYAL FESTIVAL HALL
TAKE A LOOK ROUND AT SOME OF OUR
GLASS

THE EFFECTIVENESS OF WHICH IS BEYOND DISPUTE



*The glass in the Balustrade consists of half-inch Armoured Plate Glass with flat polished edges.
Supplied and fixed by us to the order of Messrs. J. Starkie Gardner Ltd.*

ARCHITECT : Robert H. Matthew, A.R.I.B.A.


PUGH BROS. LTD.

GLASS • GLAZING • DECORATION

COMPTON STREET, LONDON, E.C.1

CLERKENWELL 3211

*glazing pains
cured
with*



SEALON

metal casement

PUTTY

"Don't use ordinary Putty for glazing Metal Windows"—extract from Ministry of Works Leaflet No. 12.

THE CURE IS SEALON—a Putty specially formulated for the glazing of Metal Casements, supplied ready for use, ensuring a clean smooth finish which will not crack or run and may be painted in three to four days.



*The most keenly priced **TOP GRADE** Casement Putty available*

OBTAINABLE FROM ALL LEADING MERCHANTS

Manufactured by **SEALANCO (ST. HELENS) LTD.**, ST. HELENS, LANCs.

Specialists in the manufacture of Putty for all purposes.



Safeguard her health...

You can help to safeguard her health by specifying "Standard" Sanitary Appliances for schools, hospitals, factories and all public buildings as well as for the home. Crazed or cracked lavatory basins and closets harbour dirt and germs which can jeopardise the well-being of everyone. By selecting "Standard" Sanitary Appliances, you will be taking the first and most

important step towards eliminating this risk. For these high-quality appliances are made of Vitreous China, the perfect sanitary material which cannot craze, discolour or stain, and will remain permanently non-absorbent. "Standard" Sanitary Appliances are strong, of exceptionally good design, will withstand hard usage, and are comparable in price with sanitary ware of inferior material.

VITREOUS CHINA

Standard
SANITARY APPLIANCES

IDEAL BOILERS & RADIATORS LIMITED • IDEAL WORKS • HULL

156

One thing
on another



That's all there is to building whether
in the nursery or on an
industrial site.

The child making his tower of
bricks is father to the man who
builds a skyscraper



Banister, Walton build in steel

LONDON, S.W.1—82 Victoria Street

MANCHESTER 17—Trafford Park

BIRMINGHAM 18—61-63 Western Road

ATLAS


has a whale of a time!



We enjoy ourselves at Thorn
Electrical. It's fun to do the unexpected.
And when we bring out something
really big — like the Atlas "Double-Life"
Fluorescent Lamp — then we have a whale of a
time! It's this spirit that's helped to
speed up the development of
fluorescent lighting. Any day now,
some Atlas scientist will
bring to light yet another
innovation. And again
the cry will go up —
"Thar she blows!"

ATLAS FLUORESCENT

You must have heard — but *just in case you haven't*—ATLAS "DOUBLE-LIFE" lamps last 5,000 hours (*twice the normal life*) and the light efficiency is fully maintained.





Unrivalled **STRENGTH**

Because it is such a picturesque material, the real reasons for the superiority of the Clay Roofing Tile tend to be overlooked. Its pleasing appearance arises from certain physical properties which are exclusive to burnt clay. Strength, for example; which is developed, as in no other material, by the vitrification which occurs at the high temperatures of kiln burning.

This superior strength of Clay Roofing Tiles may not be of outstanding importance in the early days of a building (unless workmen have to traverse them), but as the years go by the ultimate cost of a *clay* tiled roof is a source of satisfaction to those responsible for maintenance.

Reduce the Burden of
MAINTENANCE
by specifying—

CLAY
ROOFING
TILES



"The Clay Tile Bulletin", published quarterly, post free on request.
The National Federation of Clay Industries, Drayton House, W.C.1



Princes Golf Club, Sandwich

The club-house at Princes—famous championship golf course at Sandwich.

Architects: Messrs. Gunton & Gunton, F/R.I.B.A.

Contractors: Messrs. Humphreys Ltd.

Sub-contractors: Messrs. G. H. Denne & Son Ltd. of Deal.

Plumbers: Ellis (Kensington) Ltd.


Sanitary Equipment by Finch

During the war the famous Championship golf course — Princes, Sandwich, suffered severely; its greens and fairways were totally obliterated. Despite all the difficulties, this great course has now been re-designed and is, once again, "in play."

The comfort of those who visit the club has not been forgotten, as the clubhouse has been modernized and its amenities greatly improved.

The Finch Organization is proud to have supplied the Sanitary Fittings to this interesting contract.

Your sanitary equipment problems will be given immediate attention by Mr. Thrower, Manager of Finch Sanitary Division, Extension 30.



B. FINCH & COMPANY LTD., Head Office and Works: BELVEDERE WORKS BARKINGSIDE, ESSEX. Valentine 8888 (30 lines)

Showrooms at FINCH CORNER, 679/687, EASTERN AVENUE, (Southend Road) ILFORD, ESSEX

THREE QUARTERS
OF A MILE OF
HOLOPLAST
MOVABLE
WALLS



HOLOPLAST
MOVABLE WALLS

THE HOTCHKISS FACTORY,
COVENTRY. FACTORY
FLOOR SPACE CONVERTED
BY THE MINISTRY OF WORKS
INTO OFFICES.

FOR FACTORY OFFICES

6 reasons why you should use Holoplast Movable Walls

★ **SPACE SAVING**

"Holoplast" Movable Walls are one third the thickness of ordinary walls—this saves space and provides greater accommodation.

★ **MAINTENANCE**

"Holoplast" Walls have a hard and beautiful finish—last longer—are not easily damaged—maintenance costs are at least halved.

★ **TIME SAVING**

"Holoplast" Walls can be built TEN TIMES quicker than ordinary walls—permitting earlier occupation.

★ **BUSINESS DISLOCATION**

"Holoplast" Walls obviate disorganisation when alterations have to be made—no dirt, dust or noise.

★ **ALTERATION COSTS**

When alterations are made "Holoplast" costs next to nothing to take down, and all material can be used again.

★ **TAILOR-MADE FOR THE JOB**

No bills for extras—the price quoted for the whole perfect job is guaranteed.

HOLOPLAST

NO MATERIAL
LICENCES REQUIRED

Manufactured by **HOLOPLAST LTD.**

SALES OFFICE: 116 VICTORIA STREET, LONDON, S.W.1

Telephone: VICTORIA 9354/7 & 9981

HEAD OFFICE AND WORKS: NEW HYTHE, NEAR MAIDSTONE, KENT

135 Years of Engineering Progress



Mr. Boulton's Manufactory at Soho,
near Birmingham, circa 1781.

In 1772 James Watt and Matthew Boulton entered into partnership at Soho in Birmingham. There Watt perfected his steam engine and there also began the story of Hadens. George Haden served James Watt as foreman and apprenticed his son to the same employer early in the nineteenth century. In 1816 the younger George and his brother, with the blessing of the old firm, founded the engineering firm of G. & J. Haden at Trowbridge, Wiltshire. After 135 years under four generations, Hadens are more than ever prominent in the field of heating, ventilating and air conditioning.




G.N. HADEN 8 SONS L T D

19-29 WOBURN PLACE, LONDON, W.C.1. Phone: TERMINUS 2877


and Branches throughout the Provinces



Factory for Leyland Motors Limited in South Africa



School at Ruislip, Middlesex



King George V Merchant Seamen's Memorial Hospital, Malta




Flats at Hurlingham, Fulham

**Contractors for every class of Building and
Civil Engineering work at home and overseas**




*John Laing and Son Limited, Building and Civil Engineering
Contractors, London, NW7, Carlisle, Johannesburg and Lusaka.
Established in 1848*



Entrance Hall, Patons and Baldwins Limited, Darlington





B.B.C. Television Studios, Lime Grove




Club House at Esso Refinery, Fawley

IN THE TELEKINEMA STEREOPHONIC SOUND . . .



Two independent layers of **STILLITE** Kraft-covered quilt are used in the cavities between the inner and outer shells of the Telekinema, and **STILLITE 2" Semi-Rigid Slabs** are fitted as an acoustic facing to the inner walls. **STILLITE** is also used as a sound absorbent material in the auditorium seats.



The successful demonstration of stereophonic sound in the Telekinema at the South Bank Exhibition depends upon perfect listening conditions. In the Telekinema, as in the Concert Hall, Stillite Mineral Wool has been extensively used for both the exclusion of external noise and for the correction of the acoustics inside the auditorium.

Fireproof and easy to install, Stillite can be equally efficient in many other classes of building, both as a thermal insulant and an acoustic material. We shall be pleased to tell you how and why.



STILLITE PRODUCTS LIMITED
Dept. A. Sardinia House, Kingsway, London, W.C.2
Telephone: CHAncery 5146 Telegrams: Stillomite, Holb.




AUSTRALIA HOUSE

Foundation Stone laid by H.M. King George V, 24th July, 1913.

Officially opened by H.M. King George V, 3rd August, 1918.

Architects: A. Marshall MacKenzie & Son, F/R.I.B.A.




The BRITANNIC

FLOOR SPRING

*Specified by
Leading Architects*

WILLIAM NEWMAN & SONS Ltd
HOSPITAL STREET, BIRMINGHAM 19. Established over 200 years.



WRITE FOR LATEST DESIGNS

DAVID WHITEHEAD FABRICS

D. Whitehead Ltd., Higher Mill, Rawtenstall, Lancs. and New Burlington Street, London, W.1.



ONE OF THE DAVID WHITEHEAD GROUP



Closed

Open

The Car Control Panel




gearless lift

AT THE FESTIVAL OF BRITAIN


South Bank Exhibition

Hammond & Champness Ltd. have had the honour to be invited to exhibit one of their most up-to-date gearless lifts as an example of the latest and best in British lift design and construction. The complete lift is of standard design, modified only in minor detail for exhibition requirements.



The detector unit used for accurate levelling. The control circuit responds to impulses derived from this electronic valve and relay circuit.

The whole of this lift equipment is of British manufacture and conforms with the code of practice issued by the Building Industries National Council.



Hammond & Champness Ltd.

GNOME HOUSE, BLACKHORSE LANE, WALTHAMSTOW,

LONDON, E.17. Telephone : LARKSWOOD 1071.

During the day the lift is clearly visible as it travels within the transparent tower. By night, but more particularly from within the grounds, the car resembles an illuminated glass bubble, passing up and down.




Finished

AHEAD OF SCHEDULE

The contract for the fabrication and erection of the 'Dome of Discovery,' entrusted to the Horseley Organisation, was finished ahead of schedule. For over 180 years we have been engaged in large scale constructional engineering projects and contracts have been carried out in all parts of the world. Nevertheless we are particularly proud of our part in this project, symbolising, as it does, Britain's supremacy in the Engineering world.



THE LARGEST DOME IN THE WORLD




by **HORSELEY**

HORSELEY BRIDGE AND THOMAS PIGGOTT LTD
HORSELEY WORKS • TIPTON • STAFFS • PHONE 1104 P.B.X.
CARTER - HORSELEY (ENGINEERS) LTD
NEWCASTLE • PHONE JESMOND 1450 • WADDON • PHONE CROYDON 7226
LONDON OFFICES • 9 VICTORIA STREET • WESTMINSTER • PHONE ABBEY 5905

EDISWAN

Exterior Lighting for
THE FESTIVAL OF BRITAIN



EDISWAN
*are proud to make their
contribution to the Lighting Installation
for these sections of the
South Bank Exhibition*




BAILEY BRIDGE AND RIVER WALL
DOME OF DISCOVERY
LUXURY BAR · MAIN CONCOURSE
NORTH BANK ENTRANCE
PAVILION OF INDUSTRY · RESTAURANT
SEA AND SHIPS

THE EDISON SWAN ELECTRIC CO. LTD., 155 CHARING CROSS ROAD, LONDON, W.C.2

Member of the A.E.I. Group of Companies

L 121

Have you
a *knotty*
plumbing
problem....



Econa
can help you...

... or a difficult piece of internal drainage to deal with? Then pass it on to us (as early as possible) and we will disentangle it. In addition to making standard traps and fittings, we are also happy and willing to produce special jobs, for special purposes.

No architect need make his building fit the drainage. We can make the drainage fit the building. Starting from straight, smooth-bore copper tube, we can bend it or introduce branches into it—in almost any variety.

Plumbers, too, are glad to fit Econa products, because the compression joints for linking up various components make their work easier.


Econa traps and fittings are *all* made from smooth copper tubes

ECONA MODERN PRODUCTS LTD.

AQUA WORKS—WARWICK ROAD,
TYSELEY, BIRMINGHAM 11.

PHONE: ACocks Green 2211

ECONA TRAPS are specified by London C.C., Glasgow C.C., Hertfordshire C.C. and many other leading authorities.



Hemel Hempstead Primary School, Hertfordshire. County Architect : C. H. Aslin, Esq., F.R.I.B.A., M.I.Struct.E. One of a series of Primary and Secondary Schools envisaged in a 5-year building programme embracing single and two storey construction and using the flexible medium of Hills "Presweld" Components.

By specifying HILLS "PRESWELD" Components the architect is assured of complete freedom in architectural planning and design. The flexibility of this System is particularly evident in modern school construction where "Presweld" is being extensively used by County Authorities. Hills "PRESWELD" is suitable for most types of building, and offers considerable economies in materials, cost and man-hour erection time.

Based on the 8' 3" grid, buildings of almost any size of single, two and three storey construction can be completed from standard parts. As an integral part of the System, Hills supply Metal Windows, Door Frames, Gutters, Fascias and Hilcon lightweight Precast Reinforced Concrete Roof, Floor and Wall Units. Architects are invited to contact our Technical Sales Department for fuller information.

HILLS

(WEST BROMWICH) LTD

ALBION ROAD, WEST BROMWICH & 125 HIGH HOLBORN, LONDON, W.C.1

Telephone: WESt Bromwich 1025 (7 lines)

Telephone: HOLborn 8005-6

Branches at Birmingham, Swansea, Bristol, Manchester, Newcastle-on-Tyne, Glasgow and Belfast

Hilton

RENNIS LTD

Architectural Craftsmen

Our company was appointed by the Architects to design and produce Door Fittings and Decorative Metal-work in the following buildings at the South Bank Exhibition, the Festival Pleasure Gardens and the Exhibition of Architecture, Poplar.

SOUTH BANK EXHIBITION

The Dome of Discovery (Architect: Ralph Tubbs, Esq., A.R.I.B.A.)

The Shot Tower (Architect: Hugh M. Casson, Esq., M.A., F.R.I.B.A.)

Thames-side Restaurant (Architects: Fry, Drew & Partners, F/F.R.I.B.A.)

FESTIVAL PLEASURE GARDENS

The Amphitheatre, Pier Cafe, Dance Pavilion, Terrace Teashop
(Architects: Messrs. Kenneth Dalgliesh & Roger Pullen, F/F.R.I.B.A.)

Aviary Restaurant (Architects: Hugh M. Casson, Esq., M.A., F.R.I.B.A., in association
with Leslie Gooday, Esq., A.R.I.B.A., L.S.I.A.)

Riverside Restaurant (Architect: Basil Duckett, Esq., A.R.I.B.A.)


EXHIBITION OF ARCHITECTURE, POPLAR

Trinity Church, The Manse (Architects: Messrs. C. C. Handisyde & D. R. Stark, A/A.R.I.B.A.)

Ricardo Street Primary School, Ricardo Street Nursery School
(Architects: Messrs. Yorke, Rosenberg & Mardall, F/F.R.I.B.A.)

50-51, BEAUCHAMP PLACE, S.W.3. KENSINGTON 0126 (3 lines)

SUPERIOR
from every aspect



THE

Copperad
CONVECTOR

The architect's eye likes its attractive lines and beautiful finish. The engineer's brain approves its superior design and construction. The user appreciates the improved warmth and air movement.

The Copperad Convector is ideal for heating modern flats, houses, schools, offices, stores, and the like. It operates by steam, or low or high pressure hot water. Three types are available: Floor Mounting (as shown), Wall Mounting and Concealed.

Write for illustrated literature.

COPPERAD LTD.

LONDON OFFICE:

87 High Holborn, London, W.C.1.
Telephone: Holborn 0498-9

HEAD OFFICE & WORKS:

Colnbrook, Bucks.
Telephone: Colnbrook 203 (4 lines).
Telegrams: Copperad, Colnbrook.

**NORTHERN & SCOTTISH
OFFICE:**


30 Rutland Square, Edinburgh.
Telephone: Edinburgh 24067

Representatives at BELFAST, BRISTOL, DUBLIN, LEEDS, MANCHESTER, NOTTINGHAM AND WOLVERHAMPTON

FAULKNER GREENE & CO LTD

99-101 REDCROSS WAY, BOROUGH, S.E.1

Have now completed the Largest Plate Glazing Contract in the country, at the Royal Festival Hall. We executed the whole of the special glazing contained in this building, including all external windows glazed in $\frac{5}{8}$ " thick plate glass to provide sound insulation, all decorative internal glazing and mirrors.



THE ROYAL FESTIVAL HALL. Architect: Robert H. Matthew, Esq. A.R.I.B.A. and associated L.C.C. staff. Consulting Engineers: Scott & Wilson. Main Contractors: Holland & Hannen and Cubitts.

We are specialists in Patent Roof Glazing

MANUFACTURERS OF

"HERCULES" ALUMINIUM PATENT GLAZING

METAL WINDOWS · LANTERN LIGHTS · SKY LIGHTS

COPPER LIGHTS · LEADED LIGHTS

★ Send for a brochure illustrating our unique "Burglar Preventative" patent glazing.

Telephone: HOP 3811 (6 lines)

Telegrams: Herculites, Sedist, London.

Carved in Rock

The remains of the fabulous city of Petra near the Dead Sea display Greek architecture at its finest.



EDWARD
WOOD
& CO LTD

Built in Steel

This great block of flats and shops at St. Leonards-on-Sea displays a bold front in the modern manner, based on steelwork by Edward Wood & Co. Ltd.

C O N S T R U C T I O N A L E N G I N E E R S

Registered Office & Works: **MANCHESTER 17** Tel: TRAfford Park 2341 (10 lines)

London Office: 68 Victoria St., S.W.1. Tel: Victoria 1331/2. Technical Offices: BIRMINGHAM, LOUGHBOROUGH

dm VVU23



KEY TO THE SOUTH BANK EXHIBITION MODEL ILLUSTRATED ABOVE:

1. Chicheley Street Gate. 2. Information and Post Office. 3. Fairway Café. 4. Station Café, Escalator Hall for Underground below. 5. The Land of Britain. 6. The Natural Scene and the Country. 7. Minerals of the Island. 8. Power and Production. 9. The '51 Bar. 10. Sea and Ships. 11. Dome of Discovery. 12. Transport and Communications. 13. Regatta Restaurant, Embankment Gate. 14. The Skylon. 15. Landing Stage. 16. Administration Block. 17. The People of Britain. 18. The Lion and the Unicorn. 19. Unicorn Café. 20. Television. 21. Telekinema. 22. Locomotive Exhibit, Turntable Café below. 23. Police and First Aid. 24. Homes and Gardens. 25. Courtyard. 26. Administration, Staff Canteen. 27. Royal Festival Hall. 28. Seaside. 29. 1851 Centenary Pavilion. 30. Shot Tower. 31. Waterloo Bridge Gate, New Schools, and Design Review below. 32. Harbour Buffet. 33. Health. 34. Thames-side Cafeteria. 35. Sport. 36. Rodney Pier.

THOUSANDS OF YARDS OF ELECTRIC CABLES

WERE INSTALLED IN THE

Festival of Britain
South Bank Exhibition

by

TROUGHTON & YOUNG LTD.

USING

CRAIGPARK

EXTENSIVELY

ELECTRIC
CABLES


THE CRAIGPARK ELECTRIC CABLE CO. LTD., 19-21, Palace Street, London, S.W.1
REGISTERED OFFICE & WORKS—GLASGOW



BALANCED FLUE

AN OUTSTANDING ACHIEVEMENT IN THE DESIGN

A brilliantly designed multipoint gas water heater constructed on entirely new principles offering positive advantages . . . Vitiating of the air in the room is absolutely impossible, installation is simple, and appearance is pleasing.



The intake and exhaust ducts terminate behind the heater in a neat ventile flat on the exterior wall, as shown.


Ideal for multi-storied buildings as the ventile can be fitted regardless of overhanging projections.

ASCOT GAS WATER HEATERS LIMITED

WATER HEATERS

OF INSTANTANEOUS GAS WATER HEATERS

Combustion chamber and flue are sealed off from the room in which the heater is installed. Enclosed ducts draw air to burn the gas from outside the building and carry away all products of combustion. Heater can be installed in a cupboard.




The balanced flue water heater is exclusive to Ascot. The 715 has already been specified by many municipalities. A brochure containing full specification and showing various methods of installation will be sent on request.

43 PARK STREET LONDON W1 • GRO 4491

IDEAL - Standard

Foremost for heating and sanitary equipment



A No. 2-GBA and two No. 3-GBA Ideal Gas Boilers installed in a modern school

Where cleanliness is essential

To keep the atmosphere clean and healthy, the Ministry of Town and Country Planning and many local authorities are encouraging the use of heating equipment which will not pollute the air with smoke. In such a case, there can be no better selection than Ideal Gas Boilers, expressly designed to operate with extremely high efficiency on this fuel. Representing much

research and experience in this specialised type of heating, Ideal Gas Boilers are equipped with complete thermostatic controls, have insulated jackets of steel or aluminium in appropriate finishes, and are available in 22 sizes from 20,000 to 1,430,000 B.T.U. per hour.

An illustrated booklet giving full details is available on request.

IDEAL GAS BOILERS

EFFICIENT • RELIABLE • LABOUR SAVING

IDEAL - Standard
Foremost for heating and sanitary equipment

IDEAL BOILERS & RADIATORS LTD • IDEAL WORKS • HULL

157



PRESSURE PILING

means . . .

VIBRATION-FREE EFFICIENCY

Pressure Piling was adopted for the Foundation on a bomb-damaged site at Aldgate, and was sunk close to the adjoining structure without vibrations or damage to the property.


The leaders of pressure piling systems for over a quarter of a century.

THE PRESSURE PILING CO (NORTHERN) LTD 6 WINCKLEY SQUARE PRESTON LANCs TEL: PRESTON 5221

THE PRESSURE PILING CO (PARENT) LTD 637 OLD KENT RD LONDON SE15 TEL: NEW X 0347/8/9



STEELWORK



Boiler House structure at the Margam Works of the Steel Company of Wales Ltd.

Consulting Engineers: W. S. Atkins & Partners.


DAWNAYS LIMITED

BRIDGE AND STRUCTURAL ENGINEERS

HEAD OFFICE: STEELWORKS RD., LONDON, S.W.11: Telephone BATTERSEA 2535.

King's Dock Works SWANSEA 3185	East Moors Works CARDIFF 2557	54 Victoria St., London, S.W.1 VICTORIA 1541	Bridge Rd. Works WELWYN GDN. 242	Thorpe Works NORWICH
2 Rockstone Place SOUTHAMPTON 2474	40 Park Road PETERBOROUGH 4547	155 Princes Avenue, HULL HULL, CENTRAL 8161	22 High Street ROMFORD 2106	7 The Close NORWICH 23141

Cables and Telegrams "DAWNAYS, LONDON"—Code Bentley's 2nd.



Some indication of the scope and versatility of the Harris and Sheldon Organisation is apparent in the Power and Production Building, at the Festival of Britain South Bank Exhibition, where the Architectural Joinery, Metalwork and Decoration, Lighting and Furnishing were supplied and installed by Harris & Sheldon Ltd., to the design of Messrs. Warnett Kennedy and Associates, Architects and Design Consultants.

Full evidence of the Harris and Sheldon comprehensive service is reflected in many Public Buildings, Shops and Hotels, where the work has been entrusted to them by well-known Architects.

Complete Shopfitting
Furniture and Furnishings
Exhibition Design and Construction

Lighting Schemes and Electrical Contracting
Display Construction
Architectural Metalwork, Joinery and Decoration

L.G.B.

Harris and Sheldon Ltd. BIRMINGHAM • LONDON • MANCHESTER • GLASGOW



THE ROYAL FESTIVAL HALL

*Designed by Robert H. Matthew
Architect to the London County Council
and staff. Consulting Engineers, Scott
& Wilson. Main Contractors: Holland &
Hannen and Cubitts Ltd.*

*One of many surfaces in
Carter external tiles —
6"x6" external glazed tiling
in blue and oatmeal*

CARTER

CARTER & CO. LTD. POOLE, DORSET
CARTER & CO. LONDON LTD. 29 ALBERT EMBANKMENT, S.E.11
COMMERCIAL MARBLE & TILES LTD. NEWCASTLE-ON-TYNE
Associated Companies: Art Pavements & Decoration Ltd. Marbolith Flooring Co. Ltd.

*Telephone: POOLE 125
Telephone: RELIANCE 1471
Telephone: JESMOND 900
J. H. Barratt & Co. (1927) Ltd.*

THE CUBITT GROUP

AT THE SOUTH BANK

GENERAL CONTRACTORS:

*The Royal Festival Hall
Lion and Unicorn Pavilion
Unicorn Restaurant
Television Pavilion
Telekinema
Homes and Gardens Section
The Shot Tower
Seaside Section
Administrative Block*

CIVIL ENGINEERING CONTRACTORS:

*Site Works and Services
South Bank Exhibition
(Downstream section)*

SPECIALIST CONTRACTORS:

*Floodlighting, electrical
installations, water displays and
pumping, sanitary engineering,
ventilation systems*

DISPLAY CONTRACTORS:

*Lion and Unicorn Pavilion
Seaside Section
Homes and Gardens Section
(Parlour and Information Room)
Centenary Pavilion,
Boat House*

represented by

HOLLAND & HANNEN AND CUBITTS LTD.

Building Department
Structural Engineering Department
Civil Engineering Department
General Works Department
Joinery Department
Painting & Decorating Department
Co-Ordinated Services
Photographic Department
Psychromatics Department

ENGINEERING SERVICE INSTALLATIONS LTD.

Electrical Department
Sanitary Engineering Department
Heating & Ventilating Department

METALFORM LTD.

Industrial Department
Display Department

in association with

CONCRETE DEVELOPMENT CO. LTD.



HOLLAND & HANNEN AND CUBITTS LIMITED

Building & Civil Engineering Contractors


ONE QUEEN ANNE'S GATE WESTMINSTER SW 1

DOOR AND WINDOW IN ONE

A door is a window as well, when the potential customers of a shopkeeper can look straight through it into the showrooms or the shop beyond. This is the unchanging invitation given by large doors of sparkling, transparent "ARMOURPLATE" glass that swing back at a touch to admit customers. The door to the shop is no longer the barrier that it used to be a hundred years ago.



*Shops flanking the entrance to St. Bride's Avenue, Fleet Street.
From a drawing by Thomas R. Shepherd, published in 1829*



*Polished Plate Glass Windows and an "ARMOURPLATE" Glass door give unrestricted view of the interior of the Susan Bag Shop, Bond Street, London, W.1
Designer: W. Heumann, London, W.C.1*

Open up and brighten the
shop and its showrooms with
Pilkington's
"ARMOURPLATE"
Glass Doors


Consult the Technical Sales and Service Department at St. Helens, Lancs, or Selwyn House, Cleveland Row, St. James's, London, S.W.1.
Telephones: St. Helens 4001, Whitehall 5672-6.
Supplies are available through the usual trade channels.



PILKINGTON BROTHERS LIMITED, ST. HELENS, LANCS

"ARMOURPLATE" is the registered Trade Mark of Pilkington Brothers Ltd.

DOMES OF DISCOVERY SOUTH BANK EXHIBITION 1951



TYPICAL ARRANGEMENT OF THE 19 FRESH AIR UNITS
MOUNTED BETWEEN THE INNER AND OUTER WALLS

V E N T I L A T I O N

Comfortable conditions are ensured throughout the Dome of Discovery by the distribution of 10,000,000 cubic feet of fresh filtered air per hour

THE COMPLETE VENTILATING EQUIPMENT WAS DESIGNED AND INSTALLED BY


VIA-DUCT HEATING & VENTILATING CO. LTD.

EAGLE HOUSE, 110, JERMYN STREET, LONDON, S.W.1

ARCHITECT:—
RALPH TUBBS, A.R.I.B.A.

Telephone No.
TRAfalgar 5221 & 6114

VENTILATION CONSULTANT:—
HENRY G. GODDARD, F.R.I.B.A.



TAKE A LOG ... MAKE A BOARD ...

For the best board chop the best log, where the spruce trees grow. Carry to Kent, to Bowaters Kemsley Mills. Subject it to the most brutal of chemical and physical treatment and reduce to pulp; then synthesise by pressure into sheets.

From this simple sounding process are produced **LLOYD BOARDS**, grainless, knotless; and extra-resistant to the resentful climate of British cities. *Made in Medium, Standard and Super Hard, Building, Insulation and Bituminous grades.*



BOWATERS BUILDING BOARDS LIMITED

Harewood House, Hanover Square, London, W.1.

Tel.: May 9266

Issued by ASSOCIATED BOWATER INDUSTRIES LIMITED, a member of the Bowater Organisation

time

1951

and tide

The "Festival of Britain" presented both problems to the organisers. Time — relentlessly passing, placed the authorities with the problem of how to fulfil the vast first quality constructional requirements demanded by the 1951 prestige year and how best to deal with the vagaries of the Tide of the Thames as it lapped at the site of the proposed New South Embankment.

All points considered, resources — quality — reliability — speed — economy — a first-class Building and Civil Engineering Organisation completed the works ahead of schedule . . .


CONTRACTORS TO THE WORLD

Richard
COSTAIN
Limited

HEAD OFFICE: DOLPHIN SQUARE • LONDON • S.W.1 • Victoria 6624
BRANCHES: TURKEY • MIDDLE EAST • RHODESIA • UGANDA • NIGERIA

HARDWOOD FLOORS
last a lifetime

HARDWOODS
for
texture
colour
pattern



Sapele (*Entandrophragma Cylindricum*)

Hardwood floors are back again, in a bigger variety than ever before. You can choose, not only from Oak, Beech, Maple, Teak and the other traditional flooring timbers, but from many additional woods from newly developed African forests. The names may be unfamiliar but in variety of texture, colour and pattern they are unsurpassed for decoration, dignity and durability.

The square basket block floor illustrated is in Sapele ; a West African timber, close in texture, with a regular stripe. It darkens to a rich brown — with a pleasing figure. It is harder and heavier than African Mahogany, and indeed is almost as hard as Oak. Sapele works well. It is suitable for all floors with the exception of heavy duty.



**THE HARDWOOD FLOORING
MANUFACTURERS' ASSOCIATION**


14, New Bridge Street, London, E.C.4 Telephone: City 1476-7

**ASSOCIATION OF
FLOORING CONTRACTORS**

69, Cannon Street, London, E.C.4 Telephone: City 2513-4444

M.A. 3689

TAYCO



CHOSEN FOR EXHIBITION AT
THE FESTIVAL OF BRITAIN

MADE IN 7 CAPACITIES FROM
21,000 TO 80,000 B.T.U.s.

New Series
DOMESTIC BOILERS

Particulars on Request to :—

ROBERT TAYLOR & Co. (Ironfounders) LTD.

Muirhall Foundry

Larbert


Stirlingshire

London Office and Showrooms - 66 Victoria Street, S.W.1

Also at Building Centre, 9 Conduit Street, W.1

KIRK & KIRK LTD.

BUILDING & CIVIL ENGINEERING CONTRACTORS



Post-Tensioned Concrete Bridge, Waterloo Bridge Main Entrance and Viewing Tower.

Architects : FRY, DREW & PARTNERS, F/R.I.B.A.

Consulting Engineers : FREEMAN, FOX & PARTNERS ; R. T. JAMES & PARTNERS ;
OVE ARUP & PARTNERS

CONTRACTORS TO THE FESTIVAL OF BRITAIN


Work comprises :—

WATERLOO BRIDGE MAIN ENTRANCE • VIEWING
TOWER • HARBOUR BAR • RIVERSIDE RESTAURANT
POST-TENSIONED CONCRETE FOOTBRIDGE TO
CONCERT HALL • SPORTS AND OPEN AIR EXHIBITION
NURSERY SCHOOL EXHIBITION, ETC., ETC.

ATLAS WORKS, PUTNEY, LONDON, S.W.15

Telephone : PUTNEY 7244 (10 lines)

Telegrams : FOURKAYS, WESPHONE, LONDON



SOME FESTIVAL OF BRITAIN BLINDS

By "BRITAIN'S LEADING BLINDMAKERS"

J. AVERY & CO. (EST. 1834) LTD. 81 Great Portland Street, LONDON W.1. **MAKERS OF EVERY KIND OF BLIND**

CREATION WITH CRAFTSMANSHIP



A section of the new Ladies Powder Room at Messrs. Selfridges Limited, London, W.1.
Executed by Courtney, Pope Limited under the supervision of the House Architect,
R. L. Heath, L.R.I.B.A.

THE ASSOCIATED COMPANIES OF
COURTNEY, POPE

COURTNEY, POPE LTD. Store Fitting, Architectural Joinery and Metalwork.

COURTNEY, POPE (ELECTRICAL) LTD. Lighting Specialists.

AMHURST PARK WORKS, TOTTENHAM, LONDON, N.15 STAMFORD HILL 4266 (TEN LINES)

ROYAL FESTIVAL HALL

DERBYDENE AND HADENE

DERBYSHIRE MARBLE
WALL LINING AND PAVING

QUARRIED BY

DENE QUARRIES

(DERBYSHIRE) LIMITED.



BY COURTESY OF THE ARCHITECTURAL REVIEW

SOLE AGENTS


NINE ELMS STONEMASONRY WORKS
112, THESSALY ROAD, BATTERSEA, S.W.8.

For Elegance, Smoothness & Reliability



ESTATE SLIDING DOOR GEAR

An exclusive "snap-on" pelmet conceals all fittings and will harmonize with picture rail or panelled effect. ESTATE gear is approved by the L.C.C. and is stocked by hardware firms throughout the British Isles and in many countries overseas. Supplies are readily available from your local merchants.



For really pleasing appearance, maximum space economy, swift gliding action, and long life, always specify ESTATE Sliding Door Gear. Consider how easily a lounge can be enlarged to include an adjacent dining room. Again, how convenient it is to enclose a small area for heat and light economy or to provide immediate and intimate seclusion. There are many other advantages which will readily occur to planners who are interested in a high quality product at a keen competitive price. All such purposes are fully covered by the range of ESTATE Sliding Door Gear. Many housing estates throughout the country are using ESTATE Sliding Door Gear.

Please write for descriptive literature and erection data.

CLARKE ELLARD ENGINEERING CO. LTD.
Works Road, Letchworth, Herts. Tel: 979

SEE OUR EXHIBITS AT THE BUILDING CENTRE, 9, CONDUIT STREET, LONDON, W.1
& THE SCOTTISH BUILDING CENTRE, 425-427, SAUCHIEHALL STREET, GLASGOW, C.2



STAFF RESTAURANT,
BRITISH HOME STORES LTD., MARYLEBONE HOUSE.
ARCHITECT, GORDON JEEVES, F.R.I.B.A.

ARCHITECTURAL & SHIP —
— DECORATION
JOINERY & CABINETMAKING
FIBROUS PLASTER
PAINTING & GRAINING
UPHOLSTERY &—
FURNISHINGS
LIGHTING

FACTORIES

62-64 MATILDA ST., CALEDONIAN RD., LONDON, N.I.
and at—
843 HARROW ROAD, LONDON, N.W.10.



BY APPOINTMENT
DECORATIVE ARTISTS TO
THE LATE
KING GEORGE V



BY APPOINTMENT
DECORATIVE ARTISTS TO
H.M. QUEEN MARY



BRASSERIE RESTAURANT,
CAFÉ ROYAL, REGENT STREET, W.1.
ARCHITECTS, MESSRS. HENRY TANNER.

★
**WHITE
ALLOM** LTD.



IMPERIAL FORESTRY INSTITUTE, OXFORD


Thomas Worthington & Sons, Architects

HOPE'S WINDOWS

HENRY HOPE & SONS LTD
SMETHWICK, BIRMINGHAM AND 17 BERNERS STREET, LONDON, W.1




MELLOWES reflections at the FESTIVAL



We are proud to illustrate one of our contributions to the Festival of Britain in the aluminium entrance screen for the Power and Production Pavilion at the South Bank Exhibition. The striking upper reflection of the Skylon and Dome of Discovery is factual, and whilst the lower one is in one sense equally so—seeing that we provided Patent Glazing for the Crystal Palace—the reflection is nevertheless a figment of our imagination, caused by our mental associations with the past.



MELLOWES & COMPANY LIMITED
LONDON SHEFFIELD OLDHAM



Design for a floor in a Hospital Ward · From the original Collage by R. MYERSCOUGH-WALKER

In Hospitals, and all places where cleanliness is of first importance, Marley Floor Tiles provide the ideal flooring. They are quiet, non-slippery, resilient, durable, hygienic, waterproof and easy to clean. The wide range of colours permits the carrying out of colour schemes previously impracticable in Hospital work.



*Cock o'
the walk*

The Marley Tile Co. Ltd., London Rd., Riverhead, Sevenoaks, Kent. Sevenoaks 2251-6

MARLEY



ROYAL FESTIVAL HALL



Gaskell & Chambers Ltd. have manufactured and installed to the design of the L.C.C. five bars and two dispense bars in the Royal Festival Hall. Bars in addition have been installed in the Press Room, the Regatta Beer Garden, Turntable Cafeteria, all on the South Bank site, also all bars in the three taverns in Battersea Park Beer Garden. Every item of beer-raising equipment throughout the Festival has been supplied by Gaskell & Chambers Ltd.




BRITAIN'S BIGGEST BAR FITTERS


● Head Office: Dalex Works, Coleshill Street, Birmingham, 4.

● London Office: 109-115 Blackfriars Road, S.E.1.


● Branches: Bristol, Cardiff, Leeds, Portsmouth, Manchester, Liverpool, Preston, Newcastle-on-Tyne, Hanley, Sheffield, Nottingham, Glasgow, Edinburgh.



The Aquadale fully Automatic Dish Washer.




21" Wide Sinks with Double Bowls, Drainers and Tapholes.



18" Wide Sinks with Single Drainer—Reversible.

SETTING the highest standard in attractive, modern kitchen equipment, the "DALE" series of Kitchen Cabinets and Sinks makes an immediate appeal to every houseproud woman. Beneath the sleek attractive exterior of each cabinet—admirably finished in white or green hard-cream stove enamel, which will neither peel nor crack—lies a dustproof, rustproof construction of Pyluninised Aluminium and Steel. Full details of PAUL Kitchen Equipment are given in our latest illustrated leaflet. *May we send you a copy?*

Our Showrooms at No. 7 Royal Arcade, Old Bond Street, London, W.1, where a range of PAUL Kitchen Equipment can be seen and enquiries answered.



W·H·PAUL LTD BREASTON, DERBY

A visual shopfront designed to reveal the interior and encourage a desire to enter by removing the mystery and seclusion of the unseen. The shopfront is a glass screen containing display frames without window backs and the door is frameless glass set in glass wing pieces. Spot lamps, flush with the ceiling, provide the main interior lighting, while the window display frames contain fluorescent tubes fitted with "egg crate" diffusers. The display lighting is of a higher density than the general shop illumination. Tan coloured carpet covers the floor and the cases and counters are French polished teak and betula. The general construction of this extremely attractive shop is in the usual high quality associated with Pollard craftsmanship.

SHOPS



BY POLLARDS



fior

Burlington Gardens
London, W.1

Architect:
Werner Heumann

E. Pollard & Company Ltd

159 St. John Street, London, E.C.1

Telephone : CLerkenwell 6701

Showrooms: 299 Oxford St., London, W.1

Rowe



PRESSED METAL PARTITIONING

Norton Street Bakeries, Birmingham.

Architect

A. O. Chaterley, Esq., B.Arch., F.R.I.B.A.

SANITARY INSTALLATIONS

Hateley Heath Infants' School.

Architect

H. Schofield, Esq., B.Sc.(Eng.), A.M.Inst.
C.E., Borough Engineer and Surveyor,
County Borough of West Bromwich.



CATERING EQUIPMENT PLANNING

Civic Restaurant,
Birmingham.

Architect

W. N. Twist, Esq., F.R.I.B.A.

SERVICE TO ARCHITECTS

You are invited to consult the Rowe Organisation who will be pleased to place at your disposal a complete Architectural Service. This Service, maintained by a fully qualified technical staff, embraces all problems associated with the provision of equipment for specialised installations, assistance with layouts and plans, and can be combined with the Rowe Site Service, which maintains close liaison with Clerks of Works and Contractors on the site, to secure all sizes and details and ensure correct delivery of goods as required. The illustrations show typical installations provided by these Services, and also one section of one of our Branch Showrooms which display a comprehensive range of building components.



SHOWROOMS
AND COMPLETE
ADVISORY
SERVICE

Rowe BROS. & CO. LTD.

LIVERPOOL: Pall Mall. Central 5401

BRISTOL: Victoria St. Bristol 23171

LONDON: 10 Dover St. W.I. Regent 5761-2

BIRMINGHAM: Berkley St. Midland 2791

EXETER: Queen St. Exeter 4134

BLACKPOOL: 54 Coronation St. Blackpool 22341

Take your seats, please....



Whether you are playing the tuba in a Festival Concert or just dying for an excuse to rest your poor feet you will find Kingfisher ready and willing to oblige. Kingfisher furniture is all over the Exhibition—the Schools Section, Homes and Gardens, Thames-side Restaurant, Harbour Bar and Royal Festival Hall.



Kingfisher

TUBULAR FURNITURE




Kingfisher Stacking Chairs, arm-chairs and tables are in the Royal Festival Hall orchestra, auditorium, foyers and restaurant (Design by Robin Day, A.R.C.A., F.A.I.A.)

Kingfisher Metal & Wood Furniture in the Thames-side Restaurant (Design by Neville & Mary Ward, A.A.R.I.B.A., M.S.I.A. and Frank Austin, M.S.I.A.)



KINGFISHER LTD., Charles Street and Phoenix Street, West Bromwich, Staffs.

Telephone : Tipton 1631. Telegrams : Kingfisher Phone West Bromwich. London : 139, Knightsbridge, S.W.1. Telephone : Kensington 1331.



Heating the Royal Festival Hall

The heating and ventilating system comprises full air-conditioning in the auditorium, and plenum ventilation with supplementary heating in various other parts of the building.

Gas boilers were chosen as being most suitable, particularly for the quick, automatic regulation of heat input provided. The estimated total load of the gas boiler plant is 33 million B.Th.U.; amongst gas fired installations it is one of the largest and probably the most efficient in the country.

Further information on the gas installation at the Royal Festival Hall may be obtained by writing to The Gas Council.

Helpful information on the many aspects of providing efficient services for cooking, hot water, space heating and refrigeration may be obtained from local Gas Undertakings.

GAS

ISSUED BY THE GAS COUNCIL · 1 GROSVENOR PLACE · S.W.1 · TELEPHONE SLOANE 4554

NEW FASHIONED
—yet as old as time!

The all-over pattern behind these words gives the clue to their meaning. It is a photograph of the latest Chance glass, *FESTIVAL* — a design with an age-old inspiration, for it comes from the molecular structure of a mineral called apophyllite.

Why apophyllite? As members of the Festival of Britain Pattern Group, Chance Brothers accepted the invitation to create an entirely new pattern on just such a basis, and this is the outcome, with the help of designer J. Beresford Evans and the Council of Industrial Design.

You can see the new *FESTIVAL* glass in the Pattern Group displays at the Land Travel Exhibition and at the Regatta Restaurant on the South Bank. You will also find it in use in the Regatta Restaurant, in the structure of the Beer Garden in Battersea Park and in the Science exhibit at South Kensington.

You will be able to judge its true contemporary feeling, its excellent obscuration. *FESTIVAL*, moreover, is a practical design in every way — easy to fit (adjacent panes need not be matched) and easy to keep clean. There is going to be a big demand for

Chance FESTIVAL glass

Chance

GLASS
For Science, Industry and the Home

CHANCE BROTHERS LIMITED, GLASSMAKERS SINCE 1824.

Head Office: Glass Works, Smethwick 40, Birmingham. Telephone: West Bromwich 1051. London Office: 28 St. James's Square, London, S.W.1. Telephone: Whitehall 6002. Branch Works at Glasgow, St. Helen, and Malvern.

SPECIAL ISSUE ON THE

SOUTH BANK EXHIBITION



The Cover The South Bank exhibition may be regarded as the first modern townscape, not only by virtue of the fact that its buildings and furnishings are designed in the contemporary idiom throughout, but equally because its layout represents that realization in urban terms of the principles of the Picturesque in which the future of town planning as a visual art assuredly lies. One of the most successful features of the exhibition seen from this point of view is the way in which existing buildings lying outside the boundaries of the site have been brought into the picture: practical recognition is thus given to a truth which town planning theory is too apt to overlook—that in the modern world the town planner's job is as much the re-creation of the old (through the establishment of new relationships between it and the spectator) as the creation of what is physically new. The cover, with a diorama showing the Houses of Parliament, Whitehall Court and St. Paul's superimposed on a plan of the exhibition, emphasizes this significant aspect of the South Bank achievement. It was designed by Gordon Cullen and D. Dewar Mills.

72 Frontispiece

73 Foreword Conceived at a moment that seemed anything but propitious for holding a great exhibition, the South Bank exhibition, on its central London site, has triumphantly demonstrated the vitality of contemporary British architecture and should have a world-wide influence. Most of the exhibitions of the past have served as a nursery of new architectural ideas. The South Bank exhibition goes beyond them by also introducing a new standard of planning. It is a

Editors
J. M. Richards
Nikolaus Pevsner
Ian McCallum
H. de C. Hastings

Assistant

Editors: production, G. Bensusan.
art, Gordon Cullen. research, S. Lang. literary, Marcus Whiffen.
Editorial Secretary, Whitehall 0611-19

Volume 440 Number 656 August 1954

revolutionary departure from the Beaux Arts tradition on which the planning of the major exhibitions of the past has invariably been based. But while the planning of the South Bank is revolutionary so far as exhibitions are concerned, the principles underlying it are by no means new. They are in fact neither more nor less than those of the Picturesque landscape of the English eighteenth century, whose translation into urban terms the REVIEW has been urging over a period of years. The REVIEW is thus able to hail the South Bank exhibition as the first modern townscape and the present special issue has been designed primarily to illustrate this aspect of it, and to show the bearing that the lessons to be learnt from it have on the contemporary (and future) urban scene.

80 The Exhibition as Landscape This section, which takes the form of an illustrated tour of the exhibition, discusses and analyses the broader visual effects resulting from the application of the principles of the Picturesque to the layout of the South Bank. The skilful incorporation of already existing buildings into the scene, the use of water to provide an invisible but effective barrier, carefully contrived alternations of concealment and disclosure, studied changes of level and of surface, contrasts between apparent enclosure and sudden glimpses of far distance—all these are devices which may be paralleled in eighteenth-century landscape practice but which, as their use on the South Bank shows, have a new applicability today, not only for exhibition design but for permanent town building.

107 The Exhibition as a Town Builder's Pattern Book The total effect of any townscape depends to a much larger degree than is generally appreciated on the quality of its incidental details—on the design of pavements, railings, steps, street furniture and so on. A special virtue of the South Bank exhibition is that the details of this kind maintain a remarkably high standard. On these pages the camera has made a collection of those which provide the best precedents for future use—the nucleus of a town builder's pattern book.

123 The Exhibition Buildings by J. M. Richards In this section the exhibition buildings on the South Bank are illustrated and discussed as individual examples of

architecture. Taken together they represent the largest display of modern architecture to which the British public has been treated, while from another point of view they provide a fair test of the abilities of the younger generation of British architects. Several of them are the first major works of the architects responsible for them. Most attention is here given to those buildings which are least fully illustrated elsewhere in the issue, and the general views should therefore be studied in conjunction with the details appearing in other sections, to which cross-references are given in the captions.

135 South Bank Translated by Gordon Cullen The Royal Festival Hall is at present the only permanent building on the South Bank site. In time, after the exhibition has gone, it is to be joined by a National Theatre, government offices, an hotel, and other buildings. The planning principles of which the South Bank exhibition is so triumphant a justification must not be forgotten when the permanent development of the area is undertaken. Here Gordon Cullen presents his plan for it. In its main lines, and more particularly its main divisions, this plan follows that of the exhibition; it also conforms to the general proposals of the County of London Plan.

139 Anthology

139 Marginalia

142 Exhibitions

144 Trade Notes

146 Contractors, etc.

148 Acknowledgments

The Architects Biographies and photographs of the many architects who were engaged on the South Bank exhibition appear in Marginalia on page 139.

price of the Review The steadily increasing costs of production, especially the recent fantastic rise in the price of paper which has gone up by anything from 60 per cent. to 100 per cent. (varying with the type of paper) during the last few months, have made it necessary to increase the selling-price of THE ARCHITECTURAL REVIEW. As from last month the price is 5s. a copy, and the annual subscription is £2 18s. 0d. including postage. Price in USA and Canada \$9 per annum.

THE ARCHITECTURAL REVIEW

9-13 Queen Anne's Gate, Westminster, SW 1 • Whitehall 0611

FIVE SHILLINGS



1, the exhibition at night, looking down the main concourse from one of the riverside terraces. Left, the transport building; centre, Station Gate; right, entrance to the Land of Britain with the York Road screen beyond.

FOREWORD

The Festival of Britain was conceived at a moment when the temperature chart of British history, which throughout recorded time has fluctuated violently between fever heat and absolute zero, could be seen by the whole world to register several degrees below normal. There was no reason—no excuse even—for holding another Great Exhibition, except those provided by memories of the Prince Consort's courage and enterprise a hundred years before and Paxton's engineering genius.

Building on these flimsy foundations, Sir Gerald Barry's vision and Herbert Morrison's faith and pertinacity have nevertheless managed to confront an austerity-ridden people with an exhibition which forcefully reminds them of their traditional ability to make the big gesture effectively whenever they give themselves the chance. They have conjured it up on a, literally, heaven-sent site on the South Bank of the Thames in the middle of London, which their team of designers, led by Hugh Casson, have translated into a triumphant demonstration of the vitality of contemporary British architecture.


In accordance with the criteria by which most things are nowadays judged, the success or otherwise of this brave enterprise will no doubt be measured for political purposes in terms of crowds clicking through the turnstiles or the stimulus given to our export trade, but architects have a more reliable criterion: the physical structure of the exhibition itself. Judged by what is to be seen on the South Bank, 1951 shows every sign of achieving the inconceivable and proving itself the peer of 1851, from the success of which stemmed much of Britain's prestige during a hundred years and her reputation for vision and initiative.

It is clear to all those who have followed the development of the modern movement in architecture, and who comprehend the ideas for the future still only implicit in it, that at the South Bank exhibition we have not only a major architectural event but a work of art which—like the Crystal Palace before it—has potential world-wide influence.


Like the Great Exhibition of 1851, whose centenary it worthily celebrates, it is in its own way a pioneer. The earliest exhibitions asserted the architectural respectability of engineering, and culminated in Paris 1889, when Gustave Eiffel gave the world his famous tower. The exhibitions which followed contributed first of all new non-antiquarian styles of decoration (*art nouveau* was propagated in Paris 1900 and jazz-modern in Paris 1925) and then a new non-antiquarian style of architecture. Stockholm 1930, designed by Gunnar Asplund, for the first time showed modern architecture on a scale that allowed visitors to feel they were entering a world belonging to their own time. Subsequent exhibitions contributed ideas about the modern use of various materials—for example, timber in Aalto's Finnish pavilions at Paris 1937, and New York 1939. They also established the modern style of display design (landmarks are the Polish and Swiss pavilions at Paris 1937 and Misha Black's first large-scale displays at Glasgow 1938).

But the *planning* of all these exhibitions was, on the whole, orthodox. It was based on the axial avenue, the cross avenue, the *rond-point* and the vista—in fact on the *Beaux Arts* tradition, which was at its height when the first great exhibition not contained (like

Though the great exhibitions have done much pioneer work in the fields of engineering, architecture and display, their planning has remained almost wholly conventional. Except for the rather more freely planned exhibitions at Stockholm in 1930 and Zurich in 1939, every important exhibition has hitherto been laid out on monumental Beaux Arts lines, which the South Bank, with its informal landscaping, has completely abandoned. On the right are the plans of four famous exhibitions: the first great Paris exhibition of 1867, that of 1889, on the plan of which all the subsequent Paris exhibitions have been based, Glasgow 1938, the first British exhibition to make use of modern ideas in architecture, and the 1939 New York World Fair, at which the conscientious modernity of the architecture consorted particularly oddly with the formal, axial plan.



Paris, 1867



Paris, 1889


the Hyde Park exhibition of 1851) in a single building was laid out in Paris in 1867. The achievement of the South Bank 1951 is that it presents a complete departure from this tradition. It is planned in an informal style, much better suited to exhibitions than the geometrical style, since it does not exclude the elements of expectation and surprise and gives opportunity for contrast and variety of scale; and it is more useful for trying out planning ideas for permanent use elsewhere, since the geometrical style is seldom suitable for modern towns with their emphasis on multiple use and their need to allow for slow organic growth.

The South Bank exhibition thus fills the traditional exhibition role of nursery of new ideas in a particularly timely fashion, since the problems presented to its designers, especially the small size of the site, reflected many of the problems that constantly confront architects and planners in this overcrowded island: how to give a feeling of space while economizing in the use of space; how to achieve a compact urban character while avoiding congestion—visual and actual; how to weld the ideas of many architects into a whole without stifling originality or imposing uniformity; how to marry the new with the old so that one does not harm the other but, on the contrary, so that the qualities of each enhance the other.

These problems occur with special frequency in that most difficult but at the same time most exciting of all post-war architectural tasks, the building of the new towns. In fact the South Bank exhibition can itself be regarded as a new town. It is a temporary town (or, more precisely, the non-residential quarter of a town) deposited on the banks of the Thames where all can learn the lessons it contains and appreciate the ideas it contributes.

But though the planning of the South Bank is revolutionary so far as exhibitions are concerned, the planning principle it represents is by no means new. It is only new in its urban application. It is well known in landscape planning and was the basis of the Picturesque theory of landscaping which British gardeners developed in the eighteenth century. This theory, now recognized as one of Britain's major contributions to European art, demanded that the latent possibilities of any site should be exploited to the full in order to produce a layout with a character peculiar to that site alone. It thus opposed the renaissance theory of superimposing a new character by the use of rigid geometrical forms. The Picturesque landscape was as irregular, as rich in surprises, as skilful in the use of the happy accident as nature herself. Indeed as far as England is concerned it re-created nature herself; for what are often taken for the natural beauties of the typical English countryside are in fact synthetic beauties largely derived from the Picturesque improvements of the eighteenth century.

English towns, unfortunately, had the benefit of no such improvements. When they



Glasgow, 1938




New York, 1939

outgrew the formality of the Georgian market square, their further growth took the form of a series of accidents, without any understood principles to turn them into happy accidents. In our highly urbanized civilization there is a clear need to add to the codes of hygienic and traffic engineering practice by which the shape of our towns is already controlled to some degree, an equivalent visual code of practice, if only to prevent all our towns becoming identical waves in an endless sea of bricks and mortar.

The plea has been made in *THE ARCHITECTURAL REVIEW*,* and elsewhere, that this could be achieved if town-planners adopted a modern version of the Picturesque principles that were applied so successfully by country planners in the past. It has been suggested as a theory, but there has been but little opportunity of putting it into practice. At last an opportunity was offered by the South Bank exhibition site, where the Picturesque theory has been followed with triumphant results. That is the great contribution of the exhibition to contemporary architecture; it demonstrates how successfully the informal principle of town-planning, so well rooted in the English countryside, can be transplanted to the English urban landscape. It shows what rewards we may expect if we apply the same principles to the tasks with which our town builders are confronted today, especially the construction of new towns and the reconstruction of obsolete city centres.

Stand in the centre of the main concourse at the South Bank exhibition. Except for the difference that the architecture, being exhibition architecture, shows certain legitimate exaggerations of style and tricks of display which would not appear in permanent buildings, you might be in the main square of a modern town—but not a town that endeavours to exclude the humdrum world around and about it, of which it must always remain a part. At the end of the concourse is the River Thames, and beyond it the buildings of an older London. These are neither apologized for nor ignored in the planning of this foretaste of a new London. They are skilfully woven into the scene, so that historic and modern architecture serve as back-



2


* *Exterior Furnishing or Sharawadgi: The Art of Making Urban Landscape*, by the Editor, Jan. 1944; *The Second Half Century*, by the Editors, Jan. 1947; *Hazards of the Art of Introducing Obstacles into the Urban Landscape Without Inhibiting the Eye*, March, 1948; *Townscape: A Plea for an English Philosophy Founded on the Fine Rock of Sir Uvedale Price*, by I. de Wolfe, Dec. 1949.


No exhibitions have had a greater influence on architecture than the series held between 1867 and 1937 on the Champ de Mars, Paris. Their formal style of planning, however, has not changed since the Eiffel Tower was erected as a climax to the main axis in 1889. 2, an aerial view of that exhibition on which the plans of subsequent Paris exhibitions were based.

key

1. administrative offices.
2. royal pavilion.
3. Chicheley Street entrance.
4. information, lost property, etc.
5. Fairway cafe
6. Waterloo Station entrance (including Rocket restaurant): Sir John Burnes, Tais and Partners.
7. Land of Britain: H. T. Cadbury-Brown.
8. Countryside: Brian O'Rourke.
9. Minerals: Architects' Co-operative Partnership.
10. Power and Production: Grenfell Baines and H. J. Reifenberg.
11. '51 bar: Leonard Manasseh.
12. Sea and Ships: Basil Spence and Partners.
13. Skylon: Powell and Moya.
14. Dome of Discovery: Ralph Tubbs.
15. Transport: Arcon.
16. Turntable cafe: H. T. Cadbury-Brown (with George Sublotto and Terence Bliss).
17. People of Britain: H. T. Cadbury-Brown.
18. Television.
19. Telekinema.
20. Lion and Unicorn.
21. Unicorn cafe.
22. Introduction to Homes and Gardens: original design by Denis Clarke-Hall; executive architects Bronck Katz and Reginald Vaughan.
23. Homes and Gardens.
24. Garden cafe.
25. administration building: Edward Mills.
26. Waterloo entrance: Fry, Drew and Partners.
27. Royal Festival Hall: Robert Matthew, architect to the London County Council (with J. L. Martin, Edwin Williams and Peter Morol).
28. 1851 Centenary pavilion: Hugh Casson.
29. old shot-tower.
30. boat-house.
31. Harbour bar.
32. Thames-side restaurant.
33. Sport: Gordon and Ursula Bowyer.
34. Seaside: Eric Brown and Peter Chamberlain.
35. Regatta restaurant: Misha Black and Alexander Gibson.

Architects'
Co-operative
Partnership.






ground and foreground respectively in a succession of cunningly contrived compositions. Here is the first example of Picturesque planning translated into urban terms. The existing buildings around the site, with their varying scales and silhouettes, take the place of the existing natural features on which the eighteenth-century landscapists based their designs. The Palace of Westminster and Whitehall Court are the rock-strewn hill and the well-placed clump of trees towards which the spectator's eye was subtly directed and against which artificial features in the foreground were set. The Thames is the natural lake, tamed to serve the landscape gardener's purpose. And in the arrangement of the exhibition buildings themselves is the same carefully contrived alternation of concealments and disclosures that gave the eighteenth-century picturesque landscape its elusive charm.

If the great triumph of the exhibition is its general layout, contrived with so much imagination by Hugh Casson and his colleagues on the Presentation Panel, special credit must also go to H. T. Cadbury-Brown for his detailed landscaping of the main upstream area, to Peter Shephard for landscaping and garden design downstream, and to the many architects who have made brilliant use of the many other devices traditional to the landscape designer: water to provide an invisible but effective barrier; changes of surface underfoot to point the difference between a courtyard and a thoroughfare; changes of level; contrasts between apparent enclosure and a sudden glimpse of far distance. To these are added equivalent devices applicable only in an urban context. All are contrived for the benefit of the moving, not the stationary, spectator.


It is obviously impossible, even by devoting a whole issue of the REVIEW to illustrating the exhibition, to record everything of note in it, representing as it does the work of some dozens of architects over a couple of years. It has therefore been thought best, in this special issue, to concentrate on those aspects of the exhibition that have most to contribute to the progress of modern architecture and town-planning. These, in the opinion of the Editors, as the observations above explain, lie within the province of landscape planning. This issue therefore begins with a tour in photographs and drawings in which the points of three-dimensional planning are illustrated, and further analysed in a running commentary.

But the lessons contemporary planners can learn from the exhibition are not confined to broad questions of layout and landscaping. In the long run




3


Exhibitions as testing grounds for new ideas. 3, Stockholm 1930, by Gunnar Asplund, Europe's first large-scale display of modern architecture. 4, Aalto's Finnish pavilion in Paris, 1937, which had a profound influence on the use of timber by modern architects. 5, inside the Polish pavilion at the same exhibition, first evidence of a new style in interior design. 6, one of Misha Black's displays at Glasgow 1938, establishing a style that was to dominate exhibition design for many years.



4



5



6

the quality of a planner's efforts depends just as much on the way his principles are put into practice, on neatness of finish and character of detail. In this respect, too, the South Bank exhibition sets a remarkably high standard and is rich in lessons for the city architect and municipal engineer. The second section of this issue therefore takes the form of a pattern-book in which aptly designed details are collected together from all parts of the exhibition under various headings, chosen to indicate either the problems well-thought-out details can help to solve (such as how to guide pedestrians in the right direction without unsightly railings) or the actual objects that most need the designer's attention (such as lettering and street furniture).

The architecture of the exhibition buildings must also be put on record, so that its influence can remain after they have been cleared away, and a third section of the issue briefly illustrates the principal buildings with plans and exterior and interior photographs. But though the buildings are temporary, they are to be followed by some form of permanent building development. So successful are some of the ideas that have been tried out on the South Bank that a strong case can be made out for incorporating them in the permanent development of the area. In a final section of the issue Gordon Cullen makes his own choice of the exhibition features he would like to see preserved and depicts them in a possible future permanent setting. Charity begins at home, and if the South Bank exhibition of 1951 is to go down in history, as seems likely, as the fountain-head of a new style of urban development, it will be appropriate if some of its lessons are applied to the task of giving new dignity and vitality on a permanent basis to the part of London it at present occupies.

In apportioning credit among the many designers responsible for the outstanding qualities of the exhibition as outlined above, mention must first of course be made of those members of the Presentation Panel who controlled both architecture and display from the beginning under the chairmanship of Gerald Barry, director-general of the Festival. They were Hugh Casson, director of architecture to the Festival, Misha Black, James Gardner, James Holland and Ralph Tubbs.

They worked under the general guidance of the Council for Architecture, Town Planning and Building Research, one of the two advisory councils (the other dealt with science) set up by the Government when the Festival was first planned. The members were H. V. Lobb (chairman), H. V. A. Briscoe, F. J. Forty, W. G. Holford, Robert Matthew, Rowland Nicholas, Sir George Pepler, J. M. Richards and Howard Robertson.


When construction on the South Bank site was under way, members of the Presentation Panel were appointed co-ordinating architects and display designers for different areas, as follows. Architects: downstream section, Hugh Casson; upstream section, Misha Black; area immediately round the Dome of Discovery, Ralph Tubbs. Display designers: downstream section, James Gardner; upstream section, James Holland. H. V. Lobb was later appointed controller of construction for the whole site, being responsible for the progress of buildings and displays but not for their design.

H. T. Cadbury-Brown was architect for the main concourse and surrounding areas in the upstream section, and Peter Shephard, landscape architect for the equivalent downstream areas. H. F. Clark was consultant landscape architect for the whole site, assisted by Peter Youngman and Marie Shephard. The names of the architects for the separate buildings are given where illustrations of the buildings occur on the following pages. The superintending engineers were Freeman, Fox and Partners in association with R. T. James and Partners. The lighting consultant was L. C. Kalff.

THE EXHIBITION AS


LANDSCAPE

On the following pages the reader is taken for a tour round the South Bank exhibition in search of the subtleties of landscape planning that give it so much of its distinction, but whose full significance is not necessarily apparent at the first glance. For in town planning much of the art lies in concealing conscious intention—in contriving the happy accident—and it is as a highly successful exercise in the art of the town-planner that the exhibition should first of all be regarded. It makes a real contribution to town-planning technique, and as the visitor walks round it, with its thematic story unfolding before him, he might well be exploring a subtly designed town. He is led from point to point and his interest is continually renewed by the skilful use of the devices the town-designer, as well as the exhibition architect, exploits—or should exploit—in order to heighten vitality and underline the personality derived from the nature of his site: expectation and suspense, the relaxation provided by the quiet enclosure, the shock of the surprising view, the contrast of the familiar with the unexpected, changes of level, tempo and scale. These are all employed in the exhibition, both indoors and out, and are analysed on the following pages with an eye on their permanent application in town building. The itinerary followed in this tour of the exhibition in its guise of a newly planned section of London conforms roughly to the sequence in which the exhibition buildings are officially supposed to be visited. It is shown by the coloured arrow on the map of the exhibition below.





The tour begins at the Chicheley Street entrance, 7. Inside the white railings is the exhibition; outside is London. The chequered pavement of the first exhibition courtyard is carried beneath the railing to link the two. 8 (foot of page), a general view of the first courtyard—the Fairway—with the garden in front of the Country-side building in the foreground.




Inside the Chicheley Street entrance you are in a different world from London, but not in one of those formal layouts that generally accompany the architecture of display. You might be in a permanent town, a town designed to satisfy the multiple needs of daily life yet with an eye for all the incidental effects that the informal type of planning allows and that add so much to the vitality of the whole: changes of scale and texture; unexpected contrasts between the hard geometry of buildings and natural greenery; movement and mystery and the gradually unfolding view.


Consider the entrance courtyard—the Fairway, 8—as a small-town piazza, planned for pedestrians only. The multi-coloured screen on the York Road side, A in the sketch above, might be the façade of an office building or department store. At its foot is a recessed sidewalk, B, somewhat raised, serving a terrace of shops, and in front a row of little kiosks, poised over pools of water whose reflections add more sparkle to the scene. The building at the end, E, also has a recessed lower storey, suggesting that the pedestrian will find the barrier there not final. Between them, in the corner, is a small café, enclosed within transparent walls and extended in the form of an open terrace only separated from the pavement of the piazza by knee-high boxes of flowers—an agreeable adjunct to any town square. Liveliness is given to the other side of the piazza by



enclosed piazza . . .




9	10
11	12



a naturalistic garden, D, sunk a little way below it and protected by an elegant railing, C. There is a shallow stream, boulders, rank grasses and an occasional scrubby bush—a perfect foil (see sketch at foot of page) to the determined urbanity of the piazza. The garden is meant to be enjoyed as decoration, not physically experienced.

Beyond the garden rises the Countryside building, 9 on facing page, which is open to the air, and the pedestrian in the piazza looks into it, as he might into a covered market. In fact, it is a display of agricultural machinery. The eye is made to focus in turn on the wall paintings at the back, the moving machines in the centre and the implements in the foreground, with the result that the apparent width of the piazza is extended by the depth of this building. Another café terrace, half indoors and half out, overhangs the garden, 11. Further along, where the end of the adjoining building, the Land of Britain, breaks into the piazza in the form of rough stone walls, what might have been a dull passage in the design is imaginatively used to provide a kind of vertical garden in a minimum of space, a garden of roughly formed crags and boulders, 12, contrasting agreeably with the smooth chequered pavement.

As in a well-planned town, the exhibition makes the most of the space available by not disclosing itself all at one glance. By breaking it up into a sequence of enclosures the planners have greatly increased its apparent size. This particular enclosure, the Fairway, is planned with a fine sense of drama, because (see sketch plan above) only as you approach the far end do you become aware of the relatively narrow exit, 13. You turn the corner of the wall occupying the foreground of 10, the sense of enclosure being retained to the last. Then, with a shock of surprise, you find yourself on the brink of a vast territory, 14. It extends away before you, drops to a lower level, takes in the white plumes of the fountains and proceeds uninterrupted to the romantic outline of Whitehall Court, which is in fact on the far side of the river, but so skilfully are the levels managed that the river itself is




13, through the narrows from the almost totally enclosed piazza to the contrasting openness of the main concourse. 14, the view down the main concourse, closed by the romantic outline of Whitehall Court on the far side of the river. Above the riverside promenade rises the Skylon. 15, swinging left on entering the concourse the visitor sees for the first time the largest building in the exhibition, the Dome of Discovery.

open concourse . . .








not yet seen and its whole width is brought into the apparent area of the exhibition. You are now at the head of the main concourse, the limits of which are defined on either flank by the long glass façade of the Transport building and the rising curve of the Dome of Discovery. Above the entire scene the Skylon is poised as a dramatic punctuation mark.

The upper platform of the main concourse, 16, is flanked by cone-shaped aluminium porticoes, leading into the two main sequences of exhibition buildings. Into the left-hand one, 17—the entrance to the Land of Britain—the itinerary now takes you. Entering a sort of cave-mouth between rough stone walls set into a boulder-strewn hillside, you are swallowed up in a sequence of dimly lit chambers depicting the geological evolution of the British Isles. At the far end you are released into the Natural Scene, a brightly lit space (in contrast to the darkness of the other) dramatically rising in height and filled with the cries and whistles of birds. In the centre is a massive, twisted plaster tree, round which (see drawing above) runs a robust wooden gallery of ramps and steps, making spatial play in a limited area. The gallery is asymmetrical and creates a changing perspective from level to level. At the foot of the tree, 18, is an irregular woodland garden of leaves and wild flowers. And water, the most versatile element in the exhibition vernacular, lies in quiet sandy pools.

Climbing upwards and obtaining an impression of liveliness and flexibility of plan from the sight of other visitors crossing your path below and above you, as you and they circulate among the ramps and staircases, you eventually emerge on the upper level of the Countryside building into a long gallery devoted to crops and produce. At this point, and at many points afterwards, another speciality of the exhibition plan becomes apparent: the effectiveness of the frequent panoramic views, framed within the interior structure of the buildings, that are contrived so as to furnish unexpected but well-composed pictures of the bright outdoor world. They occur at all levels. 20, for example, allows you a glance back across the centre of the concourse through the escape doors at the end of the first floor produce gallery you have just reached.

A subtle variation of the same theme is performed along the whole

17, the aluminium cone which marks the entrance to the Land of Britain seen from within the corresponding cone (shown on the facing page) on the opposite side of the upper platform of the main concourse. 18, the foot of the great tree, standing in a woodland garden, round which the flora and fauna of the British Isles are displayed.



17



18

side wall of the same gallery, which is glazed to show a wide panorama of the Dome of Discovery, but partially obscured again (sketch below) by growing plants in the foreground and vertical canvas louvres outside the glazing, so that the view recedes into the distance and becomes a kind of two-dimensional drop-scene. By way of contrast, the next viewing-point brings you to close-quarters again with the open air: 21, from the platform reached from the far end of the same gallery. Here you look down into the piazza in which your tour began and are reminded that one side of it was formed by an open hall, in an upper gallery of which you are now standing. The unexpected presentation of a familiar scene from a different viewpoint is one of the most effective tricks of the town-planner's trade.


From this level you descend again, and continue your way through the lower portion of the Countryside building into the Minerals building, where you are plunged once more into a sequence of cave-like galleries, lighted only by the displays themselves. These terminate in a staircase, 19, from which you emerge through the side of the pyramidal Minerals building on to a lightly constructed footbridge, 20 feet above the ground, presenting another dramatic view across the upstream half of the exhibition site. You cross the footbridge into the Power and Production building, but instead of leaving the view just revealed to you you find it again, 22, framed in a tall window. The route now lies along an internal gallery from which you look into a machine hall below, and then down into a second hall, in which machine products are displayed, at the far end of which is another tall window giving a ground level view, 23, over a new quarter of the exhibition.

Here you are introduced to a fresh aspect of the exhibition plan.



19

19, a staircase rises up from the darkened lower floor of the Minerals building to daylight again and a footbridge leading to the Power and Production building.





side wall of the same gallery, which is glazed to show a wide panorama of the Dome of Discovery, but partially obscured again (sketch below) by growing plants in the foreground and vertical canvas louvres outside the glazing, so that the view recedes into the distance and becomes a kind of two-dimensional drop-scene. By way of contrast, the next viewing-point brings you to close-quarters again with the open air: 21, from the platform reached from the far end of the same gallery. Here you look down into the piazza in which your tour began and are reminded that one side of it was formed by an open hall, in an upper gallery of which you are now standing. The unexpected presentation of a familiar scene from a different viewpoint is one of the most effective tricks of the town-planner's trade.


From this level you descend again, and continue your way through the lower portion of the Countryside building into the Minerals building, where you are plunged once more into a sequence of cave-like galleries, lighted only by the displays themselves. These terminate in a staircase, 19, from which you emerge through the side of the pyramidal Minerals building on to a lightly constructed footbridge, 20 feet above the ground, presenting another dramatic view across the upstream half of the exhibition site. You cross the footbridge into the Power and Production building, but instead of leaving the view just revealed to you you find it again, 22, framed in a tall window. The route now lies along an internal gallery from which you look into a machine hall below, and then down into a second hall, in which machine products are displayed, at the far end of which is another tall window giving a ground level view, 23, over a new quarter of the exhibition.

Here you are introduced to a fresh aspect of the exhibition plan.



19

19, a staircase rises up from the darkened lower floor of the Minerals building to daylight again and a footbridge leading to the Power and Production building.




... the unexpected view




20 | 21
22 | 23

westminster backcloth





Hitherto you have been exploring a closed world, sufficient to itself. Only for a moment, when looking down the length of the concourse, were you aware of an older London in the shape of a distant romantic skyline. Now you are brought close up to it—or rather it (the panorama of London) is brought close up to you. You are reminded that this newly laid out town is part of a larger city, with which it shares a busy river highway. The exhibition planners have made magnificent use of a site in the geographical heart of London from which, among other groups of famous buildings, the towers of the Palace of Westminster make a better composed group than from any other viewpoint. These have been skilfully woven into the exhibition scene. They can be admired in the open, as in 24, a view from the terrace of the '51 Bar, or framed by exhibition architecture as in the sketch above, where they are seen beneath the projecting wing of the riverside Sea and Ships building.



The Sea and Ships building, 25, 26, 27, sums up in miniature the multi-level internal-external type of planning in which the exhibition specializes. Strung along the river front, a sequence of galleries, ramps and staircases leads you in and out among the exhibits—model ships and full-size parts of ships; marine objects of all kinds; diving gear and fishing gear—sometimes spanning over pools of water, sometimes under cover and sometimes in the open air (the coloured areas in the sketch plan above are those which are roofed over). The visitor views them from all levels and at the same time sees, as an appropriate background to them, the busy life on the river itself and hears the sound of breaking waves simulated by the mobile water-sculpture that stands in front.


On leaving the Sea and Ships display you turn your back on the river,



25



26




27

Sea and Ships display: 25, ship models on show beneath a suspended roof; 26, pool and staircase with the riverside promenade beyond; 27, basin of the water sculpture, with the openwork structure of the building on the right.

the insubstantial wall . . .



28
29 | 30



descending from the riverside promenade to the lower level of the main concourse. The exhibition regains its identity as a self-contained town. The concourse becomes the intersection of two main avenues. Trees line the sidewalks and offer a flickering view across the street. The Transport building, 28, becomes a department store which uses its whole façade as a show window of impressive depth owing to the transparency of its external wall. Kiosks and flower tubs divide and so extend the foreground. A bus is parked in a side street, and under a railway bridge a brightly coloured mural startles the spectator who thought that painting belonged exclusively to the city art gallery. A truncated Concert Hall looms mysteriously above the bridge.

Beyond the intersection another piazza opens out, a few feet higher. Here again trees alternately obscure and reveal. The high flung arch of the Waterloo Station Gate, 29, with its prominent viewing galleries,



31



32

31, entrance to the People of Britain. 32, garden within, seen from two levels as shown also in the sketches alongside.

provides an imposing contrast to the level forecourt. It has no end walls, being open to the air, so that the sky is seen through as well as above it. In a corner of the piazza, an open café is perched on a raised terrace, 30. The slight change of level, allied with a little planting, is sufficient demarcation between the pavement and the café terrace, which disappears beneath its lightly supported slab roof to become a two-level café-bar cleverly contrived underneath the arches of the railway viaduct that bisects the exhibition site.

In the background of the same picture, 30, is a disappearing wall in a rather different sense: a mural painting used not only as decoration but to break down the apparent solidity of a flat wall and give spatial complexity to an arrangement of basically simple architectural elements.

From this upper platform of the main concourse, there begins the second stage of the exhibition itinerary, by way of another cone-shaped aluminium portico, seen in 29, and then a footbridge, 31 and 33, which carries you over a shallow pool of water into the dark recesses of the railway arches. Before emerging into the downstream half of the exhibition you pass through the galleries depicting the story of the People of Britain, ingeniously planned on several levels so that the circulating streams of visitors pass over and under each other, 32 and 34, contriving a number of surprising spatial effects in a confined area, as when they come upon a jungle garden spread out beneath their feet, 32, and meet it again at eye level a little while later. An impression of this two-level planting is given in the sketches on the previous page, and at the top of the facing page is a diagram showing the circulation within the People of Britain galleries.

Half-way round the sequence of galleries the wall dissolves and you are taken by surprise by another view of the main concourse, 35, which you seemed long ago to have left behind. It is seen not only framed, as in the photograph, by the gallery posts and railings, but also partly obscured, as in the sketch immediately below, by a louvre screen through which the familiar view is given a new character by being separated into thin slices. This is a horizontal counterpart of the vertically fragmented view from the upper gallery of the Countryside building.

A little further along, at the corner of the building, is a break-away into a café. It is planned with exceptional cunning. The one-way circulation of the exhibition requires—and is provided with—occasional escape routes, so that the visitor does not feel too strictly regimented; or so that



33





34



35

33, entrance to the People of Britain by a footbridge across a water garden. 34, multi-level planning inside. 35, view back into the main concourse.






the window-shopper, if this were a pedestrian shopping arcade in a new town—as a building so planned well might be—can slip away as soon as he is bored or fatigued.

As you approach the corner of the People of Britain building, therefore, before turning to make the final passage underneath the railway, you are invited, but not too forcibly diverted from your tour of the exhibits, by an open concrete grille beside a doorway, 37, leading into a paved passage. On turning through the doorway a boldly lettered arrow points the way to a side entrance to the same vaulted café—the Turntable café, 36, that you inspected previously from the concourse. This side entrance is so ingeniously planned (see diagram below) and the doorway from the People of Britain so discreetly masked, that no one in the main concourse is aware of it and there is no tendency for the visitor unwittingly to enter the sequence of display in the People of Britain at a half-way point. Without any physical barrier the one-way traffic is maintained.

Continuing the tour you plunge beneath the railway, emerging from the darkness the other side into the open air and the downstream half of the exhibition. Once more you step into what might be the busy market-square, 39 (overleaf), of a real town. There is another enclosed piazza—though not so completely enclosed as the Fairway. The architecture here is rather different in scale. It is quiet, intimate and a little formal, in contrast to the more aggressive exhibitionism of the upstream architecture. This difference between the two halves of the exhibition not only underlines the difference of theme, but produces a pleasantly varied character very different from the insistent clamour for attention, never letting up for a moment, which characterizes most exhibitions and many town centres.



You enter the piazza through the pillared lower storey of the television building. On your left, raised on a low platform, is the calm, dignified façade, discreetly monumental, of the Lion and Unicorn building, 38, as it might be some small public building commanding the town square. On your right, the far side of the piazza is closed by the Telekinema and

37, break-out from the People of Britain into the Turntable café. The lettered arrow points the way to 36, a two-level café terrace beneath the railway viaduct.




36



37

the narrow exit beyond the television building, 40, suggests a street ready to lead you away into other quarters of the town. Facing you is the variegated façade of the Homes and Gardens building.

The piazza provides for several different uses: for normal pedestrian traffic, for more leisurely promenading, for sitting in the sun, 41, and (a little in the background) for eating and drinking out of doors, since the fourth side of the square (see sketch plan below), partially closed by the



38, the paved platform in front of the Lion and Unicorn building, facing on to the downstream piazza. 39, looking into the piazza, beneath the television building from the exit from the People of Britain.




38

Lion and Unicorn building, is also bounded by an informally planted garden containing the Unicorn café, 43.

Here and elsewhere in the piazza the designers have made skilful play with a number of the many devices that are at the town-builder's disposal in his task of giving character and vitality to the urban scene: minor changes of level, 40; informal planting, 40 and 41, to provide a foil to steps and paving and screen off a garden area for rest and reflection; the invisible wall, 42, beneath which the exterior paving is carried into the building, making the closest possible visual connection between inside and outside.

In the Unicorn café, 43, exemplary use is made of a number of other devices whose use the town-builder has taken over from the landscape gardener. At C in the sketch below, water not only adds liveliness to the



garden layout through its changing surface and its reflections of the sky, but provides the perfect barrier, defining the limit of the café area without interrupting the view. No railing is required; only a low stone kerb, B, with which the rough boulders bounding the water garden on the other side, D, make an agreeable contrast. The hanging umbrellas, A, likewise obstruct the view as little as possible, while providing the necessary shelter. They indicate the location of the café for a distance, and give the


flat garden an interesting skyline. Their rounded forms and strong colours make a lively contrast with the wiry shapes of the white-painted furniture.

The colour-scheme of the piazza shows evidence of the most careful study and the walls of the buildings (like the floor of the piazza) are rich in texture. The upper wall of the television building is plastered in sky blue, with large letters in yellow; the quilted wall of the Telekinema is earth brown, and the introductory pavilion to the Homes and Gardens building carries canvas panels broken into triangles of pale green, black and chocolate brown. These clear colours are relieved by the grey texture




39





44



45



46



47




48

Entrance to Homes and Gardens: 44, first portico; 45, closed vista; 46, open view to left; 47, concealed turning; 48, entrance left, break-away right.



of the flint gable wall of the same Homes and Gardens pavilion, by the brownish brickwork of the main Homes and Gardens building and by the vertical white lines of arrises, columns and flagpoles. The main view riverwards from the piazza passes between the formal planting in front of Homes and Gardens on the one hand and the irregular café garden on the other, to find a climax in the old shot-tower, a striking study in planned landscape.

On a smaller scale an even more striking bit of planning is the entrance to the Homes and Gardens building illustrated in the series of pictures on the left and in the sketch plan immediately below, on which the photographic viewpoints are marked. It is another instance of the concealed opening used on a larger scale in the Fairway piazza in the upstream section, for as you move from the piazza towards the portico formed beneath the superstructure of the introductory pavilion, 44, you



are confronted, in despite of the invitation extended by the bold inscription, not with a doorway but with a blank wall, 45, given some degree of formality by a piece of sculpture centred on it. As you move forward there is a sense of gathering confinement, which is suddenly dispelled a few paces further on by an unexpected view to the left, 46, across a lawn, a sunken pool, a sculptured figure and the distant shot-tower—a playback, as it were, of the view you have lately left. The foreground is unobstructed, but the slightly raised level of the lawn is sufficient to deter you from straying in this direction. As you approach nearer the blank wall, 47, you are enclosed again on both sides, and partly roofed in by a geranium-decked trellis, throwing a pattern of shadows on the pavement. An opening now reveals itself in the left-hand corner which, approached more nearly, 48, reveals itself as a double exit, straight on down a ramp—a break-away into another courtyard—or sharp left into the comparative darkness of the interior of the building.

The Homes and Gardens building lives up to the second part of its name by assiduously introducing the garden indoors and providing views of outdoor greenery. 49 (facing page), flower boxes protect a plate-glass window beyond which is a children's garden and another courtyard with its partially concealed bandstand. 50, a planted window-cill, and beyond it still another view of the piazza you have recently left. 51, a miniature formal garden, displaying a variety of floor textures. It is slightly sunk below the roadway outside, giving quite a new aspect to the half-seen exhibition concourse beyond. 52, another formal garden with a garden terrace in the background, showing the decorative value in an urban



foreground and background . . .




53	54
55	56

setting of minute quantities of planting when combined with a well-chosen variety of materials and textures.

At the far end of the Homes and Gardens building is another unexpected view, 53, through a glass screen whose vertical plane is decisively marked by a display of pottery and glassware in front of it, to the mysterious back courtyard already glimpsed in 49. In the near corner of the courtyard is a café (seen more clearly in 57) and beyond it a bandstand—an exhibition side-show casually revealed. Beyond that again is a busy background of boundary screen and flagpoles.

You emerge from Homes and Gardens into the main concourse of the downstream section, 55, dominated by the steel and glass observation tower that marks the Waterloo Gate. The entrance platforms (B in the sketch at bottom of page) at its foot extract plenty of drama from floating roof-slabs and cantilevered galleries and the deep shadows cast beneath them. From one of the half-landings a narrow footbridge, A, springs right across the concourse and boating-pool to provide a direct link between the Waterloo entrance and the Royal Festival Hall, to which it gives access at terrace level. Within the land arches of Waterloo Bridge, C, are the entrances to the Schools and Health displays, where an intriguing sense is given of being both indoors and out. The wide roadways of the concourse are



relieved by flowers and sculpture, 58, and from it a paved street, 56, runs down to the river between the boating-pool on one side and a raised café terrace on the other. There are glimpses of the river hereabouts, but this stretch of the river front (where the north bank panorama opposite is at its dullest) has been deliberately closed off by the semi-transparent Sports display, 54, adding an element of mystery to the riverside treatment, using suspense and surprise as foils to the open display of riverside scenery encountered elsewhere. 54 is taken from the cast-iron and concrete gallery containing the 1851 memorial exhibit.



57, concealed courtyard and garden café, seen through a pottery display in the Homes and Gardens building. 58, flowers and sculpture as foreground to the Waterloo concourse.



57



58

This is closely linked to the shot-tower, and they jointly provide a high focal point in the centre of this irregularly planned area as the sketch on page 99 indicates.

On approaching the river the itinerary takes you round to the right, behind the Thames-side restaurant with its pretty undulating roof and underneath the first land arch of Waterloo Bridge. It then brings you out on to a terrace (in the top left-hand corner of the plan below), and confronts you with a new and surprising aspect of this magnificent riverside site: the view *down-river*, 59 and 62, entirely different in character from the up-river view you admired from the Sea and Ships building and the terrace of the '51 Bar.

On the right is working London, a tangle of grimy jetties, cranes and warehouses rising picturesquely from the foreshore mud. Beyond them is the wide sweep of the river as it curves away towards the south and beyond that the skyline of the city crowned by the dome of St. Paul's. An exhilarating view and a perfect platform from which to admire it, near enough to the water to feel its coolness in the air, a thing a Londoner can rarely do in spite of the fact that his city has grown up along the river.



59




60



61

Thames-side restaurant: 59, downstream terrace; 60, clerestory landscape; 61, board-walk and river view.




The Thames-side restaurant is equally well-sited to provide the same experience. It is worth entering first of all by the down-river entrance to observe, in the entrance vestibule, the clerestory windows, 60, past which you are surprised to see walking foot-passengers on Waterloo Bridge, outside the exhibition grounds altogether—a landscape view at an unexpected level. But you must return thence, through one of the openings in the glass screen that forms the river wall of the restaurant, on to the narrow board-walk outside, which follows the curve of the restaurant the full length of its river front. This board-walk, 61 and 63, has a row of tables along its outer edge and thus combines the functions of open-air café and river promenade. It has nautical-style railings, a red and white striped awning for shelter and a boarded floor with open joints through which the movement of the water can be seen beneath your feet, giving a wonderful feeling of the immediacy of the river.

The board-walk, like the restaurant, passes beneath Waterloo Bridge, after which the downstream view, 63, is exchanged for the upstream view, 64. In the background is the serrated skyline of Whitehall Court, already familiar as the climax of the upstream concourse. The board-walk terminates in a staircase, 65, leading up to a viewing deck from which a new waterfront panorama is obtained. The staircase, cantilevered out over the river wall, gives the visitor a remarkable sensation of being swung for a moment, as it were, right outside the exhibition, an effect



river view . . .





enhanced by the open risers through which the exterior face of the river wall, as well as the river itself, can be seen.

Up-river from this viewing-deck, as far as Hungerford railway bridge, is another stretch of riverside promenade behind which rise the terraces of the permanent Royal Festival Hall (see sketch plan at top of page). Suspended above it, and overhanging the river wall, are look-out platforms, 66 (facing page) and 68, smartly painted and beflagged, and designed with all the economy of means and forthrightness of effect traditional to nautical engineering. Their function is to enable a visitor who climbs the double flight of stairs to feel isolated for a moment from the bustle of life on land. They are a spirited addition to London's riverside amenities which, like the Thames-side restaurant and board-walk, might well be preserved after the exhibition closes.

Along the inland side of the promenade stretches a continuous awning, providing a parallel promenade under cover, and a pleasant area of shadow to contrast with the brightness and sparkle of the rest. It accommodates various outdoor displays evocative of seaside life and leisure. With its freely planned kiosks and entertainments it might, indeed, be the water front of a river or seaside resort. It can be seen in the background of 69, and 67 is taken from underneath it. In the centre of 67 is the base of one of the masts which, by a system of cables and counterweights, hold up both the awning itself and the look-out platforms illustrated on the facing page.


At the up-river end of the promenade, as you emerge from the shelter of the awning, there is a view, 70, up a service side street, alongside the flank of the Royal Festival Hall, the terrace of which forms a side-walk at a higher level. You then pass beneath the railway bridge, 71, on to the



67



68



69




70



71

Downstream river front: 68, look-out platforms; 69, seaside parade with awning (in the background the Royal Festival Hall); 70, side street and flank of Royal Festival Hall; 71, under the railway bridge to the upstream section.




upstream promenade, meeting again the distant view of the towers of Westminster, framed this time by the terraces of the Regatta restaurant.

This three-storey restaurant combines with its own system of open terraces the terraces and staircases required to receive visitors who approach the exhibition across the Bailey footbridge specially built over the Thames alongside Hungerford Bridge. They arrive at a high level and are brought down to the riverside promenade (and thence to the main course), on the landward flank of the restaurant, 73. The opportunity is used to create an intricate composition of platforms and staircases which frame both river and exhibition views. In the middle is a garden, 75 and 76, designed to be seen from the various surrounding levels, and alongside it an overhanging wing of the restaurant, 74, shelters an outdoor bar (see sketch plan below), with sitting space incorporated in the garden.

The design of this garden and the terraces around it is an object-lesson in the intelligent use of many of the landscape devices which this exhibition so aptly demonstrates for the benefit of the future town-builder. Several of them are illustrated in 76: the low flower boxes (D in the sketch above) to rail off the sitting area without the need for obstructions at eye-level; sculpture; water and greenery arranged in an informal way, C, to give variety of texture and set off the rigid lines of the architecture; variety of levels, B, to provide the unexpected view; transparency of structure, A, to take full advantage of the lively prospect across the river. This river view, the climax of the exhibition, to which the visitor's eyes are continually encouraged to return, is seen best of all from the upper terrace of the restaurant, 77 (overleaf), where the panorama of London buildings constitutes an older counterpart to the buildings of the temporary new town on the South Bank—a permanent *North Bank* exhibition.

The river view is at its most romantic at night. 72, looking across from one of the terraces of the Regatta restaurant to floodlit buildings on the north bank of the Thames.



....juggling with three dimensions



73	74
75	76

north bank exhibition . . .



THE EXHIBITION AS A

TOWN BUILDER'S PATTERN BOOK

A civilized urban landscape depends just as much on the quality of its incidental details as on the quality of the buildings the town is composed of. Good architecture can be ruined by clumsy street furniture, by the ill-considered design of railings, steps and pavements, by bad lettering or by a failure to make proper use of trees and plants. On the other hand, if all these details are well handled, they are capable of transforming bad architecture, if not into good, at least into an acceptable whole, so that it becomes a variegated and only partially apprehended background to a satisfactorily designed foreground scene.

A special virtue of the South Bank exhibition is that details of this kind are, almost without exception, of a remarkably high standard—imaginatively conceived and intelligently carried out. It is, or should be, an object lesson to town-planners, borough engineers and others responsible for the design of roads and their furniture, public spaces and their layout, and of all the other incidentals that occupy the foreground of the urban landscape. It should be studied with special attention by the designers of our new towns, where the scene is not already confused by the mistakes of the past and where there is therefore a rarely found opportunity of setting up new standards in urban design.

Other parts of this issue illustrate the buildings of the South Bank exhibition and the layout of the grounds in its larger aspect. On the following pages the photographer's eye is focused on the smaller external details. The examples chosen from the many interesting pieces of detailing in the exhibition are those which provide the best precedents for future use in new towns and old—the nucleus of a town-builder's pattern book. They are arranged under the following headings, which correspond to a distinct type of problem that the town-builder has to solve and echo the title under which the REVIEW has dealt with similar problems in the past.

the functional tradition* To decide, as we must, that the acknowledged historical styles of architecture are no longer relevant to the needs of to-day does not mean abandoning all reference to the past. Alongside and contemporary with the historical styles there has always existed a tradition of non-stylistic architecture, derived from a straightforward fulfilment of function by the simplest engineering means, and from the logical use of materials. This anonymous architecture, whether in the form of large structures like bridges, harbour works and warehouses or of small details like hand-rails, steps and bollards, provides a valuable basis for a rule of thumb solution to many design problems, and is well in tune with the spirit of our own age since

we, too, lay stress on fitness for purpose and truth to material. The exhibition contains several good examples of the functional tradition of design which show how readily it is adaptable to modern needs.

the nautical style A variant of the functional tradition, with a special character of its own, is to be found all round our coasts wherever the forthright demands of the shipwright and the seafaring man have gradually shaped building materials to their purpose over many generations. The attributes of the nautical style are a robust shapeliness, which is given an easily recognizable personality by the frequent use of whitewash and tar, originating as aids to visibility, but evolving with time into a decorative vernacular. The riverside situation of the

* See THE ARCHITECTURAL REVIEW, January 1950.

exhibition has inspired several of the architects to explore the possibilities of this nautical idiom, which seaside and riverside towns elsewhere would do well to study too.

Intricacy comes to modern architecture

Several buildings on the South Bank show modern architects successfully at work on the task of building up a richer vocabulary of effects than was current a few years ago, when simple geometry was admired for purity's sake. Intricacy is shown to be attainable by the use of all-over pattern, by the use of transparent planes visually superimposed and by other means that naturally come from an imaginative use of modern materials and structure techniques.

sky pattern The severe horizontal roof-line that has dominated architecture for many years—indeed, since the Georgian revival supplanted Norman Shaw romantic at the beginning of the century—is at last being broken. It is characteristic of the contemporary emphasis on lightness and spatial effects that it should be broken not by a picturesque silhouette of gables and chimneys, but by transparent structures making a pattern with the sky. It is the kind of effect that can bring sparkle and variety to the urban landscape when skilfully contrived, but can ruin it when allowed to happen accidentally as when the sky becomes almost blotted out by a network of overhead wires.

interrupted view Closely related to the use of pattern against the sky, as a visual technique of great potential value to the town builder, is the use of screens of various degrees of transparency to make the most of a distant view when some sense of enclosure is, nevertheless, desirable, and to define the limits of a foreground space without creating an absolute barrier. On the South Bank are numerous examples of this technique skilfully used: glimpses of the exhibition grounds through the horizontal louvres of Venetian blinds that cover the windows of some of the buildings or form the outer walls of others, views of the river half revealed by bamboo or planted screens on restaurant terraces, glass show-cases indoors that permit a view of the outdoor activities beyond. An intriguing sense of being half indoors and half out might well be similarly contrived in the shopping arcade, the café terrace and elsewhere in permanent town architecture.

the use of hazards From the interruption of the view to the interruption of physical progress. There are many places where the town-planner needs to guide the pedestrian in one direction rather than another and prevent his feet straying where they shouldn't. Rather than rely on the solid wall or the forbidding high iron railing he can make use of many more imaginative means, generically known as 'hazards,' which, instead of putting a solid barrier in the pedestrian's path, suggest a barrier by subtle psychological means: by the use of slight changes of level, of water, of grass and of planting. The potential decorative value of these is illustrated in many parts of the exhibition.

exploiting the third dimension Town-planners are beginning to understand that their art is not only one of drawing lines on the ground, but of projecting them into the air. But in their rediscovery of the third dimension they have not yet exploited it to the full as some examples of the dramatic use of levels at the South Bank suggest. A contemporary architecture of slender structures, bold cantilevers and transparent walls lends itself particularly well to three-dimensional planning and all the visual effects which that implies.

planting in odd corners A recurrent problem in the layout of streets and squares, of which too few municipal authorities are even aware, is how to treat the odd corners, the small areas of unusable space at road junctions, where the pavement suddenly widens, where the blank wall of a building faces a public square. If they are ignored the result is an air of neglect and a receptacle for dirt and paper bags. As many towns of Scandinavia show (and many imaginatively treated corners of the South Bank) such odd corners can be effectively filled in with informal planting, adding a touch of greenery where it is needed most. Municipal planting is generally restricted to public parks and gardens of some extent, but planting on a minute scale is proportionally far more rewarding, though it must be done wittily and without formality. What is not required is the heavy hand of the municipal engineer.

wallscape Variety of texture in wall surfaces, whether produced by changes of material or by the application of colour or other decorative surface, makes an important contribution to the progressive enrichment of their vocabulary which modern architects are now seeking. The range of materials and textures to be seen on the South Bank is immense and their applicability elsewhere is obvious.

street furniture A special virtue of the South Bank exhibition is the care given to the design of all the items of equipment that stand on and around the pavements: seats, lamp-posts, litter containers and the like. They charm the eye individually and give unity to the whole scene, illustrating the value of well-designed furniture in any urban landscape.


lettering Campaigns against bad lettering in public places have resulted in the elimination of many ill-conceived, showy Victorian and Edwardian styles, but have replaced them by rather negative styles, of which a genteel good taste is the only virtue and in which the orthodox Roman letters or the sans-serif letters popularized by Eric Gill are preferred to the more robust letters of the older English display traditions, such as the Egyptian. Now that the fashion for Gill has served its purpose of establishing the value of restraint and simplicity, town designers are free to introduce more *character* into the lettering they use, with the aid of colour, relief and the strongly defined square serifs which an earlier generation evolved for similar purposes. The effectiveness of this signwriter's tradition can be seen in almost every building on the South Bank.

functional tradition

The functional use of pebbles to give variety of pavement surface, 78, thrown down loose, and kept in bounds by a stone kerb: the terrace outside the Lion and Unicorn building (R. D. Russell and R. Y. Goodden, architects; Peter Shepherd, landscape consultant), 79, embedded in cement to form traditional cobbled paving on the terrace of the Royal Festival Hall (Robert Matthew, architect to the London County Council).

78
79

80, railings, decking and canopies linking the boardwalk outside the Thames-side restaurant (Fry, Drew and Partners, architects) with the riverside promenade. This and the external stair, 81, at the Dome of Discovery (Ralph Tubbs, architect) illustrate the modern use of traditional functional elements—traditional in the sense that they might have come out of stock at any time since the materials they employ were first brought into use.

80
81

There is also a functional tradition of exterior paintwork, as exemplified in the base of the old shot-tower, 82, painted black and white by Hugh Casson to contrast with the stock brickwork above. In accordance with tradition, the window-cills and window-reveals in the tower are white also. Another example of the traditional use of colour, both functional and decorative, is the black and white painted kerb on the far side of the boating pool.



82

functional tradition


The posts forming a chain barrier, 83, in the Sports section (Gordon and Ursula Bowyer, architects) are a sleek adaptation of the traditional quayside bollard. The white painted railings, 84, in front of the Countryside building (Brian O'Rourke, architect) use a traditional style of park railing with great elegance. Note the uprights planted direct into the grass just clear of the pavement edge, and the slight angle at which the railing is canted inwards.



83
84

nautical style

The constructional techniques and characteristic finishes evolved by generations of shipwrights and dock engineers are well adapted for use in modern architecture, which takes the same delight in economy of line and structure. They are aptly used in the design of the look-outs that overhang the river wall in front of the Seaside section (Eric Brown and Peter Chamberlin, architects). 85 and 86, typical details.



85
86

87, one of the same look-outs, seen from below. The platforms are carried on a light steel framework suspended from a mast (another familiar ingredient of the nautical style) by a system of cables which are then taken back to support the canvas roof of the displays behind. For both brilliance and charm of effect this combination is one of the most successful things in the exhibition. It is the ideal waterfront treatment for the Royal Festival Hall and should be retained permanently. Notice also in this picture the appropriately nautical character of the railing that surmounts the river wall, with its handrail of polished wood. It is *genuine* nautical detail, not an architect's approximation to it.



87

83
84


88, nautical-style railing, with wooden handrail and stretched canvas panels, on the boardwalk outside the Thames-side restaurant (Fry, Drew and Partners, architects). Note the open-jointed timber decking which permits glimpses of the river beneath one's feet, enhancing the sense of the immediacy of the water. Timber decking is also used in the Sea and Ships building, 89 (Basil Spence and Partners, architects), where it is surmounted by another standard type of nautical railing.



88
89

85
86

The previous examples of the nautical style show modern architects taking over genuine nautical elements and techniques and incorporating them in their own designs. 85 to 89 might be parts of a liner or a landing-stage. In 90 the process is taken a stage further. This crow's-nest decorating the Seaside section (Eric Brown and Peter Chamberlin, architects) is a fantasy inspired by nautical structures, but adapting them to its own purposes, an example of a live tradition reinterpreted and given a very different character in the process. This is in fact a skit on the nautical style. The success of such a skit depends on the wit of the designer, which in this case is of a high order. It is legitimate in an exhibition; elsewhere it has obvious dangers.



90



***intricacy
comes to
modern
architecture***

A remarkable richness of texture is achieved in the screen, 91, separating York Road from the exhibition grounds (Architects' Co-operative Partnership) by an intricate arrangement of panels of coloured canvas stretched on a welded tubular steel framework to form a three-dimensional pattern. On the right of the picture is the underside of the timber roof of one of the kiosks (by the same architects) which stand over pools of water at the base of the screen.



91



Two examples of the intricacy of effect obtainable when all three dimensions of a structure are visible at the same time. Both the sport exhibit, 92 (Gordon and Ursula Bowyer, architects), and the Sea and Ships building, 93 (Basil Spence and Partners, architects; James Holland, display designer) are conceived not as buildings to contain exhibits but as a kind of skeletal architecture consisting of the exhibits themselves and access gangways for the public woven among them.

92
93

Intricacy is introduced into the larger view by the use of masts, flags and their supporting lines and cables, arranged in a regular pattern and helping to define, as it were, the receding planes of the picture. 94, Seaside section (Eric Brown and Peter Chamberlin, architects). 95, Unicorn café (R. D. Russell and R. Y. Goodden, architects). In the background are the old shot-tower and the temporary rear wall of the Royal Festival Hall.


94
95

The effect of intricacy in 96 is produced by the array of vertical elements in different planes: the strongly marked vertical angles of the buildings, the background flagpoles and the foreground railings. The façade of the Homes and Gardens building (Bronek Katz and Reginald Vaughan, architects) seen from one of the garden balconies designed by Gordon Cullen. In 97, the Waterloo gate (Fry, Drew and Partners, architects) intricacy is produced by the transparency of the whole structure and by the use of floating slabs intersecting and overlapping at various levels.

96
97

sky pattern


This light steel framework, 98, decorated with coloured balls, is designed both to provide a lively pattern against the sky and to distract the eye from the buildings visible beyond the boundary of the exhibition at the north-east corner. Edward Mills is the architect of this screen and of the observation post (seen in the background of the picture) which stands on top of his administration building.



98

sky pattern

99, a complicated sky-pattern provided by the open-work canopies suspended above the Chicheley Street entrance (Architects' Co-operative Partnership). The essential character of the skylon, 100 (Powell and Moya, architects) lies likewise in its dramatic silhouette, accentuated by the near invisibility of the cradle of cables that supports it. In the foreground the boldly overhanging roof of the Dome of Discovery (Ralph Tubbs, architect) contrasts with the delicate outline of its lattice steel struts. On the left, the transparent structure comprising the Sea and Ships exhibit.



99
100


101, a variety of sky-patterns: the coal-faced concrete tetrahedron housing the mineral exhibit, the open-work canopy over the Chicheley Street entrance illustrated above and the angular concrete hood cantilevered over the pay-boxes and turnstiles. All are by the Architects' Co-operative Partnership. In the distance is the skylon, also shown from below in 102, with one of the exhibits outside the Sea and Ships building, showing how the same aesthetic quality is also found in functional—especially maritime—objects.



101
102

the interrupted view

The screen at the north-east corner of the exhibition, 103 (Edward Mills, architect—see also previous page) focuses the eye of the spectator on the coloured balls suspended within it and throws the London buildings beyond far into the background. That is the functional use of the interrupted view. Its decorative use is shown in 104, where the river scene is interestingly framed for the benefit of the visitor sitting in the Thames-side restaurant by the vertical members of the glazed side wall and the canopy and balustrade of the board-walk beyond (Fry, Drew and Partners, architects).




103
104

105, a bamboo screen used to partially reveal the view of the Palace of Westminster from the terrace of the '51 bar (Leonard Manasseh, architect) providing an interesting change of texture. The arched bamboo pergola frames the sky in a geometrical pattern and makes a ceiling of lights after dark. 106, pottery and glass arranged on glass shelves in the Homes and Gardens building (Robin Day, display designer) provides a well-defined foreground to a glass screen beyond which are intriguing glimpses of the café and courtyard beyond.

105
106

the use of hazards

The use of hazards is the technique of guiding people in a required direction without resorting to railings or other obstructive barriers. In 107 the flower boxes are a decorative way of preventing the unobservant walking through the plate-glass windows of the Homes and Gardens building (Bronek Katz and Reginald Vaughan, architects). The short wooden spikes on the upper surface, to prevent their being used as seats, are hazards of a rather different kind. 108 shows flower boxes similarly used at the Regatta restaurant (Misha Black and Alexander Gibson, architects) to enclose the seating area of the garden bar without obstructing the view in or out.

107
108

Water is one of the most effective hazards because there is no temptation to overstep the boundary it defines. It is sufficient, therefore, to mark the boundary only with a clearly visible low kerb, like the stone edging separating this water garden, 109 (Peter Shepherd, architect) from the Unicorn café, from which the visitor gets an uninterrupted view over the garden. This picture also shows the effectiveness of the decorative screen already illustrated in preventing the buildings outside from intruding into the exhibition landscape.



109

the use of hazards


Pools of water, 110, effectively guide the visitor's feet towards the steps leading to the Fairway kiosks (Architects' Co-operative Partnership). When traffic is to be canalized along one definite route water constitutes the most effective deterrent against the visitor straying elsewhere, as in the entrance to the Land of Britain, 111 (H. T. Cadbury-Brown, architect). The planting is by Peter Youngman and the sculpture by Henges.



110
111


exploiting the third dimension

The cantilevered or lightly supported slab, intensifying for whoever stands on it the drama of being poised in mid-air, is effectively exploited in the various terraces of the Waterloo gate, 112 (Fry, Drew and Partners, architects) and the Embankment gate, 113 (Misha Black and Alexander Gibson, architects). The garden is by H. F. Clark and Peter Youngman.



112
113

The same kind of drama is created internally in the Lion and Unicorn building (R. D. Russell and R. Y. Goodden, architects), where a lightly railed-in gallery spans from one end of the building to the other. This unfinished view, 114, shows the minimum interruption of the view down on to the floor of the building on one side and down to the ground outside on the other through the glass wall that opens one side of the building to the sky.



114

A sense of being agreeably poised on the edge of a precipice is also given in the '51 bar, 115 (Leonard Manasseh, architect) and the Regatta restaurant, 116 (Misha Black and Alexander Gibson, architects) where glazed walls are taken right down to the floor and restaurant chairs placed immediately inside them. The sculpture below the '51 bar is by Daphne Hardy.


115
116

The third dimension is fully exploited by the design of gardens in section, as it were, as well as in plan. The planting, 117, on the Royal Festival Hall Terrace (Robert Matthew, LCC architect) is composed of hexagonal concrete flower boxes which can be piled on top of one another both to allow changes of level and to provide additional depth of earth. 118, a more naturalistic garden at the end of the Fairway piled up at a steep angle so that it can be seen from a distance almost, as it were, in plan. The conventional flat garden occupying the same area would be overlooked (H. T. Cadbury-Brown, architect; planting by Peter Youngman).

117
118

planting in odd corners

Opening out from the galleries of the Homes and Gardens building (Bronek Katz and Reginald Vaughan, architects) is a series of sunk gardens which admirably demonstrate the value of a small planted area as a foil to architecture. The herb garden, 119, by Peter Shephard, consists of a regular pattern of beds set in a square of paving of various textures.



119

**planting in
odd corners**

120, miniature oriental-style garden, occupying a concrete trough slightly raised off the ground against the brick wall of the Turntable café, alongside the Station gate (H. T. Cadbury-Brown, architect).



120


121, another way of enlivening the odd corners around a building: plants in circular pots form a temporary garden (by Peter Shephard) behind the Royal Festival Hall and, as in 119, provide a foil to various textures of paving. Squares and other open spaces also have their odd corners which, if not carefully treated, become a receptacle for dirt and rubbish. Such a corner, 122, is filled in by the three-dimensional Fairway garden already illustrated in 118.




121
122

wallscape

Varied wall texture is one of the most obvious means by which modern buildings can be given more colour and richness. 123, the timber flank of the Sea and Ships building (Basil Spence, architect; planting by Peter Youngman). 124, introductory pavilion to Homes and Gardens—stretched canvas panels on the left; flint walling on the right (original design by Denis Clarke-Hall; Bronek Katz and Reginald Vaughan, executive architects).



123
124



125, great richness of wall texture is attained in this miniature terrace—a kind of formal garden planned vertically—designed by Gordon Cullen outside the Homes and Gardens building. The elements employed are rubble stone walling, white-painted trellis (square and diagonal), timber slats, plants in pots, board fencing and the complicated shadows each of these casts on the others.

125

street furniture

The South Bank maintains a very high standard of design in the various items of furniture that stand about on the pavements and piazzas. 126 and 127 are two of the most successful: the standard cigarette bin, by James Cubitt and Partners—the top and legs are black; the body partly yellow and partly red and white stripes—and the standard litter box, by Jack Howe, in grey with a yellow letter. The container is removable. There is also a single model, for placing against a wall.

126
127

street furniture

A standard outdoor chair used throughout the exhibition. This model is known as the 'Antelope' and was designed by Ernest Race. It is of bent steel rod, painted white, with a plywood seat painted in various colours. 128 shows a group of the chairs empty. 129 shows their elegant appearance when occupied.




128
129

In many parts of the exhibition grounds light fittings are placed among the plants so as to illuminate them at close range at night, as in 131. The fittings shown in both these pictures were designed in the Festival of Britain office, as were the circular plant pots in 130, grouped by H. T. Cadbury-Brown outside the entrance to his People of Britain building. The building in the background of 131 is the Telekinema by Wells Coates.



130
131

132, portable signpost, with lettering in white on grounds of various colours, used throughout the exhibition and designed by Robin Day and Milner Gray. 133, paybox at the Chicheley Street entrance, by the Architects' Co-operative Partnership. This geometrical arrangement of transparent, louvred and solid panels constitutes a style of design well suited for telephone boxes and similar structures in town streets.



132
133


lettering

External lettering throughout the exhibition was under the general control of Gordon Cullen. In the past when the usual tasteless array of commercial lettering has been brought under control it has been replaced by a genteel roman or by the—for display purposes—characterless Gill. Here there has been a welcome return to the well-tried early nineteenth century tradition of bold Egyptian-style letters with square serifs. 134, cut-out letters mounted on the screen of wooden slats enclosing one side of the Turntable café. The script lettering above makes a lively contrast (Terence Bliss and George Subiotto, designers).



134

135, the italic form of the same style of letter, painted on the wall at the side entrance of the same café. 136, standard direction signs (by Milner Gray) in the same style as on the signpost already illustrated in 132. Below are three out of the large number of signs, mostly employing pictorial symbols, that have been devised for use in standardized form all over the exhibition.


135
136

137 and 138, two variations of the square-serif, Egyptian-style letter used by Misha Black on a wall panel at the entrance to the Regatta restaurant and by Fry, Drew and Partners against a background of polished copper outside the Harbour bar. 139, an example of the use of large letters for their decorative effect on the landward side of the Sport exhibit (Gordon and Ursula Bowyer, architects).



137

138
139



140



141

DOME OF DISCOVERY

ARCHITECT: RALPH TUBBS

The dome itself consists of a network of aluminium alloy ribs, intermediate rafters and purlins, covered with aluminium sheeting and resting on a circular ring girder of welded mild steel. The girder is supported 45 feet above ground by 48 diagonal struts of tubular steel. The diameter at the base of the struts is 365 feet. There are three internal galleries, the highest supported on a ring of reinforced concrete fins, 15 inches thick, arranged radially and narrowing towards the ground, and the other two supported on a steel frame. The gallery floors are of precast concrete slabs. The interior is enclosed by a double-skin drum wall, placed eccentrically to the dome above. The top of the wall intersects an inverted cone of aluminium descending from the eaves of the dome. Consulting engineers: Freeman, Fox and Partners. 140 and 141, two interiors showing the galleries and staircases. 142, the exterior looking across the main concourse. See also photos 15, 22, 81 and 100.



142



THE EXHIBITION

BUILDINGS

Elsewhere in this issue attention is concentrated on the layout, landscaping and external detailing of the South Bank exhibition, rather than on the architecture of the buildings, because in its landscape treatment lies the special contribution made by the exhibition to contemporary design. But the buildings as individual examples of architecture must not be ignored. They represent together the largest display of the modern architectural idiom that the British public has seen, and they provide a fair test of the designing abilities of the younger generation of British architects. Several of the buildings are the first major work the architect responsible has carried out. In this article the principal buildings are discussed and criticized, and on the pages that follow they are briefly illustrated, the greatest attention being paid to those buildings which are not shown—or are only touched upon—in the illustrations in other sections of the issue. The general views on the following pages should therefore be studied in conjunction with the details appearing on the preceding pages to which cross-references are given in the captions.

By far the largest building in the exhibition, and potentially the most interesting, is the Dome of Discovery (Ralph Tubbs, architect; Freeman, Fox and Partners, engineers). It is also the most disappointing in so far as it falls short of getting full value out of a grandly simple idea, that of roofing in a great space with a lightly constructed saucer dome supported on its extreme edge by a system of struts, themselves as light as possible in appearance. The three internal galleries are supported quite independently of the dome structure, the top one being cantilevered from a circle of reinforced concrete fins, radiating from the centre, and the others resting on a steel frame.


The essential attributes of this ambitious conception are the apparent effortlessness with which so vast a space is enclosed and the lightness with which the roof is poised on its supports. The opportunity of creating a distinguished—an aesthetically satisfying—piece of architecture lay in exploiting them to the full. When the dome was under construction it showed every promise of doing so. There were thrilling moments when the fragile lattice-work of the interior dome structure, lightly resting on its slender struts, could be seen simultaneously with its smooth outer surface, giving a wonderful effect of dramatically enclosed space. But as the curtain walls went up this effect was lost. It often happens that the skeleton of a modern building reveals the drama of its construction more impressively than the finished result, but in this case the total enclosure of the perimeter by a solid wall completely belies the nature of the structure. This wall, spanning between massive raking ribs, and the downward-sloping soffit above it, though both are only infilling, look as if they support the dome and appear to employ an unnecessary weight of material for the purpose. So instead of a wide-spreading roof delicately poised on the minimum support, the effect is of a heavy circular wall carrying a disproportionately insubstantial aluminium roof. A dynamic structure has become a static one.


It was no doubt necessary, if the maximum use was to be made of the interior for display purposes, that the perimeter of the buildings should be totally enclosed, but it would surely have been practicable to have stopped the wall short of the underside of the dome, and contrived some less substantial form of soffit, thus better expressing the character of the wall as a mere

curtain. The dull colour with which the walls, the soffit and their rather clumsily proportioned ribs have been painted adds to the heavy effect, though it has the advantage of setting off the delicate lines of the tubular steel supporting struts and the gracefully detailed outside staircases, which are painted in light colours. It might have been even more effective to have broken up the wall surface by painting it in some kind of free pattern that cut across the vertical ribs, as a way of destroying its apparent structural solidity; adapting, that is to say, the technique of dazzle-painting used on ships in war-time. Architects do not make nearly enough use of the experience camouflage artists acquired during the war of how to create and destroy form by the application of colour.

The Dome of Discovery is well placed on its platform, and the overhang of the roof on the side next to the main concourse, resulting from the fact that the circle of the outer wall and galleries is not concentric with the circle of the dome, provides a vigorous frame to the view up and down the concourse, making a useful contribution to the pictorial variety of the exhibition landscape.

If the foregoing remarks about the dome seem unduly severe, that is because it is a building which demands to be criticized





Dome of Discovery: ground floor plan scale 1/96 in. = 1 ft.

by high standards. They are a tribute, that is to say, to the boldness and imagination that went into its initial conception. In its interior, these qualities are much more clearly revealed. The great span of the roof, emphasized by the criss-cross pattern of its aluminium lattice structure, is truly impressive; so is the contrasting sweep of the strongly defined concrete galleries. The effect is somewhat marred by the confusion of displays on the ground floor, which are planned without any apparent relationship to the circular form of the building. They are also sadly out of scale with it, the only interior displays properly in scale being the large abstract constructions which occupy each bay between the concrete fins, round the upper perimeter.

The numerous displays (by the Design Research Unit) are nevertheless full of ingenuity, but this is perhaps the place to remark on the tendency apparent throughout the South Bank exhibition to indulge in over-elaborate display technique. It is inevitable in so large an exhibition that there should be a certain amount of repetition of the various tricks which have become the display designer's stock in trade, but in too many places these obscure, instead of underlining, the message the exhibits are meant to convey. A possible explanation is that British exhibition design, which emerged so brilliantly during the war under the leadership of Misha Black, and has since maintained a standard as high as anywhere in the world, had as part of its war-time task to evolve a technique of translating into visible terms concepts which were not visual in themselves. Whether the purpose was an exhortation to dig for victory or a reminder of the part played by the Merchant Navy in defeating the submarine menace, there were no goods or other exhibits to which the display had merely to draw attention and create a suitable background. The designer's interpretation of the idea was the whole exhibit.

Many clever devices were invented to meet this need, but they cannot be carried over to the display of actual objects such as industrial products. This was shown at the first important exhibition held after the war, 'Britain Can Make It' at South Kensington, where the designers brought into play so many tricks of the propaganda trade that it was often impossible to tell whether the object on which one's attention was focused was one of the exhibits or merely part of the setting.

This tendency to over-installation is apparent in many parts of the South Bank, especially where products are shown rather than ideas. Inside the Dome of Discovery there is a mixture of both. The special fault here is that the scientific displays are adorned with a profusion of murals, peepshows and pictorial symbols whose significance (except as decoration) is not made clear enough to enable them to

convey any message to the lay public, and which are a mere distraction to the serious student. The need that one feels for more explanatory labels on pictures and models is an indication that the medium employed is not always fully integrated with the purpose it serves.


One other building, besides the Dome of Discovery, has been treated frankly as a container for exhibits—an airy shed within which they can be freely disposed at various levels. This is the Lion and Unicorn building (architects, R. D. Russell and R. Y. Goodden), the most important in the downstream half of the exhibition and, on the whole, the most successful building of all, in that it is absolutely consistent throughout in taste and style. The lightly constructed envelope, with two walls wholly of glass and an arched timber roof, is essentially simple; it is elegantly proportioned and beautifully finished, especially in the detailing of the staircases and the gallery that flies from end to end of the building. The display (by the same architects together with Richard Guyatt) is equally elegant and sophisticated in a somewhat Scandinavian style.

The interior is immensely rich, almost to the point, in some places, of being visually indigestible. The side wall, for example, is faced with a delightful yellow wallpaper, flocked and patterned. This is pierced with small eye-shaped windows, superimposed on it are the royal arms woven from chains of black wooden discs and in front of it stands a complicated mural painting. The display in the gallery likewise consists of a competing array of screens, models, showcases and hanging panels bearing inscriptions which tend to compete one with the other. But since this building deals with abstract ideas and has, like the war-time exhibitions already mentioned, itself to translate them into visual terms, the designers had more excuse than most for indulging in a multiplication of decorative conceits.

The airiness and transparency of the building, in any case, and the fresh, light colours employed, enable exhibits to be arranged in a quantity that would be oppressive in a darker toned interior or between solid walls. The displays show unusual imagination and lightness of touch. A huge wicker cage, the starting-point of a flight of symbolic doves, and a lion and unicorn in plaited straw are perhaps the most charming. The building also contains a mural painting by Edward Bawden which is one of the best in an exhibition where the lavish use of murals has on the whole neither produced a high standard of art nor established it in an interesting relationship to architecture.

A completely different approach to exhibition architecture from that of the Dome of Discovery and the Lion and Unicorn building is shown by the Sea and Ships building (architects, Basil Spence and Partners), where there is no enveloping structure. The exhibits are the building. All fairly large in scale—ship models, marine engines and the like—they are disposed along the river front at various levels and surrounded by a complex system of galleries, staircases and gangways to allow the public to circulate among them. The whole structure is transparent; there are no continuous walls or floors; floating roofs are suspended from a series of lattice-steel frames.

The appearance of the whole is naturally rather complicated, and perhaps lacks unity of scale, but it is an effective piece of display and introduces a sense of design in depth that provides a welcome change from the skin-tight surfaces so prevalent in modern



Lion and Unicorn: ground and gallery floor plans scale 1/64 in. = 1 ft.

is-
ore
he
ose

een
nin
he
Y.
he
all,
le.
ass
tly
of
he
ard
uat

me
le,
ed.
on
nd
in
els,
to
ith
dy
ers
of

nd
in
or
nd
a
are
ral
an
er
ng

om
ng
ce
its
ne
at
es,
ng
us
ee-

ed,
of
a
rn

L
e
T




143

LION AND UNICORN

R. D. RUSSELL AND R. Y. GOODDEN

A steel-framed structure, carrying a lamella roof of oak (span 45 feet). The eaves curve upwards and project 7 feet 3 inches. The north and east walls are wholly of glass. Consulting engineers were R. T. James and Partners and E. Lewis. 143, the south wall from the gallery, showing the flocked wallpaper designed by Richard Guyatt and, at its foot, a painting by Kenneth Rowntree. 144, the exterior from the west. The end wall is marbled. 145, the glazed entrance front. See also photos 38, 42, 43, 78, 95, 109 and 114.



144




145


SEA AND SHIPS

BASIL SPENCE AND PARTNERS

Roofs and walls are suspended from a row of 17 lattice-steel frames of 50-foot span, varying in height from 40 to 45 feet. Staircases and gangways are mostly steel with hardwood decking. Wall surfaces (when not formed by the exhibits) are cement rendered on steel framing or aluminium. Consulting engineers, Freeman, Fox and Partners. 146, rear of building from Dome of Discovery. 147, looking across river front showing mobile water sculpture by Richard Huws. See also photos 25, 26, 27, 89, 93, 100, 102 and 123.



146



147



148

COUNTRYSIDE

BRIAN O'RORKE


Main structure is a Dutch barn with 20-foot bays. The main roof is asbestos; partitions are timber slats, stone or brick. Consulting engineers, R. T. James and Partners. 148, the exterior of the food-crops gallery, showing the green canvas louvres shading the glasshouse which forms the outer wall. They move through 90 degrees, and are operated by motor. Below are the livestock pens. 149, looking out of the open side of the Dutch barn. 150, the end of the Dutch barn, with model dairy and milk-bar. On the left is a section of the large wall painting by Leonard Rosoman. See also photos 9 and 18 and (for the stream and rock-garden immediately outside) 11 and 84.



149



150




151

LAND OF BRITAIN

H. T. CADBURY-BROWN

With the exception of the upper part of the drum of a concrete dome the whole structure (a large part of which houses machinery operating the displays) is faced externally with a landscape of rocks and stone. The north side, 152, is Yorkshire stone, in the form of outcrops on a grassy hillside. On the west is a wall of red sandstone, catching the afternoon sun. On the south (see photo 12) is square-formed Forest of Dean stone. See also 118 and 122. The display inside, 151, depicting the structure and formation of the earth, is by V. Rotter.




152



14




150



6


architecture. Its appearance of intricacy too is appropriately reminiscent of the confusion of struts and gables seen in a ship-building yard. The river front of the Sea and Ships building is marred by a painting and a work of sculpture that are among the poorest, as well as being about the largest, in the exhibition. As some compensation, in front of it is an enchanting mobile water sculpture by Richard Huws.



Sea and Ships: ground plan scale 1/96 in. = 1 ft.

The Countryside building (architect, Brian O'Rorke), like the Sea and Ships, takes the visitor back and forth on a three-dimensional itinerary, ingeniously planned. It has a pleasantly unassuming exterior, employing as great a variety of materials as the average group of farm buildings. An interesting detail is the use of vertical hinged louvres of green canvas to screen the large upper window on the side facing the Dome of Discovery. The other side is open, and the visitor in the piazza outside looks across a pleasantly naturalistic stream, bordered with grass and rushes, into a large Dutch barn. Here, as elsewhere in the exhibition, a feeling of being at the same time indoors and out adds vitality to the architecture, and the scale of the displays is skilfully adjusted accordingly.

The display in the Countryside building (by F. H. K. Henrion) is, taken all round, the most brilliant in the exhibition; there is real poetic feeling in the design of the great plaster tree, growing into the ceiling of the section entitled *The Natural Scene*, round which are stout timber galleries bearing exhibits which depict the flora



Countryside: ground and first floor plans scale 1/64 in. = 1 ft.




153, looking towards
Westminster from
within the Sea and
Ships building,
showing some of the
many open galleries
and stairs.

and fauna of the British Isles. At its foot is a woodland garden. Inside the Dutch barn the tendency to over-elaboration in display, already remarked, results in the effect of a good wall painting by Leonard Rosoman being confused by sculptured figures on the pillars and other motifs hanging from the ceiling, and in the upper gallery a straightforward layout is similarly marred by unnecessary rows of gaudy umbrellas on top of the showcases.

The Countryside building is approached by way of a sequence of galleries dealing with the Land of Britain, the entrance to which (architect, H. T. Cadbury-Brown) is through an effectively placed and imaginatively designed rock-strewn hillside, one of several instances in the exhibition of miniature naturalistic landscaping effectively used as a foil to the brittle geometry of much of the architecture. The most notable are those which, unlike the conventional town garden, which is spread out flat as a pocket handkerchief, are piled up in the angle between two walls or planted in layers, so that the effect of greenery operates in three dimensions.


The Power and Production building (architects, Grenfell Baines and H. J. Reifenberg) had a particularly difficult site, overshadowed by the rather aggressively baroque mass of County Hall and without any vantage point from which it could be seen as a whole. The architects also had the problem of providing internal lighting suitable for display but not unsuitable for the use of the machine hall as an operating factory. The building is a straightforward structure, mostly of yellow stock bricks, with an appropriately industrial character. Interest is given to the exterior by a series of projecting bays, with sawtooth




Land of Britain: layout and roof plan scale 1/64 in. = 1 ft.

roofs, glazed at the end, and to the interior by the exposed tubular steel framework, forming a pleasant roof pattern.


The remaining large exhibition building in the upstream half of the site is the Transport building (architects, Arcon). It has a bold cliff-like facade of glass, through



154, Television building, by Wells Coates, with way through beneath far end. Reinforced concrete construction; hollow tile floors; plaster walls.



gallery floor plan



Power and Production: ground and first floor plans scale 1/64 in. = 1 ft.

which the displays of aircraft in the upper sections are visible—this is particularly effective after dark—surmounted by a somewhat complicated roof structure. The glass enclosed access ramp at the end away from the river is not very happily attached to the main building. Inside there are some dramatic display effects, and some very oddly designed concrete staircases with their treads bent at right angles to form a balustrade, which are not very practical and quite unusually ugly.

Downstream the buildings change their character, being less imposing and more domestic in scale. Grouped round the same piazza as the Lion and Unicorn building, already discussed, are the unpretentious, neatly designed little Television building by Wells Coates and the Homes and Gardens building by Bronek Katz and Reginald Vaughan. The latter, a long, low structure in a pleasantly coloured brick, is planned in a number of bays to accommodate a sequence of model rooms, and opens out at intervals into small formal gardens, sunk below the level of the roadways outside.



These gardens are charmingly designed in themselves and the views into them from inside the building cleverly contrived. They are supported by some interesting trellis and other treatments on the flanking walls (designer, Gordon Cullen). The internal display packs a great many ideas, and even more products, into the space. There are some excellent qualities in both, as well as a certain amount of furniture that is not up to the high standard of design achieved elsewhere in the exhibition.

This article is concerned with buildings rather than display, and so can only mention in passing the Schools, Health, Industrial Design and People of Britain sections which are installed, usually with remarkable skill, under the arches of Waterloo Bridge approach and Hungerford railway bridge, and the Sport and Seaside sections, which take the form of open-air displays. The former (by Gordon and Ursula Bowyer) consists of a series of showcases arranged on two levels and connected by galleries and arcades. It is an intriguing piece of solid geometry, pleasant in colour and with the additional virtue of getting a great deal into a small space. The Seaside section (by Eric Brown and Peter Chamberlin), as well as showing a light touch in display, has the outstanding merit of recognizing the things that really matter in the tradition of English seaside architecture and reinterpreting them in a modern way.*

There remain to be discussed two classes of building, both of


considerable importance because they play a large part (together with the landscaping, dealt with in another article, and the use of colour and lighting) in establishing the architectural character of the exhibition as a whole: the three main entrances and the various restaurants and bars. The Chicheley Street entrance (by the Architects' Co-operative Partnership) includes a semi-circle of management offices, the upper floor of which takes the form of a series of glass-fronted boxes slung from steel bipods—an eccentric and somewhat uneconomical way of providing office space, but legitimate in this situation where an arresting form of construction provides a refreshing contrast to the staid architecture of York Road and suggests the architectural excitements to be found inside the turnstiles.

Between these offices and County Hall is the Royal Pavilion, which again seems to employ unusually complicated means to support a simple plywood roof. In this instance the result has not the same liveliness and elegance; its proportions are uncomfortably squat. Liveliness returns in the entrance itself: a row of sensitively designed pay-boxes—like abstract paintings projected into a third dimension—is surmounted by a boldly cantilevered concrete slab which makes a vigorous angular silhouette against




Sports and Seaside: ground and first floor plans scale 1/128 in. = 1 ft.

* See the Functional Tradition and the Nautical Style, page 107 of this issue.




ther
e of
r of
ious
the
e of
of a
tric
but
tion
ork
und


ion,
s to
not
om-
v of
cted
red
inst



155



156



157

POWER AND PRODUCTION

GRENFELL BAINES AND
H. J. REIFENBERG


The building consists of a large machine hall, flanked by cantilevered galleries, and a smaller show-hall for finished products. It has a structural framework of welded tubular steel with external walls of brick, concrete panels and asbestos cement. The consulting engineer was F. J. Samuely. 155, the main entrance staircase, leading direct to gallery-level, from outside the Dome of Discovery. The large windows on the right are part of a row of six, arranged in a saw-tooth pattern both in plan and section. 156, the glazed end of the show-hall for finished products, facing the river (see also photos 22 and 23). 157, the interior. The white-painted tubular steel frame is seen against a dark blue ceiling.

TRANSPORT ARCON

The building is steel framed, except for a ramp in reinforced concrete. Walls, where not glazed, are mostly of asbestos sheet. The main roof is the same. Floors are precast concrete slabs. The consulting engineer was F. J. Samuely. 158, the main glass facade facing the concourse. Railway locomotives and other vehicles are displayed in the open air beneath the first floor overhang. Aircraft are suspended from the ceiling, as shown in the interior, 159, of the main display hall. The photograph shows the two types of stair used throughout the building, both composed of precast concrete units cantilevered either side of a central spine. The example on the left has a plated steel balustrade; that on the right includes a concrete balustrade as part of the same casting. See also photos 1, 14, 16, 20 and 28.



158



159



160




161


SPORT

GORDON AND
URSULA BOWYER

A series of kiosks, some independent, others linked. Part of the display, on an upper level, is viewed from a raised platform of caulked teak strips, partly protected by canvas awnings. These can be seen in 160, a broadside view of the display looking towards the river across the athletic arena. 161, one of the independent kiosks, with canvas roof laced to a tubular frame. See also photos 54, 83, 92 and 139. The consulting engineer was Lawrence Kenchington.



162



163

ENTRANCE SCREEN

ARCHITECTS'
CO-OPERATIVE
PARTNERSHIP

Between the Fairway piazza and York Road. It is of welded tubular steel with coloured canvas panels (about 1,000 in number) arranged in a diagonal pattern. Consulting engineers, Ove Arup and Partners. 163, the screen illuminated at night, showing also the café (bottom left), the terrace of information and other bureaux beneath the screen and the kiosks in front of it, on platforms poised over pools of water. 162, a detail (in daylight) of one of these kiosks. See also photos 7, 8, 10, 21, 91, 99, 101, 110 and 133.



164

51 BAR

LEONARD MANASSEH

This bar and terrace are at first floor level, built above a rectangular brick and reinforced concrete building containing lavatories and an electricity sub-station. At one end (away from the river) rises a 5,000-gallon steel-framed water-tower. Consulting engineers were Freeman, Fox and Partners. 164, from the east, showing the water-tower at left, the access by open steel stair and the terrace at right, with bambooscreens and cane pergola on alloy tubing. 166, the exterior at night. The sculpture is by Daphne Hardy. 165, interior of the bar, looking towards the river. See also photos 24, 105 and 115.



165



166

E


TS'
IVE
HIP



164



130



167, reinforced concrete canopy over Chicheley Street entrance: Architects' Co-operative Partnership. It shelters four double pay-boxes, framed out of standard aluminium extrusions.

the sky and provides a first-rate example of the drama that is waiting to be extracted from modern methods of construction.

The same architects designed the screen backing on to York Road. It rises above a terrace of information and other offices, in front of which is a series of little kiosks hung over pools of water and terminating in a small restaurant. These, together, form a charming piece of design, right in scale, elegant in construction and making good use of water and subtle changes of level. The three-dimensional harlequin design of canvas panels decorating the screen of tubular scaffolding is one of the most successful bits of exhibitionism on the South Bank.


By contrast the Waterloo Station entrance gate (architects, Sir John Burnet, Tait and Partners), which also has a restaurant attached, is very heavily handled. There is nothing intrinsically unsatisfactory about the idea of a series of laminated timber arches with a roof suspended from them, but it needs to be carried out with a precision and delicacy lacking in this instance. The detailing is coarse, especially that of the viewing platforms and stairways facing the main concourse. The heavy, insistently rectilinear, elevation to York Road is reminiscent of the modernism of the 1930's and provides an encouraging reminder of the warmth and sensitivity that the modern movement has acquired since then.

The other main entrance (the Waterloo Gate by Fry, Drew and Partners) is much more delicately handled, and the precipitous descent from the high level to the level of the exhibition grounds has been cleverly exploited. The various ramps, stairs and canopies, and the slender footbridge leading across the boating pool to the concert-hall terrace, make an intriguingly complex pattern of horizontal planes and show (in contrast to the Waterloo entrance just referred

to) how elegant a material reinforced concrete, imaginatively used, has now become. The engineers were Ove Arup and Partners.

Of the restaurants and bars, the four most interesting are the '51 Bar alongside County Hall, the Regatta Restaurant, which also forms the landing platform at the end of the Bailey Bridge, the Thames-side Restaurant beneath Waterloo Bridge and the Harbour Bar. In addition the small Turntable Café carved out of the arches of Hungerford railway viaduct should be mentioned not only for its skilful planning on different levels and its admirable lettering,* but because it contains a mural painting by Julyan Trevelyan which is one of the best in the exhibition.

The '51 Bar (architect, Leonard Manasseh), though modest in size and obscurely situated, is a most elegant and sophisticated design. Raised on a platform provided by one of the service blocks, it consists of a small foyer and bar and a large roof terrace decorated with, and lighted from, a cane pergola. The Regatta Restaurant (architects, Misha Black and Alexander Gibson) is more ambitious internally, but surrounded as it is by the spec-




plan of '51 bar scale 1/32 in. = 1 ft.


tacular architecture of large exhibition buildings, has rightly been kept very simple externally, being an unassuming, pleasantly proportioned arrangement of flat walls and wide windows, surrounded by elegantly detailed stairways and terraces, one of which is cantilevered over a delightful garden and shelters a little outdoor bar. Inside the Regatta Restaurant much play is made with decorative motifs based on crystal structures. A designer is entitled to use any motif that comes his way, but its merit lies solely in what he makes of it. The patterns displayed here are most interesting when they are furthest removed from their crystallographical starting-point, and it shows some confusion of thought on the part of the Council of Industrial Design, whose purpose it is to encourage the use of good designers (not to suggest that science can do the work for them) that the Council should have sponsored this somewhat naively conceived exposition of a not altogether new idea.

* See page 121.


168, inside the Waterloo Station entrance gate (by Sir John Burnet, Tait and Partners). The building also contains offices, a restaurant and lavatories. 169, the elevation to York Road.




168




169




170, interior of the Press Room, occupying the northern end of the Regatta Restaurant on the ground floor. Designer, Misha Black.



second floor plan scale 1/96 in. = 1 ft.



first floor plan scale 1/96 in. = 1 ft.



Regatta Restaurant: ground floor plan scale 1/64 in. = 1 ft.


The Harbour Bar is the nearest thing on the South Bank to a continental terrace café. Slightly raised above the pavement and facing the boating pool, it has the traditional striped awning and particularly well-thought-out interior detailing, the work of Ward and Austin who also designed the interior of the Thames-side Restaurant. The building in each case is the work of Fry, Drew and Partners. The special merits of the Thames-side Restaurant from the planning point of view, with its boardwalk bringing visitors into the closest possible contact with the river, are discussed elsewhere in this issue.* It is pleasantly detailed inside and out and its lightly constructed undulating roof makes an interesting contrast with the massive concrete above as it disappears beneath one of the land arches of Waterloo Bridge.

Finally, there are two incidental buildings, of a high quality of design, which must not be overlooked. Edward Mills's thoroughly workmanlike administration building with external gallery access alongside Waterloo Bridge approach—it happily combines the straightforward character demanded by its utilitarian function with a lightness and a sparkle that enables it to provide a sufficiently festive background to the exhibition scene—and Wells Coates's Telekinema. The design of the latter involved special planning problems of a kind not normally presented to an architect. They are too complex to be described here, but seem to have been solved most successfully. The various levels inside are interestingly expressed elevationally. It is not a showy building; indeed it does everything asked of it with a deceptive appearance of ease—always a sign of a well-considered design—and is in fact one of the most mature pieces of architecture in the exhibition.

A word of praise should also be given to the 1851 Centenary Pavilion, a miniature Crystal Palace mounted on a Victorian gothic cast-iron staging. It has been charmingly designed, with just enough period character—faintly ironical without being disrespectful—by Hugh Casson and James Gardner, and skillfully linked to the base of the old Surrey Shot-tower. The latter, after years of public disregard, has had the attention of all London focused on it while it plays the important role of a campanile, setting off the horizontal roof-lines of the various downstream enclosures. It emerges from the ordeal as full as ever of vigour and assurance. It has equal value, regarded as a vertical feature, with Powell and Moya's Skylon which dominates the upstream section, the one an example of the real architectural distinction that often emerges from the solid functionalism of early nineteenth-century engineering, and the other a first-rate demonstration of the romantic potentialities of twentieth-century building science, imaginatively exploited.


In conclusion the general verdict can be confidently pronounced that with only one or two exceptions the buildings throughout the

exhibition maintain a very high standard of planning and design, and a remarkable consistency of style considering the number of architects employed—a tribute to the single-mindedness and diplomacy of the co-ordinating architects, Hugh Casson and Misha Black. The only reservation one feels inclined to make is that though a consistent idiom is admirable up to a point it is irritating when it involves the repetition of the same design cliché. Every other building on the South Bank uses somewhere a rubble stone wall as a foil to smooth concrete or glass, and contains somewhere one of those fashionable raking stairs; a stair, that is, in which the string is not at right angles to the line of the treads. But these are minor matters beside the general stimulus likely to be given to design by the fact that on the South Bank, for the first time, the public can move around in a landscape that could belong to no other age than the present.



171, the 1851 centenary pavilion, by Hugh Casson. It is raised on a concrete slab, supported by cast-iron columns and linked by a gallery to the interior of the old shot-tower.

* See page 100.



n,
of
d
a
at
g
y
e
e
e
e
o
e
o



172

HARBOUR BAR

*FRY, DREW AND PARTNERS
(INTERIOR: WARD AND AUSTIN)*

A semi-open-air bar and buffet, constructed mainly of tubular steel uprights and very light tubular steel lattice trusses supporting a red and white striped canvas roof. See also photos 56, 82 and 138. 172, the bar from the direction of the river, showing in the background the Waterloo gate and observation tower by the same architects (also illustrated in photos 55, 58, 97 and 112). It consists of an arrangement of platforms, stairs and ramps in reinforced concrete, including a post-stressed concrete bridge in four spans, some as much as 76 feet, but with a structural beam nowhere exceeding 22 inches in depth; also a steel and glass tower containing a lift. The consulting engineers were Ove Arup and Partners.

REGATTA RESTAURANT

MISHA BLACK AND ALEXANDER GIBSON


Seats about 500. There are also open terraces and an outdoor bar, 173, beneath one wing of the restaurant, looking on to a garden (see photos 75, 76, 108, 113 and 116). 174, from the concourse. The stairs on the right lead to the Hungerford Bridge entrance. 175, the entrance hall from the riverside promenade, with painting by John Tunnard. 176, the top of the staircase leading to the main first-floor restaurant. See also photos 74, 77 and 137.



173




174



175



176



177



178

THAMES-SIDE RESTAURANT

FRY, DREW AND PARTNERS

The building extends beneath Waterloo Bridge and follows in plan the curve of the new river wall. Its riverside elevation is completely glazed and outside it is a boardwalk, with room for one row of tables, overhanging the water and sheltered by a canvas awning. The main restaurant has an undulating roof consisting of a continuous 2-inch aluminium and cork sandwich slab used as a series of arches and inverted arches. It has a span of 27 feet and is supported on 3-inch steel tube columns. Engineers, Ove Arup and Partners. 177, the landward side. 178, the interior. 179, the boardwalk, 180, looking through the glazed river front. See also photos 61, 63, 64, 80, 88 and 104.



179



180



181


ADMINISTRATION

EDWARD MILLS

A long narrow four-storey steel-framed structure on the eastern boundary of the exhibition, containing offices, canteens and so on, all reached from external galleries. Floors are of reinforced concrete on steel joists and external walls hollow terra-cotta blocks rendered. Balustrades are wrought-iron tubes with coloured canvas panels. On the roof is a tank room and observation post with a central flag-pole. Consulting engineers, R. T. James and Partners. 181, the elevation to the exhibition. For the decorated screen on the right, see photos 98 and 103.


SOUTH BANK TRANSLATED

The County of London Plan envisaged the development of the South Bank as an integral part of Central London. The temporary use of part of the site for the Festival has demonstrated some of the possibilities of the site and opened our eyes to the form this permanent development could take. On these pages Gordon Cullen suggests a translation of the planning conceptions (that have made the South Bank exhibition so successful) from the Exhibition to everyday London.



1939

When the Festival of Britain has run its course the South Bank site of 27 acres will become what might be described as a planner's vacuum. But not entirely, since the Royal Festival Hall has already been built, the National Theatre is to go alongside it and Government accommodation will straddle the upstream section. But these are zoning proposals and cannot tell us about the nature of the development. In the 'thirties new building became a battleground on which the modern style of architecture struggled to establish itself. The Government-sponsored South Bank exhibition shows how well this battle is now going. Today's new building projects must become a battleground for modern planning. The first salvo in this new battle has been fired in this same South Bank site, and the preceding pages of this issue will have demonstrated how effectively some of the best principles of modern planning, or Townscape as its visual aspect is called, are employed there; how buildings and the space and floor which they enclose or bound are regarded TOGETHER to produce scenes and progressions of emotional value. This article attempts, very simply, to translate this planning conception from EXHIBITION into a permanent part of everyday London.



1951


The plans alongside show:

1939 The river bank is industrial, based on river transport. The Surrey Lead Works is marked by its shot-tower. Behind this zone lies a mass of small streets of two and three storey houses.


1951 The County of London Plan reserves the area as a cultural and office zone. The war has helped to clear the site and the exhibition stimulates the erection of the Royal Festival Hall and embankment. Some of the roads, the bridges and the shot-tower (and of course the river) are all that remain of the old pattern. The new pattern is one of meandering quadrangles.

The Future


Government offices, conference rooms and hostels; a large hotel and the National Theatre are the main buildings envisaged to replace the exhibition. Although the exhibition pattern is retained the density of building is greatly increased in the scheme put forward herewith.



The Future



Entrance from York Road




General view of hotel area (traffic routes shown in yellow).

HOTEL ZONE

Entering the site from York Road at what is now the Chicheley Street entrance to the exhibition there will be a courtyard flanked on the left by a garden and on the right by hotel ancillaries such as grill room, ball-room and shops. The courtyard will be a drive-in for hotel traffic but with pedestrian priority. Interest at eye level (the lack of which renders so much of London

a bore) is thus provided by garden, paving, shops and restaurants. The exit from this square in the direction of the river is, as at present, a concealed narrows (see page 81) but is accentuated by providing a covered way in the form of a tunnel running between hotel and public house. This preserves the feeling of enclosure and at the same time emphasizes the point of exit.

Exit from hotel courtyard to main square






View along the Piazza to Whitehall Court


PIAZZA

A purely pedestrian area (occupying part of the present main exhibition concourse) flanked on the west by Government buildings and on the east by cafés. As at present Whitehall Court, across the river, provides the fourth wall of the enclosure brought more sharply into focus by the raised terrace which cuts out the intervening river. It is proposed to keep the Regatta Restaurant on the river front.


The two drawings on this page show the contrast of scale aimed at in this area. The cheerful and intimate nature of the cafés on the one side and the lofty, sculptural effect on the other.




A flashback to the review scheme, 'South Bank Regained' (A.R., January, 1949). A similar arrangement is again proposed for the riverside development in the present scheme.



View from the cafés to the Government centre (including conference rooms and hostel for distinguished visitors) raised to provide car parks below.



The Seaside section of the South Bank exhibition which it is proposed to preserve in this REVIEW scheme for the permanent development of the area.





Aerial view of zone looking north

ROYAL FESTIVAL HALL AND NATIONAL THEATRE ZONE


It must be pointed out at the start that the proposals shown here are put forward on its own responsibility by the REVIEW, and are not based on official schemes.

The proposals involve the siting of the National Theatre right on the river wall. There are in fact only two possible alternative sites for the building: either on the river or set back to line up, approximately, with the façade of the Royal Festival Hall. The latter position cuts up the available open space into two pieces when it would seem desirable to increase the sense of space on a small site by making one large courtyard and utilizing the space of the river itself. It would further have the effect of establishing a linear development along the river bank which may be desirable with a continuity of building but may not be so successful with the axial monumentality already established. If, as we hope, Hungerford Bridge becomes pedestrian, then a meandering causeway linking it to Waterloo Bridge at high level would bring the pedestrian to any desirable point of the site in all weathers. (An important consideration in the attempt to popularize the South Bank after the Festival has closed.) The Thames-side restaurant would be kept, and approached as at present along the embankment, but under the overhang of the National Theatre. Also preserved is the Seaside Section, the only change being the substitution of shops for the exhibition displays. The courtyard which gives access to both the Royal Festival Hall and the National Theatre, would be treated as a water.square; out of the water rises the shot-tower.

Below, left, a view looking towards the National Theatre from inside a glazed, all-weather causeway, which, it is suggested, should link Hungerford and Waterloo Bridges. Below, right, the National Theatre overhanging the river bank near Waterloo Bridge and the catwalk leading to the Thames-side restaurant.



Plan for Asphalte



Carriageways . . . roads . . . car parks and playgrounds . . . they all call for asphalte . . . and asphalte means Val de Travers. For nearly eighty years this famous firm has been developing new techniques in asphalte construction. And now, with a group of Associated Companies and branches throughout the country, their knowledge, experience, and general resources make them pre-eminent in this field.

ACTIVITIES

of the Company and its Associates

• ASPHALTE MINE OWNERS in Germany and Sicily • QUARRY OWNERS • ASPHALTE CONTRACTORS • TAR PAVIORS • TARMACADAM MANUFACTURERS • ASPHALTE GROUT MAKERS • TAR SPRAYERS • ROAD LINE PAINT SPECIALISTS • HARD TENNIS COURT and PLAYGROUND CONSTRUCTORS • VALCO-THERM TILE MANUFACTURERS.



VAL DE TRAVERS

The name that stands supreme for product and service

THE VAL DE TRAVERS ASPHALTE PAVING COMPANY LIMITED
VAL DE TRAVERS HOUSE, 21 - 22 OLD BAILEY, LONDON, E.C.4

Telephone: City 7001 (10 lines) • Telegrams: Traversable, Telex, London

ASSOCIATED COMPANIES

A. C. W. HOBMAN & CO. LTD. TARROADS LTD. THE DIAMOND TREAD (1938) LTD.
THE LONDON ASPHALTE CO. LTD. SICILIAN ROCK ASPHALTE CO. LTD. UNITED
LIMMER & VORWOLFE ROCK ASPHALTE CO. LTD. W. G. WALKER (GLASGOW) LTD.

BRANCHES

BIRMINGHAM • CANTERBURY • EXETER • GLASGOW • LINCOLN
LIVERPOOL • MANCHESTER • NEWCASTLE-ON-TYNE



A flat roof is as watertight as its joints.

The problem of making watertight expansion joints in flat concrete roofs can be solved by the use of Expandite rubber waterstops.

These waterstops were developed in the first place for sealing joints in hydraulic structures and are widely used by hydraulic engineers.


Three different sections are available, and, as shown in the illustrations below, the complete joint consists of the

waterstop, Flexcell cane fibre joint filler, and a surface seal of one of the Expandite rubber-bitumen sealing compounds.


This is but one example of the general problem of sealing joints where there is movement. Government, Consulting and Municipal Engineers are constantly sending us drawings and asking for our suggestions on the treatment of joints in all types of structures. Can our Technical Department be of assistance to you?

Sealing 'joints which move' is our speciality.


TYPE A TO ACCOMMODATE EXTREME MOVEMENT IN TENSION OR SHEAR



TYPE B FOR JOINTS WHERE RELATIVELY LESS MOVEMENT IS ANTICIPATED



TYPE C A MORE ROBUST SECTION FOR JOINTS WITH COMPARATIVELY SMALL MOVEMENT



EXPANDITE LIMITED

**CUNARD ROAD,
LONDON, N.W.10
ELGAR 5151**

Recipe for Good Design

To The Leading Men of Manchester. Are you to be remarkable in all that renders manufacture useful in material, perfect in completion and wonderful in despatch, and yet slavishly bow down to the earth before France—humbly beg *her* to design your patterns, and gratefully pay *her* whatever in *her* superiority, she may choose to demand? Shall England kiss the ground before her rival any longer with feudal humbleness, year after year, month after month, day after day, hour after hour; when by the same judicious efforts which have given France her rank, you can place yourselves on the same level, and then rise above it?

Surely one of the greatest anomalies of the period is that Manchester should be without a School of Design! Why should Manchester be without? What has raised Lyons to her just superiority in taste? I appeal to you all, gentlemen, to read the examination before the committee of the master manufacturers. I appeal to you all to dwell on the bitter complaints made by master and mechanic of the want of instruction—the *only want*.

We can beat other nations, say they, in production—we can beat them in material, but in taste, in design, we are vastly inferior; and it came out in the evidence, that where we had proved equal and superior was in that very branch wherein the masters had procured instruction for the apprentices.

* * *

In a nation so celebrated for common sense as the English—in a town so distinguished for capital and diligence as Manchester—what plausible pretext can be urged against the establishment of that which has given superiority to our neighbours? So that, first, the mechanic should begin by learning to draw the figure, as in Lyons—the elements of all design being the same, whether for the artist or the artisan; secondly, that when he could draw the human figure competently, and when, by the examination of competent persons, he is pronounced competent, he should proceed to the ornamental school (more particularly *his* necessity), that, having begun with the most difficult, he will proceed with the least so with comparative pleasure. Having given evidence of power in drawing the figure, and then the ornamental, he should proceed to chemistry and colour, its principles and its combinations, and botany, in as far as the difference, species, and forms of plants are concerned; then will be required, first, lectures on anatomy and design, second lectures on ornament, colour and botany; thirdly, instructions how to apply the acquired knowledge to manufactures.

* * *

There is no easy way of attaining greatness in anything; and it is not the least extraordinary characteristic in both English and French, that the one, gay, thoughtless, and volatile, without common sense, should conduct their design in art and manufactures with the greatest degree of it; and that the other, distinguished by this characteristic should, in the practice of the arts, give proof of no common sense at all.

Allow me to warn you, as I have warned the government before; suffer not *your* school to be rendered ineffectual by pompous pretence, or ingenious and malicious affectation of superior knowledge.—What is the first requisite in design? The figure.—What the next? The figure.—What the third? The figure.—Without that knowledge, your skill in colour, in chemistry, in botany, in ornament, as applied to design, will be useless; you will spend your money, raise your buildings and pension your instructors, in vain, and find yourselves, after thousands are gone, little more advanced than when you subscribed the first guinea. That Manchester may keep her capital to reward her own genius, and the genius of her own country, by founding a sound and practical school of design, based on no narrow views, no paltry envies, no mean apprehension, but open to all whom God has gifted—high or low, rich or poor, the refined artist, and the modest mechanic—is the constant hope and earnest desire of your grateful and obedient servant,

BENJAMIN ROBERT HAYDON (*The Manchester Guardian*, September 13, 1837).

South Bank Architects

The South Bank exhibition, illustrated on the preceding pages, is the work of a large number of architects, of whom portraits and brief biographical notes are given herewith. The series starts with the architect-members of the Presentation Panel, who laid out the site and co-ordinated the designs of the various buildings; it continues with the landscape architects and consultants and concludes with the architects of the individual buildings.



HUGH CASSON, Director of Architecture, Festival of Britain: member Festival Presentation Panel: responsible for layout of downstream section, South Bank Exhibition and 1851 Centenary Pavilion: born 1910; trained Cambridge; private practice from 1937 with the late Christopher Nicholson: Camouflage Officer, Air Ministry 1940–44; Technical Officer, Ministry of Town and Country Planning 1944–46: since then in private practice.



MISHA BLACK, OBE (right), member Presentation Panel: responsible for layout, upstream section: Chief Display Designer, Dome of Discovery, Architect in conjunction with Alexander Gibson of Regatta Restaurant, Embankment Gate, and decoration of Bailey Bridge: born 1910: designer of Steel, Coal, Shipbuilding and Public Welfare Halls, UK Pavilion, Empire Exhibition, Glasgow, 1938: Designer, MARS Group Exhibition, 1938, Public Welfare and Maritime Halls, British Pavilion, World's Fair, New York, 1939: Principal Exhibition Architect, Ministry of Information, 1940–45: Director Design Research Unit since 1946. Exhibition consultant to UNESCO. Alexander Gibson (left) was trained at the AA: worked with Gropius and Fry and Norman and Dawbarn: joined DRU 1948.



3 **RALPH TUBBS**, member Presentation Panel and architect Dome of Discovery: born 1912; trained AA; Secretary MARS group in 1939; member of Council and Executive RIBA between 1944 and 1950; vice-president AA 1945-47; most recent work, Indian Students' Union and Hostel under construction at Fitzroy Square, W.1.



4 **JAMES GARDNER**, OBE, member Presentation Panel, Co-ordinating Display Designer, Downstream Section, Display Designer People of Britain and Centenary Pavilion: born 1907; after art school course spent six years designing jewellery, later general publicity work; during war years Chief Development Officer camouflage for Army; Chief Designer 'Britain Can Make It' Exhibition; responsible for 1951 display in Main Hall, Olympia Ideal Home Exhibition; Chief Designer Festival Pleasure Gardens, Battersea Park; industrial design work for BEA including aircraft interiors.



5 **JAMES HOLLAND**, member Presentation Panel, Co-ordinating Display Designer for Upstream Section, Joint Display Designer (with Basil Spence) for Sea and Ships Pavilion, Co-ordinating Designer for Festival Ship 'Campania,' head of Festival Office Design Section: born 1905; trained Royal College of Art; worked on Peace Pavilion, Paris Inter-


national Exhibition 1937; murals and display treatment UK Pavilion, Glasgow Exhibition 1938 and New York World's Fair 1939; joined Exhibitions Division MOI 1943; Chief Designer (Exhibitions) COI, 1947.



6 **H. F. CLARK**, general landscape consultant: born 1902; in private practice with Christopher Tunnard until 1939; Consultant Landscape Architect to Holborn Borough Council (reinstatement of the Bloomsbury Squares, St. Giles Churchyard Garden and playground) 1947. Consultant to Stevenage Development Corporation since 1948; from 1946 Lecturer in Landscape Architecture at Reading University and the Department of Civic Design, School of Architecture, Liverpool University.



7 **H. T. CADBURY-BROWN**, architect for main concourse and surrounding area in upstream section, The People of Britain and the Land of Britain: born 1913; trained AA 1930-35; began private practice in 1937; won competition for British Railways Town Office 1937 and for Central Feature, Women's Fair at Olympia, 1938; served Royal Artillery 1939-45; taught at AA 1946-48; recent work for CID and Harlow New Town Corporation; member RIBA Town Planning and Public Relations committees.



8 **PETER SHEPHEARD**, Landscape

Architect, Downstream Section: born 1914; trained Liverpool; 1937-40 assistant to D. L. Bridgewater; 1940-43, Ministry of Supply, Royal Ordnance Factories; 1943-44 with Sir Patrick Abercrombie's staff on Greater London Plan; 1945-47, Ministry of Town and Country Planning working on Stevenage master plan; 1947-48, Deputy Chief Architect, Stevenage Development Corporation; 1948 onwards in partnership with D. L. Bridgewater working on housing (including work at Lansbury), schools and landscaping; Member of Councils of RIBA, ILA and AA.



9 **R. D. RUSSELL** and **R. Y. GOODDEN**, architects Lion and Unicorn, and Unicorn Café: R. D. Russell, trained AA 1924-27; with Gordon Russell Ltd. 1928-34; staff designer Murphy Radio 1936-42; ship camouflage RNVR 1942-46; RDI 1948; professor in charge, School of Wood, Metals, Plastics, RCA. R. Y. Goodden, trained AA 1926-31; consultant industrial designer, glass, silver and pottery 12 and private architect 1932-39; radar operator RAF and ship camouflage RNVR 1940-45; private practice 1947; RDI 1948; professor in charge, School of Silversmithing and Jewellery, Department of Industrial Glass, RCA.



10 **ARCHITECTS' CO-OPERATIVE PARTNERSHIP**, architects of Administrative Offices, Royal Pavilion, Chicheley Street Entrance, York Road Screen, information and lost property offices, kiosks, etc., Fairway Café, and Minerals pavilion: C. K. Capon, P. L. Cocke, M. H. Cooke-Yarborough, A. W. Cox, L. M. De Syllas, J. M. Grice, M. A. R. Powers; partnership formed in 1939

with eleven partners all qualified in that year at AA; responsible since war for Bryn Mawr Rubber Co.'s factory, South Wales, research programme on hospital design for St. Albans and Mid-Herts Hospital Board, prefabricated schools for Herts and Derbyshire County Councils and Coventry and Sheffield City Councils; whole partnership does part-time teaching at AA.





11 **W. WELLS-COATES**, OBE, architect Television building, Telekinema and interior of Royal Pavilion: born Tokio 1895; joint BA, BSc (Engineering) McGill University; war service 1915-19, research degree, engineering, London University; 1928, private practice, London; early work, BBC Studios Broadcasting House, Cresta Shops; founder-member MARS group 1933; in charge Fighter Development RAF 1940-45; RDI 1944; resumed private practice 1945.



ERIC BROWN and **PETER CHAMBERLIN**, architects and designers of The Seaside. Eric Brown is head of the Department of Architecture, Kingston School of Art and Peter Chamberlin is deputy head.

[continued on page 141]

LIA
 itect
 and
 born
 gin-
 vice
 ring,
 vate
 BBC
 esta
 roup
 ment
 med
 ER
 and
 own
 chi-
 and
 ed
 ice
 's
 o-
 St.
 cal
 or
 ty
 ld
 ip
 41



Central fitting for the Royal Pavilion,
 designed by A. B. Read, R.D.I.,
 A.R.C.A., F.S.I.A., Director of Design.

Light ON THE FESTIVAL SCENE


We supplied to the Festival Exhibitions more than five thousand electric lighting fittings, either of special design, or chosen from our Mondolite, Tubalux, Ultralux and Versalite ranges.
 In addition we were chosen as the contractors for the main portion of the electrical installation at the South Bank Site.

TROUGHTON & YOUNG LTD

143 KNIGHTSBRIDGE, LONDON, S.W.1.

TELEPHONE: KENSINGTON 8881 (15 LINES)

THE ROYAL FESTIVAL HALL



After the shouting has died down and the Festival of Britain is over, it is intended to clear the whole of the South Bank Site, with one exception. The Royal Festival Hall is to remain—a permanent reminder of the Festival's glories and a tribute to those men of vision and imagination who gave our greatest city a Concert Hall worthy of its musical traditions.

The Neuchatel Asphalt Company Limited is proud to have been associated with the erection of this magnificent building, and has been responsible for the whole of the flat roofing. This consists of three layers of Nacofelt Built-up Bituminous Roofing with a grit finish. All areas subject to foot traffic are protected with Nacorecrete screed divided into 4' 0" by 2' 0" rectangles, the joints being filled with a bituminous composition. The gutters are lined with asphalt.

To end this display of trumpet virtuosity we should like to add that we have surfaced all the roads at the South Bank Site, approximately 45,000 yards of black, red and green asphalt laid under very difficult conditions.

THE NEUCHATEL ASPHALTE COMPANY LTD.

Head Office: 58 Victoria Street, Westminster, London, S.W.1.

Branches at Glasgow, Edinburgh, Manchester, Newcastle, Birmingham, Portsmouth, Plymouth, Frome, Belfast



13 **B. KATZ and R. VAUGHAN**, architects Homes and Gardens: B. Katz, born 1913: trained Technical University, Vienna 1935: worked with Gropius and Fry in England 1936-39: DCRE's Office, London, West Area, 1940-42: designed exhibitions for MOI and MOS 1943-45: appointed exhibition consultant to UNESCO, 1947: R. Vaughan, born 1906, trained AA: Architect to Municipality of Penang for three years: Chief Assistant Maxwell Fry and later to Gropius and Fry, 1933-38: served RE 1939-45.




14 **POWELL and MOYA**, architects of Skylon: Philip Powell, born 1921: trained AA 1939-43: worked in office of F. Gibberd: part-time teacher Kingston School of Art 1947-49. Hidalgo Moya, born 1920: trained AA 1939-43: worked in office of F. Gibberd: part-time teacher AA 1947-48: partnership together since 1946 (with Michael Powell who left to become Assistant Housing Architect, LCC in 1950) and won competition for Westminster City Council's Pimlico Housing Scheme 1946.



15 **G. GRENFELL BAINES and H. J. REIFENBERG**, architects Power and Production pavilion: G. Grenfell Baines, born 1908: after working as junior in office of rating surveyor and valuer from 1923 became junior draughtsman with Lanes. County Architect: trained at night school

and later Manchester University: won Southern Rhodesia Parliament House competition, 1937: now in partnership working as planning consultants of Aycliffe and Peterlee. H. J. Reifenberg, born 1904: graduated Berlin Technical University, 1922: private practice in Berlin, 1924. Came to England 1938 and became British subject.



16 **EDWARD MILLS**, architect Administration Building: born 1915: trained Regent Street Polytechnic: worked in offices including Maxwell Fry's and Gropius': private practice since 1936: worked in India, Nigeria, W. Africa, S. Africa: buildings include Factory Canteen and New Process Building, Dagenham, Flats at Hackney, St. Helier Methodist Community Church, etc.: research work includes design of modern chemical laboratories, low rental housing and slum clearance.



17 **MAXWELL FRY and JANE DREW**, architects Waterloo Entrance, Harbour Bar, Thames-side Restaurant: Maxwell Fry, born 1899: trained Liverpool University School of Architecture: partnership 1927-34: with Gropius 1934-36: practised alone 1936-39: war service in War Office and RE West Africa: Town Planning Advisor, West Africa, 1943-45: returned to England setting up partnership with his wife (Jane Drew): works include flats for Lewisham Borough Council and Harlow New Town, Ibadan University, Nigeria, Hospital and Schools at Kuwait: member Royal Fine Art Commission. Jane Drew, born 1911: trained AA: partnership with J. T. Alliston from 1934-39: during war designed aircraft factories, and research in kitchen planning: chairman RIBA exhibition 'Rebuilding Britain', 1943: Assistant Town Planning Advisor to the Resident Minister, West African Colonies 1944-45: first woman council member AA and ARC: now designing hospitals, flats and school in West Africa: editor 'Architects' Year Book.'



18 **GORDON and URSULA BOWYER**, architects of Sports Section: Gordon Bowyer, born 1923: trained Regent Street Polytechnic School of Architecture 1940-44: architectural and industrial design assistant 1944-46: taught at Regent Street Polytechnic 1946-48: private practice since 1948, mostly exhibition work. Ursula Bowyer, born 1926: trained at Regent Street Polytechnic 1942-46: worked as architectural assistant 1946-49: in partnership with her husband since 1949.



19 **BASIL SPENCE**, architect Sea and Ships: born 1907: trained at Schools of Architecture, London and Edinburgh Universities: worked with Lutyens for year: designed Scottish pavilions, Glasgow Exhibition, 1938 with T. S. Tait: Chief Architect, 'Britain Can Make It' Exhibition, 'Enterprise Scotland' (1947): at present working on housing at



20 **ARCON**, architects Transport Pavilion: Rodney Thomas, trained University College, London, School of Architecture 1919-22: studied painting at Slade: private practice 1931-39: partnership with Raglan Squire 1941-43: founder-partner Arcon 1943, in charge of the unit responsible for Transport building. Edric Neel, trained Cambridge School of Architecture, 1932-35: worked with W. Wells-Coates 1935-37: private practice 1937-39: architect-

Sunbury-on-Thames, Dunbar and Selkirk, three schools, a shopping centre and a theatre reconstruction.



23 **LEONARD MANASSEH**, architect of '51 Bar: born 1916: trained AA: CRE North London and private firms working on canteens, kitchens, aircraft factories, etc.: 1943-46, pilot, Fleet Air Arm: 1946-48 under C. H. Aslin, Herts County Architect, on police housing and schools: 1948-50, a Senior Architect with Stevenage Development Corporation, designs for Town Centre, housing, shops, etc.: won competition for Luxury Restaurant, South Bank Exhibition (abandoned for economy): 1950, Director of Preliminary School AA.




24 **GORDON TAIT**, architect Station Gate: born 1912: trained AA: partnership with Sir John Burnet, Tait & Partners since 1939: served as pilot RAF during war: pre-war work largely on Glasgow Exhibition 1937-38: at present engaged on three schools, 300 London flats, a nursing home and maternity hospital, Scotland; a large City office block and a bank in Portsmouth.



21 **ARCON**, architects Transport Pavilion: one of founders of Arcon partnership, 1943: member Board of Assoc. for Planning and Regional Reconstruction, and of School Planning 1945-49: A. M. Gear, trained Nottingham University School of Architecture 1929-31: worked in various offices in Nottingham and later London: during the war with Professor Holford and Sir Alexander Gibb and Partners: joined Arcon 1943, partner 1946.

THE ROYAL FESTIVAL HALL



After the shouting has died down and the Festival of Britain is over, it is intended to clear the whole of the South Bank Site, with one exception. The Royal Festival Hall is to remain—a permanent reminder of the Festival's glories and a tribute to those men of vision and imagination who gave our greatest city a Concert Hall worthy of its musical traditions.

The Neuchatel Asphalte Company Limited is proud to have been associated with the erection of this magnificent building, and has been responsible for the whole of the flat roofing. This consists of three layers of Nacofelt Built-up Bituminous Roofing with a grit finish. All areas subject to foot traffic are protected with Nacorete screed divided into 4' 0" by 2' 0" rectangles, the joints being filled with a bituminous composition. The gutters are lined with asphalt.

To end this display of trumpet virtuosity we should like to add that we have surfaced all the roads at the South Bank Site, approximately 45,000 yards of black, red and green asphalt laid under very difficult conditions.

THE NEUCHATEL ASPHALTE COMPANY LTD.

Head Office: 58 Victoria Street, Westminster, London, S.W.1.

Branches at Glasgow, Edinburgh, Manchester, Newcastle, Birmingham, Portsmouth, Plymouth, Frome, Belfast



13 **B. KATZ and R. VAUGHAN**, architects Homes and Gardens: B. Katz, born 1913: trained Technical University, Vienna 1935: worked with Gropius and Fry in England 1936-39: DCRE's Office, London, West Area, 1940-42: designed exhibitions for MOI and MOS 1943-45: appointed exhibition consultant to UNESCO, 1947: R. Vaughan, born 1906, trained AA: Architect to Municipality of Penang for three years: Chief Assistant Maxwell Fry and later to Gropius and Fry, 1933-38: served RE 1939-45.



14 **POWELL and MOYA**, architects of Skylon: Philip Powell, born 1921: trained AA 1939-43: worked in office of F. Gibberd: part-time teacher Kingston School of Art 1947-49. Hidalgo Moya, born 1920: trained AA 1939-43: worked in office of F. Gibberd: part-time teacher AA 1947-48: partnership together since 1946 (with Michael Powell who left to become Assistant Housing Architect, LCC in 1950) and won competition for Westminster City Council's Pimlico Housing Scheme 1946.



15 **G. GRENFELL BAINES and H. J. REIFENBERG**, architects Power and Production pavilion: G. Grenfell Baines, born 1908: after working as junior in office of rating surveyor and valuer from 1923 became junior draughtsman with Lanes. County Architect: trained at night school

and later Manchester University: won Southern Rhodesia Parliament House competition, 1937: now in partnership working as planning consultants of Aycliffe and Peterlee. H. J. Reifenberg, born 1904: graduated Berlin Technical University, 1922: private practice in Berlin, 1924. Came to England 1938 and became British subject.



EDWARD MILLS, architect Administration Building: born 1915: trained Regent Street Polytechnic: worked in offices including Maxwell Fry's and Gropius': private practice since 1936: worked in India, Nigeria, W. Africa, S. Africa: buildings include Factory Canteen and New Process Building, Dagenham, Flats at Hackney, St. Hellier Methodist Community Church, etc.: research work includes design of modern chemical laboratories, low rental housing and slum clearance.




MAXWELL FRY and JANE DREW, architects Waterloo Entrance, Harbour Bar, Thames-side Restaurant: Maxwell Fry, born 1899: trained Liverpool University School of Architecture: partnership 1927-34: with Gropius 1934-36: practised alone 1936-39: war service in War Office and RE West Africa: Town Planning Advisor, West Africa, 1943-45: returned to England setting up partnership with his wife (Jane Drew): works include flats for Lewisham Borough Council and Harlow New Town, Ibadan University, Nigeria, Hospital and Schools at Kuwait: member Royal Fine Art Commission. Jane Drew, born 1911: trained AA: partnership with J. T. Allston from 1934-39: during war designed aircraft factories, and research in kitchen planning: chairman RIBA exhibition 'Rebuilding Britain,' 1943: Assistant Town Planning Advisor to the Resident Minister, West African Colonies 1944-45: first woman council member AA and ARC: now designing hospitals, flats and school in West Africa: editor 'Architects' Year Book.'



18 **GORDON and URSULA BOWYER**, architects of Sports Section: Gordon Bowyer, born 1923: trained Regent Street Polytechnic School of Architecture 1940-44: architectural and industrial design assistant 1944-46: taught at Regent Street Polytechnic 1946-48: private practice since 1948, mostly exhibition work. Ursula Bowyer, born 1926: trained at Regent Street Polytechnic 1942-46: worked as architectural assistant 1946-49: in partnership with her husband since 1949.



19 **BASIL SPENCE**, architect Sea and Ships: born 1907: trained at Schools of Architecture, London and Edinburgh Universities: worked with Lutyns for year: designed Scottish pavilions, Glasgow Exhibition, 1938 with T. S. Tait: Chief Architect, 'Britain Can Make It' Exhibition, 'Enterprise Scotland' (1947): at present working on housing at



ARCON, architects Transport Pavilion: Rodney Thomas, trained University College, London, School of Architecture 1919-22: studied painting at Slade: private practice 1931-39: partnership with Raglan Squire 1941-43: founder-partner Arcon 1943, in charge of the unit responsible for Transport building. Edric Neel, trained Cambridge School of Architecture, 1932-35: worked with W. Wells-Coates 1935-37: private practice 1937-39: architect-

Sunbury-on-Thames, Dunbar and Selkirk, three schools, a shopping centre and a theatre reconstruction.



LEONARD MANASSEH, architect of '51 Bar: born 1916: trained AA: CRE North London and private firms working on canteens, kitchens, aircraft factories, etc.: 1943-46, pilot, Fleet Air Arm: 1946-48 under C. H. Aslin, Herts County Architect, on police housing and schools: 1948-50, a Senior Architect with Stevenage Development Corporation, designs for Town Centre, housing, shops, etc.: won competition for Luxury Restaurant, South Bank Exhibition (abandoned for economy): 1950, Director of Preliminary School AA.



GORDON TAIT, architect Station Gate: born 1912: trained AA: partnership with Sir John Burnet, Tait & Partners since 1939: served as pilot RAF during war: pre-war work largely on Glasgow Exhibition 1937-38: at present engaged on three schools, 300 London flats, a nursing home and maternity hospital, Scotland: a large City office block and a bank in Portsmouth.







atural staff Cement & Concrete Assoc. 1939: one of founders of Arcon partnership, 1943: member Board of Assoc. for Planning and Regional Reconstruction, and of School Planning 1945-49: A. M. Gear, trained Nottingham University School of Architecture 1929-31: worked in various offices in Nottingham and later London: during the war with Professor Holford and Sir Alexander Gibb and Partners: joined Arcon 1943, partner 1946.

EXHIBITIONS

Even if one allows for the fact that much of the painting and a little of the sculpture is purely illustrative, and so should be considered under the head of exhibition technique rather than as works of art in their own right, the South Bank exhibition provides, incidentally, a very considerable show of contemporary English art. The critic, however, is confronted with a difficulty about which he may justifiably feel annoyance: the ten-shilling catalogue, so far as painting and sculpture are concerned, is utterly inadequate. Not only is there no index of any sort; the individual entries fail to give the most elementary particulars (title and material or medium—to ask nothing more) about the works to which they relate.

Taking the sculpture first, it is hard to resist the reflection that size and aesthetic quality tend to be in inverse ratio, at least in that upstream section of the exhibition where Charoux's *Islanders* glare defiance over the river in the direction of Scotland Yard, and Keith Godwin's *Neptune*, on the end wall of the Sea and Ships pavilion, does his best to ignore Daphne Hardy's Lehmbruckian girl outside the '51 Bar. But in any case there are only three, or perhaps four, works of sculpture which live in their own right—as something more than evidence of the taste and talent of their creators. One is Henry Moore's reclining figure outside the Country pavilion; in this the feeling of power in repose conveyed by the posture and by the dynamo-like conformation of the chest or diaphragm is reinforced by the raised linear patterning of the bronze with its resultant sense of surface tensions. Another is Barbara Hepworth's pair of biolithic figures, or *Contrapuntal Forms*, on the podium of the Dome of Discovery; here duality has been resolved with truly monumental effect. The third really notable sculpture—the order is geographical, assuming entry by the Chicheley Street Gate—is Reg Butler's *Bird Cage* at the downstream extremity of the site beyond the Thames-side Restaurant. With an extramural crane as background, this has been rather unfortunate in its placing; in articulation and in complication of structure, however, it goes a step further than anything Butler has previously done, while maintaining the surface richness of his smaller recent works. And the fourth? Certainly it is not a likeable work, and it belongs to a convention which many may feel to be outworn, yet Epstein's leaping figure near the entrance to the Homes and Gardens pavilion has a certain quality of positiveness which is lacking from so much of the other sculpture; it must be admitted that the artist knew where he was going, even by those who think it was the wrong direction.

In addition to these four outstanding works, there are several of considerable charm. Karin Jonzen's dancing nymph at the end of Waterways certainly takes a high place among them, while Lynn Chadwick's copper cypress tree by the Regatta Restaurant is as pretty a garden ornament as one could hope to find. (There is a characteristic hanging mobile by the same artist at the top of the Waterloo Bridge Gate viewing tower.) Richard Huws' water mobile—the



25, *Contrapuntal Forms*, stone, by Barbara Hepworth; 26, *Reclining Figure*, stone, by Henry Moore; 27, *Bird Cage*, iron, by Reg Butler; 28, *Discovery*, by Keith Vaughan; 29, *Mural* by John Piper.

seventh wave is always the biggest, or is it?—is a diversion whose popularity with all comers is deserved; Barbara Hepworth's revolving abstract in concrete in the garden of the Thames-side Restaurant is enjoyed by many who would never admit to a liking for abstract art.

But it is time to consider the paintings. Out of doors, the three largest are John Piper's mural on the end of Homes and Gardens, John Hutton's on the Sea and Ships, and Felix Topolski's under the railway. Piper's architectural fantasy, in which one picks out parts of Kirby Hall, Castle Howard, the Brighton ter-

aces, etc., is easily the most successful of these three: the scale and the amount of incident are both just right. Hutton's shipbuilding mural is too much like a small painting, or a number of small paintings, enlarged up: the confusion that is Topolski's *Cavalcade of Commonwealth* can be regarded, at best, as a gallant failure. Victor Pasmore's calligraphic abstract in ceramic ware on the east wall of the Regatta Restaurant, on the other hand, is a triumphant success; here is a mode of external decoration which surely has great potentialities for the future. And another technique whose existence

[continued on page 144]

It's as simple as . . .



Glass Blocks retain the temperature you want inside, and bring in the daylight as well . . yet there is still the advantage of privacy.

"INSULIGHT"

HOLLOW GLASS BLOCKS

Send for the free booklet giving fixing details for "INSULIGHT" Hollow Glass Blocks.

Consult the Technical Sales and Service Department at St. Helens, Lancs., or Selwyn House, Cleveland Row, St. James's, London, S.W.1. Telephones: St. Helens 4001, Whitehall 5872-6.



PILKINGTON BROTHERS LIMITED

Supplies are available through the usual trade channels. "INSULIGHT" is the British registered trade mark of Pilkington Brothers Ltd.

with them from the South Bank, and that is that the painters and sculptors have not risen to the occasion in the way that the architects have. They should reflect that, in so far as the private experience has taken the place of the public occasion as an effective stimulus to artistic production, contemporary painters and sculptors are the victims of an historical process rather than active delinquents.

TRADE & INDUSTRY

Hardwood Floors

There must be more innovations in technique and design in the Royal Festival Hall than in any other recent building in Europe. It is therefore an interesting fact that the material chosen for a very large part of the flooring was the traditional hardwood. The implications are obvious, for the timbers and finishes selected are an undoubted asset to the design while their hard-wearing qualities are too well known to require comment.

The flooring has been laid throughout by Vigers Bros. Ltd. That in the foyer is laid in teak and Muhimbi strip, the first, of course, being a timber of long-standing reputation, since it is stable and possesses a rich appearance in colours varying from light gold to dark brown. Its oily nature has the advantage of minimizing 'dusting.' Teak has also been used for the auditorium. Muhimbi, an extremely hard wood from Uganda, is here used for the first time in a floor of any appreciable size in this country. In colour it is not unlike walnut.

[continued on page 146]

30

Foyer of the Royal Festival Hall showing teak strip flooring.

architects might profitably remember is that of *sgraffito*, worthily represented on the South Bank by Augustus Lunn's wall at the Seaside.

Indoors, or let us say under cover, the most extensive mural is Leonard Rosoman's *Seasons* in the Country pavilion (which, however, lacks punch), and the most notable work of art is without question the big Sutherland in the Land of Britain. Taking other buildings in the order of the catalogue, in the Minerals Josef Herman's expressionist *Miners* and in the Sea and Ships James Boswell's *Drifters* may be noted as playing the very different parts that their settings demand of them with some success, though neither is intrinsically very remarkable. In the Dome of Discovery Keith Vaughan's *Discovery* makes an effective decorative gesture; John Minton, in his *Exploration*,


has for all his skill as an illustrator got bogged down in the problem of representing sixteenth-century seamen and twentieth-century aeroplanes in a manner at once fresh and realistic—and, indeed, it may well be an insuperable problem for our age. In the Lion and the Unicorn Edward Bawden's *Country Life* mural on the end wall and Kenneth Rowntree's serial *Freedom* do what they set out to do wittily and well; the '51 Bar contains a mural of the Crystal Palace by Julian Trevelyan, which has a feeling of spontaneity welcome after so many set pieces; Ben Nicholson contributes a mural in the Thames-side Restaurant.

A survey of this length must necessarily be highly selective; nor will everyone agree with the selection. However, there is one conclusion which many people are likely to carry away

AT THE FESTIVAL

Storage units on show at the Homes and Gardens Pavilion, South Bank Exhibition. Designed by Robin Day, A.R.C.A., F.S.I.A., and made by Heal & Son.

Heal's were represented in the 1851 Exhibition and many Heal products have been selected for the Festival of Britain a century later.





We invite you to come and inspect our large selection of contemporary furniture by well-known present day designers. If you are unable to visit us, we will gladly send you a copy of our "Contemporary Furniture" folder.

HEAL & SON

HEAL & SON LTD., 196, TOTTENHAM COURT ROAD, W.1. TELEPHONE: MUSEUM 1666. TELEGRAMS: FOURPOSTER, RATH, LONDON

THE AMENITIES BLOCK serving the Beavor Iron Foundry of Messrs. Ruston & Hornsby Ltd., Lincoln, is equipped with a balanced system of warmed fresh air ventilation, and direct radiator heating giving temperatures of 60° F and 65° F in the various Mess Rooms, Changing Rooms, etc. For this system the boiler used is a "Rex" 3/7 rated at 875,000 B.Th.U.s per hour. There is also a hot water service provided by a "Rex" D/6 boiler rated at 197,000 B.Th.U.s per hour, supplying hot water to all draw-off fittings, wash-fountains, etc.



Heating installation by

RICHARD CRITTALL & CO. LTD.

151 GREAT PORTLAND STREET, LONDON, W.1.

using

POTTERTON
gas-fired boilers

THOMAS DE LA RUE & CO. LTD.

(GAS DIVISION)



Imperial House, 84/86 Regent St., London, W.1. Northern Area: 4 Albert Sq., Manchester 2. Midlands Area: Portobello Works, Warwick.

continued from page 144]

In the Restaurant the floor is in white maple strip laid on a sub-floor of yellow deal. As its name suggests it is very light in colour, being a sapwood, but despite this it is very hard and capable of standing up to the most severe wear and tear.

The staircases are unusual both in design and in the construction of the treads. The treads which overhang the concrete stair are built up with cores of Gurjun, a strong durable timber, light reddish brown in colour, from the Far East. Each core is cased in with teak and bolted to the concrete stair. The floors are all waxed, with the exception of the Muhimbi, which is treated with 'Bourne Seal,' a preparation with a tung oil base, and then burnished with steel wool.

An important technical problem which had to be met was that of moisture content, for the proximity of panel heating and the variations in temperature within the building, whether heated or otherwise, can have a considerable effect on the timber. The relative compressibility of the timbers used therefore required careful assessment.

Vigers Bros. Ltd., Broadway Chambers, Ludgate Broadway, E.C.4.

Research in Brick Making

The London Brick Company has recently completed a new Research Laboratory, designed by C. C. Handisyde, FRIBA, at Stewartby, the largest brickfield in the world. Although research has been carried on since 1928, this new development will intensify research into the nature of clay materials, brickmaking processes and new clay products.

The modern architect wants a lighter weight

brick possessing better thermal qualities than are at present possible. Builders, in fact every-one, require to reduce the site-costs of construction. The industry is naturally facing competition from other products which for various reasons lead to a lowering of these costs.

Increased knowledge of what happens to a brick as it passes from the green brick to finished brick should result in greater uniformity of product, and thus an improved one.

The London Brick Co., Ltd., Stewartby, Bedfordshire.

CONTRACTORS etc

South Bank Exhibition. General Contractors: Richard Costain Ltd.; Holland & Hannen and Cubitts Ltd.; Kirk & Kirk Ltd. **Sub-Contractors:** Acme Metal Works (1921) Ltd.; Acorn Anodizing Co.; A.D. Services Ltd.; Adam & Lane & Neeve Ltd.; Adamsez Ltd.; Agrapite Ltd.; Aygee Ltd.; Aidas Electric Co.; The Aircrow Co.; Aldous & Campbell Ltd.; Allen & Greaves Ltd.; Alphamin Ltd.; Amalcraft; Appleby-Frodingham Steel Co.; Arden & Co.; Armstrong Cork Co.; Art Pavements & Decorations Ltd.; Ascot Gas Water Heaters Ltd.; Aston Construction Co.; J. Avery & Co.; Wm. Bain & Co.; Bakelite Ltd.; Barker & Son; Bassett-Lowke Ltd.; R. J. Bates & Co. (London) Ltd.; Baume & Co.; Bayliss, Jones & Bayliss Ltd.; Beachcroft Concrete & Slab Co.; J. D. Beardmore & Co.; E. E. Beaumont Ltd.; Bective Electric Co.; Benjamin Electric Ltd.; Bennett's Wood Flooring (Tungit) Co.; Best & Lloyd Ltd.; A. J. Binns Ltd.; E. C. Blackmore Ltd.; Boddy Roofing Co.; John Bolding & Sons; Bolton Gate Co.; Boulton & Paul Ltd.; Bow Slate Enamel

Co.; Fredk. Braby & Co.; Braithwaite & Co. (Engineers) Ltd.; Wm. Briggs & Sons; British Aluminium Co.; British Challenge Glazing Co.; British Insulated Callender's Construction Co.; British Reinforced Concrete Eng. Co.; British Ropes Ltd.; British Thomson-Houston Co.; Brooks Air & Heat Systems Ltd.; Brooks Ltd.; D. Burkle & Son; Camden Joinery Mill & Display Works; Camden Tile & Mosaic Co.; Camper & Nicholson Ltd.; Carter & Co. (London) Ltd.; Carter, Horseley (Engineers) Ltd.; Catesbys Ltd.; R. H. Catterall & Co.; Cawood Wharton & Co.; Cellulin Flooring Co.; Cement Marketing Company Ltd.; Central Rediffusion & Services Ltd.; Chance Brothers Ltd.; Chubb & Sons Lock & Safe Co.; Cinema Television Co.; City Display Organisation; James Clark & Eaton Ltd.; Clark & Fenn Ltd.; Frank W. Clifford Ltd.; Cockade Ltd.; J. Collins & Son; Colour-point Decorations Ltd.; W. H. Colt (London) Ltd.; Commercial Welders Ltd.; Comyn Ching & Co. (London) Ltd.; Concrete Ltd.; Concrete & Structural Products Ltd.; H. W. Cooper & Co.; Alfred A. Corre & Co.; James Couper & Co.; Craigpark Electric Cable Co.; Crittall Manufacturing Co.; Horace W. Cullum & Co.; Dales Lettering Ltd.; Dancel Engineering Ltd.; Darlington Fencing Co.; A. Davis & Co. (Shopfitters) Ltd.; H. & C. Davis & Co.; Davson & Pritchard; Dawns Ltd.; Deans Blinds (Putney) Ltd.; Dennison Kett & Co.; Doulton & Co.; Dover Limited; Wm. Doxford & Son; Dryad Metal Works Ltd.; Duncan Tucker (Tottenham) Ltd.; Dualloys Ltd.; Eastwoods Ltd.; Benjamin Edgington; John Edgington & Co.; Edison Swan Electric Co.; A. Edmonds & Co.; Educational Supply Association; Electrolumination Ltd.; Samuel Elliott & Sons; W. T. Ellison & Co.; E.M.I. Sales & Services Ltd.; Empire Stone Co.; Engineering Services Installation Ltd.; English Bridge & Structural Eng. Co.; English Electric Co.; David Esdaile & Co.; Eustace & Partners; Everseal Products Ltd.; Exhibition & General Construction Co.; Expanded Metal Co.; S. W. Farmer & Son; F. E. W. Models & Displays; B. Finch & Co.; Finlay & Co.; Fireproof Shutter & Door Co.; J. F. Firth & Sons; Fleming Bros.; Flush Woodwork Ltd.; Forson Design & Engineering Co.; Franco British Signs Ltd.; W. N. Froy & Sons; Gardiner, Sons & Co.; Geo. H.

[continued on page 148]



London's Festival Gardens at Night

This view shows the illuminated Gothic towers, arcades and rotundas of the Main Vista . . . a harmony of tungsten, fluorescent and floodlight.

A major share of the electrical installation of the Festival Gardens was entrusted to . . .

Drake & Gorham (Contractors) Ltd.

36 GROSVENOR GARDENS, LONDON, S.W.1

Also at:— CARDIFF · EDINBURGH · HEREFORD · MANCHESTER · NEWCASTLE · PLYMOUTH & WINCHESTER

& Co.
British
ng Co.;
on Co.;
h Ropes
s Air &
& Son;
len Tile
arter &
engineers)
Cawood
Cement
sion &
& Sons
Display
Clark &
e Ltd.;
s Ltd.;
rs Ltd.;
e Ltd.;
Cooper
& Co.;
cturing
g Ltd.;
g Co.;
avis &
Deans
oulton
Dryad
nham)
njamin
Swan
Supply
Elliott
ervices
es In-
Eng.
z Co.;
Ltd.;
anded
dels &
proof
eming
gn &
V. N.
O. H.
ge 148

The external roof
of the Royal Festival Hall
has been isolated from
the main roof structure by

FIBREGLASS
TRADE MARK
SOUND-DEADENING QUILT

FIBREGLASS LTD
RAVENHEAD, ST. HELENS, LANCs. (ST. HELENS 4224)

LONDON OFFICE:
63/65 Piccadilly, W.1.
(Regent 2115/6)

GLASGOW OFFICE:
136 Renfield Street
(Douglas 2687)

NEWCASTLE-ON-TYNE OFFICE:
c/o Pilkington Brothers Ltd., Westgate Rd.
(Newcastle 20938)

MANCHESTER OFFICE:
11 Piccadilly
(Blackfriars 8863)

continued from page 146]

Gascoigne Co.; Gaskell & Chambers Ltd.; Robert Gay & Co.; General Electric Co.; General Motors (Frigid-
aire Division); T. Gerrard & Co.; James Gibbons
Ltd.; Gilliam & Co.; Girtings' Ferro-Concrete Co.;
G. H. Green & Co.; Grundy Arnatt Ltd.; Guntex
Ltd.; G. N. Haden & Sons; Hadfields (Merton) Ltd.;
Hailwood & Ackroyd Ltd.; Holcon Ltd.; Halerete
Panels Ltd.; Hall & Company Ltd.; J. & E. Hall
Ltd.; Matthew Hall & Co.; Hammond & Champness
Ltd.; Harland & Wolff Ltd.; Harmer & Fuller;
Harris & Sheldon Ltd.; G. A. Harvey & Co.; Harvey
Langford Ltd.; Haskins Rolling Shutters (E. Pol-
lard & Co.); Haywards Ltd.; Heals Contracts
Ltd.; Heating & Engineering Co. Ltd.; P. C. Hender-
son Ltd.; Higginson & Wright; High Brooms Brick
& Tile Co.; Hille & Co.; Hills (West Bromwich) Ltd.;
Hobson & Wise; Oswald Hollman; Holoplast Ltd.;
Henry Hope & Sons; Horsley Bridge & Thomas
Piggott Ltd.; Horsley Smith & Co. (Hayes) Ltd.;
Howarth & Sons; Hume Atkins & Co.; Huntley &
Sparks Ltd.; Hunting Aerosurveys Ltd.; Hygienette
Mfg. Co.; T. & W. Ide Ltd.; Ideal Boilers Ltd.;
Imperial Chemical Industries Ltd.; Ingersoll Ltd.;
International Paints Ltd.; Jaconello Ltd.; Jiewood
Ltd.; G. Johnson Bros.; T. C. Jones & Co.; W. G.
Kaleyrads Ltd.; Keith Blackman Ltd.; Geo. W.
King Ltd.; Laidlaw Smith Ltd.; J. Latham; Lens-
crete Ltd.; The Lettering Centre; Lightfoot Refrig-
eration Co.; Light Steelwork (1925) Ltd.; Limmer &
Trinidad Lake Asphalt Co.; Linden Doors Ltd.;
John Line & Sons; Lipscombe & Co.; Liverpool
Artificial Stone Co.; London Aluminium Co.; London
Brick Co.; London Electricity Board; London Sand
Blast Decorative Glassworks Ltd.; London Welding
Co.; J. Long & Sons (Bath) Ltd.; Lund Bros. & Co.;
Macartney Ltd.; Walter Macfarlane & Co.; McClean
& Co. (Metal Windows) Ltd.; F. McNeill & Co.;
R. & A. Main Ltd.; Wm. Mallinson & Sons; Maple &
Co.; Marconi's Wireless Telegraph Co.; Marryat &
Scott Ltd.; Edward Marshall; Mellows & Co.;
Merchant Adventurers of London Ltd.; Metalform
Ltd.; Montague Meyer Ltd.; Midhurst White Brick
Co.; Monk Metal Window Co.; Morgan & Partners
Ltd.; Morris Bowden Plastic Co.; Mountford
Brothers Ltd.; Nash & Thompson Ltd.; National
Coal Board "Synthaprufe"; Nettlefold & Moser Ltd.;
Neuchatel Asphalt Co.; John M. Newton & Sons;
Nicholls & Clarke Ltd.; Northern Aluminium Co.;

Ozonair Ltd.; Parnall & Sons; Thomas Parsons
& Sons; Partridge Models Ltd.; Pearce Signs; Penny-
cook Patent Glazing & Engineering Co.; Philip Floor-
ing Co.; Pilkington Bros.; Potter Rax Ltd.; Pressed
Steel Co.; Preview Models; Robert L. Priestley Ltd.;
Pryke & Palmer Ltd.; Ernest Race Ltd.; Racecourse
Equipment Ltd.; Ragusa Asphalt Co.; Recorded
Sound Ltd.; Redpath Brown & Co.; Rennis Ltd.;
Rippers Ltd.; Roffe Limited; Rosser & Russell Ltd.;
Rownson Drew & Clydesdale Ltd.; Ruberoid Co.;
Russell Bros. (Paddington) Ltd.; John Sadd & Sons;
Fredk. Sage & Co.; Santon Ltd.; Saunders & Taylor
Ltd.; Scaffolding (Great Britain) Ltd.; Semtex Ltd.;
J. & W. Shale Ltd.; Shanks & Co.; Matthew T.
Shaw & Co.; Siegart Floor Co.; Silixine Paints Ltd.;
Simplex Electric Co.; W. B. Simpson & Sons;
Skellorn Edwards & Co.; Smart & Brown (Engineers)
Ltd.; W. H. Smith & Co.; K. & A. Sommerfeld Ltd.;
Charles Spreckley & Co.; Standard Telephones &
Cables Ltd.; Starkie Gardener Ltd.; Steel Bracket-
ing Ltd.; Steel Ceilings Ltd.; Steel Scaffolding Co.;
Stewarts & Lloyds Ltd.; Stitsons Sanitary Fittings
Ltd.; Stoneycombe Lime & Stone Co.; James Stott
& Co.; Stramit Boards Ltd.; Standard Pavements
Ltd.; Strand Electric & Engineering Co.; Structural
& Mechanical Development Engineers Co.; Stuarts
Granolithic Co.; Sundeala Board Co.; Sycamore
(Brentford) Ltd.; George E. Taylor & Co.; W. A.
Telling Ltd.; James Templeton & Co.; Ten Test
Fibre Board Co.; Thomas & Frediani Ltd.; John
Thompson (Beacon Windows) Ltd.; Thorn Electrical
Industries Ltd.; Thornborough & Sons; Tidmarsh
& Sons; Timber Development Association; Titan Lift
Co.; Tretol Ltd.; Troughton & Young Ltd.; Trussed
Concrete Steel Co.; Turners Asbestos Cement Co.;
Turner Bros. & Co.; J. A. Tyler & Sons; Hugh
Twaddle Ltd.; Twistee Reinforcement Ltd.; United
Steel Companies Ltd.; Universal Asbestos Manu-
facturing Co.; Universal Metal Furring & Lathing
Co.; Via-Duet Heating & Ventilating Co.; Venesta
Ltd.; Vent-Axia Ltd.; Wainwright & Waring; W.
Walker Limited; G. W. Waller Ltd.; S. & C. Walms-
ley Ltd.; Norman Walton & Co.; George Wands-
worth & Son; Warerite Ltd.; Wates Ltd.; Wessex
Guild Ltd.; Westminster Joinery Co.; J. Whitehead
& Sons; Wiggins-Sankey Ltd.; Willen Key & Com-
pany (1946) Ltd.; Willment Ltd.; Williams &
Williams Ltd.; Woods of Colchester Ltd.

ACKNOWLEDGMENTS

Cover: Gordon Cullen; all drawings and plans in
this special issue are by Gordon Cullen and all
photographs by Galwey, Arphot, except the follow-
ing: Frontispiece, 72, 131, 168, David Potts; pages
76 and 77, F. Mackenzie; 17, H. T. Cadbury-
Brown; 114, 119, 140, 141, 146, 147, 150, 157, 159, 160,
165, 166, 169, 170, 175, 178, 180, Millar and Harris;
149, 151, A. Anderson; 162, Read, Arphot;
MARGINALIA: all photographs Galwey, Arphot,
except 16, 19, Sam Lambert; 2, DRU; 5, Keystone;
6, GPA; 10, *Picture Post*; 12, Black Star; 14, Millar
and Harris; 15, A. Anderson; 17, Camera Press; 20,
S. Newbery; 24, *Building*; 25, A. Panting; 26, Arts
Council; 28, *The Times*; 29, FOB; 30, J. Maltby.

Advertisements

WOODCARVING undertaken by skilled craftsman of repute
and long standing. Consultation and estimates given. C. T.
Hayward, Architectural Woodcarver, High Street, Harlington,
Middlesex. Telephone: Hayes 2906.

SCULPTURE, MURALS, MODELS & MOBILES photographed
by a specialist. The difficult or unconventional problem is
particularly welcomed. John Vickers, A.I.B.P., 29b, Belgrave
Road, S.W.1. VIC. 4915.

THE POLYTECHNIC, 309, REGENT STREET, W.1.

SCHOOL OF ARCHITECTURE, SURVEYING AND BUILDING

President of the School: **SIR BANISTER FLETCHER,**
D.LIT. (LOND.), M.A.R.C.H., F.F.R.I.B.A.

Head of the School: **JOHN S. WALKDEN,**
F.R.I.B.A., DIST. T.P., M.T.P.I., R.I.B.A. Athens Bursar

DAY SCHOOL

The Day School of Architecture is fully recognised by the Royal
Institute of British Architects. The Final Diploma Examina-
tion of the School is a qualification for registration under the
Architects (Registration) Act.

The course embraces all aspects of Architectural Education,
including Interior Design, Structural Design and Equipment, and
the Science of Building materials.

The Day Schools of Surveying and Building offer courses in
Building and Quantity Surveying and in Building Technology.
Session commences 18th September, 1951.

EVENING SCHOOL

Professional courses are available for pupils and assistants in
the Architectural, Town Planning, and Surveying professions
and in the Building Industry.

Prospectuses may be obtained on application to the undersigned.

J. C. JONES, Director of Education.



Part of an industrial building protected by Milners shutters

"A Milners job"

CONSTRUCTED with the superior work-
manship that has made the Milners Safe
Co. suppliers of protective equipment
to the Bank of England, the Admiralty
and War Office, and to Banks through-
out the world, Milners Steel Rolling
Shutters—electrical or hand-operated
—are your premises' best possible
protection against fire or theft.



Write for full particulars and Catalogue to the Shutter Division of

Milners Safe Co. Ltd. 58 Holborn Viaduct, London, E.C.1.

Telephone: CENTral 0041-5



Lingerie Department, Messrs. Selfridges of Oxford Street


EFFECTIVE display setting can interpret an atmosphere appropriate to the product — interpretation of design characterises the work of The George Parnall Organisation.

Messrs. Selfridges of Oxford Street, London, W. have completed certain replanning of departments and it was the pleasure and privilege of George Parnall & Company Limited to carry out this work under the direction of the House Architect Mr. R. L. Heath, L.R.I.B.A., and Consulting Architect Mr. J. S. Beaumont, F.R.I.B.A.


Design and Craftsmanship by
GEORGE PARNALL

GEORGE PARNALL & CO. LTD. 4 BEDFORD SQUARE LONDON, W.C.1

STANDARD P-TRAP




The illustration shows a standard lead P-trap with cap and lining on the inlet and brass connector on the outlet for iron waste-pipes.



RESEALING P-TRAP

The illustration shows a McAlpine Patent Resealing P-trap and hundreds of thousands of these traps have proved their efficiency over a number of years. They eliminate the need for ventilation pipes and are being widely adopted for housing developments. They are particularly useful for installation in flats and conversions to flats. In addition, they have been extensively installed in Factories, Hospitals and Public Buildings. The model illustrated is suitable for installations where lead pipes are used.

STANDARD S-TRAP



This standard design with cap and lining fitted on inlet, the McAlpine "Leadcop" joint (Provisional Patent No. 26401) fitted on outlet. This fitting has been specially adapted to allow the advantages of a lead trap in a copper waste system.

Good plumbing is good planning

The recognised advantages of Lead Traps, Bends and Offsets in all types of waste systems are fully developed in the manufacture of McAlpine Standard and Special designs. They are cheaper to instal, more satisfactory in use, easier to maintain, and the McAlpine patent "Leadcop" Joint makes them perfectly adapted to copper waste systems also. There is every advantage in specifying McAlpine products. Delivery is prompt and supplies are usually available from stock. We shall be glad to give quotations on receipt of details.

**ALL OUR PRODUCTS CAN BE SUPPLIED
TO SUIT LEAD, COPPER OR IRON
WASTE PIPES.**

McALPINE

AND COMPANY LIMITED

Manufacturers of Hydraulic-drawn Lead Traps, Bends and Offsets.

KELVIN AVENUE, HILLINGTON, GLASGOW, S.W.2.

Telephone : Glasgow, HALFWAY 3213

London Address : 39 CHEAPSIDE, E.C.2. Telephone : London, CITY 3085.

HARDROW

CONCRETE SLATES

WITH THE ARCHITECTURAL FEATURES OF NATURAL STONE



COMPOSITION. BODY : Crushed granite and cement.
SURFACE: Coloured sand and cement (approx. one-seventh of the whole thickness) which is completely permanent.
Made in Natural Stone colours and in Green.

We have been manufacturing Hardrow Slates for over a quarter of a century and during this time have supplied roofs for over 50,000 houses and substantial numbers of large blocks of flats.

The minimum standard size of Hardrow Slate is 18" x 12"—the maximum standard size 2' 4" x 18".

The texture of the material and the size of slate give character to any roof.

Many fine old buildings over 200 years old have been re-roofed with Hardrow Slates.

ROBERT ABRAHAM LTD.

43, BANK HALL ST., LIVERPOOL 20
TELEPHONE : BOOTLE 2048

● HAWES, YORKSHIRE
TELEPHONE : HAWES 231

Balustrading

at the South Bank site
for the Festival of Britain

BY

BAYLISS, JONES & BAYLISS LTD.

*Manufacturers of Bolts and Nuts · Railway Fastenings
Fencing · Gates · Ornamental Ironwork · Fabricated
Steelwork · Rounds, Flats, etc. · General Forgings &
Castings · H.T. and L.T. Line Equipment · Steel Bars
Sections for Railway and Tramway Fastenings · Components
for Agricultural Implements and Equipment.*



HEAD OFFICE : VICTORIA WORKS, WOLVERHAMPTON
Telephone : Wolverhampton 20441

LONDON OFFICE : 139 CANNON STREET, E.C.4
Telephone : Mansion House 8524



HAND PRODUCED WALLPAPERS

"N hand printing the block consists of three thicknesses of wood cemented together, the top, or cutting surface, being usually of sycamore or pear tree wood. The outline is 'rubbed down' on this fine surface and the design is coloured in with a wash of vermilion. The block in this state is handed to the block cutter, who goes over all the outline with tiny gouges and chisels, cutting the outline into the block to the depth of about 3-16ths of an inch. When the whole of the outline has been cut he removes all the superfluous surface of the block, leaving only those portions which were coloured by the tracer.

"We have now a block with the design standing up in bold relief, but before it can be used to print a continuous design it must be provided with metal pins, which mark the top and bottom of the design. These are intended to print on the edge of the paper, which will be trimmed off by the paper-hanger. These printed dots are used by the printer to register the repeating of the design. For the purpose of handling the block a short strap is nailed across the back, making a loop just large enough to allow the printer's hand to be inserted. The printing table is still made on the pattern of those used in the earliest days of the craft. Pressure is brought to bear on the block by a 'dolly pole' suspended over the centre of the table. This pole can be brought down by a simple system of levers worked by the foot of the printer. On the table are laid several thicknesses of felt, and over this is drawn the paper to be printed.

"Beside the table stands the colour box. This consists of a box holding a few inches in depth of thick gum, upon which floats a shallow tray measuring about 36 in. by 32 in., the bottom of which is made of waterproof canvas, and on this is laid a square of felt. A lad or girl stands by the colour box to keep the square of felt well brushed over with the size colour used for printing. The printing block is dabbed on this colour, then laid on the paper to be printed, and the needed pressure is applied by the 'dolly pole.' The block is then returned to the colour case and the printed portion of the paper is drawn forward, leaving the next space in position ready for the next impression of the block. The printer follows on the work by fitting the leading pin or gauge on to the one at the end of the first print, continuing to repeat the design by carefully joining end to end, until the twelve-yard length of the paper has all been passed under the press. If the pattern has two or more colours the process must be repeated for each colour.

"The paper itself is first covered with a ground of colour—this for a few pieces is done by hand on a table twelve yards long, or, if many pieces are required, by a grounding machine. The paper is sometimes embossed after the printing, or as a first process to the plain white paper. This latter way gives a very rich effect when transparent colour is used, as the deeper parts of the embossing take a darker colour. There is no comparison between the two processes in finish, still less in output, for while the machine can roughly turn out thousands of rolls a day, there are hand-printed designs where skilled printers cannot exceed one hundred pieces a month."

Those elusive refinements of the hand-made that are invisible yet always unmistakably apparent characterise each of the "Studies in Harmony" wallpaper productions. The complete collection can always be seen at our London and Branch Showrooms.

WE INVITE YOU TO VISIT OUR SHOWROOMS


JOHN LINE & SONS LIMITED

MAKERS OF THE "STUDIES IN HARMONY" WALLPAPERS AND PAINTS

213-216 TOTTENHAM COURT ROAD, LONDON, W.1

Carda WINDOW AT THE FESTIVAL

The perfect timber window, for double and single glazing



CARDA WINDOWS IN THE SUSPENDED OFFICES OF THE FESTIVAL OF BRITAIN ADMINISTRATION BUILDING.

Architects: Architects' Co-operative Partnership.

ADVANTAGES OF CARDA WINDOWS

- EXCELLENT APPEARANCE ● UNBROKEN VISION
- DRAUGHT-FREE VENTILATION ● HIGH THERMAL INSULATION, U—0.6 ● ALL SURFACES EASILY AND SAFELY CLEANED FROM INSIDE ● HIGH SOUND INSULATION, ATTENUATION 50 DECIBELS ● POSITIVE LOCKING ON FOUR POINTS BY ONE HANDLE ● DRAUGHT PROOF WHEN CLOSED ● EASILY INSTALLED ● NEED NOT BE BUILT IN ●

The Carda window can, due to its construction, be made to very large dimensions, and the architect has therefore a free hand when proportioning his elevations or the lighting of the rooms. The window gives an uninterrupted view through large undivided window panes. Carda windows are manufactured to any size within the following limits: Max. area 43 sq. ft. Max. width 8 ft. 10 in. Max. height 7 ft. 6 in. If units with areas greater than 43 sq. ft. are required, two or more windows can be combined. CARDA units can also be combined with wing lights and hopper lights for double glazing. CARDA windows can be made in soft or hard wood as desired.


ACOUSTIC MATERIALS ● ENAMEL GLAZED WALL TILES ● CERAMIC FLOOR TILES ● THERMAL AND VIBRATION INSULATORS




Window open for normal ventilation.



Window inverted for cleaning.



Double glazed window inverted and sashes separated for cleaning. (Outer sash side hung.)



Double glazed window inverted and sashes separated for cleaning. (Outer sash stay hung for wide windows.) Note wide access to the interspace provided by special stays.

SOME RECENT CARDA ORDERS:

<i>Project:</i>	<i>Architects:</i>
The Astor Avenue Primary School, Dover.	Henry Braddock & Martin Smith, F/A.R.I.B.A., London.
The Hilton Primary School, Blakelaw, Newcastle-on-Tyne.	George Kenyon, Dip. Arch., A.R.I.B.A., Dip. T.P., A.M.T.P.I., Newcastle City Architect.
Research Laboratories for The Brewers' Association, Nutfield, Surrey.	Easton & Robertson, F/F.R.I.B.A., London.
Borough Polytechnic New Building, London.	Norman & Dawbarn, F/A.R.I.B.A., London.
Gray's Farm Junior County Primary School, St. Paul's Cray, Chislehurst.	Scott & Westmoreland, F/A.R.I.B.A., London.
Upholland Grammar School, Wigan, Lancs.	Yorke, Rosenberg & Mardall, F/A.R.I.B.A., London.
Wimpson County School, Southampton and Middleton Moorclose Secondary School, Lancashire.	Lyons & Israel, A/A.R.I.B.A., London.
Nunnery Farm Secondary Modern School, Worcester.	E. B. Musman, B.A., F.R.I.B.A., London.
Hallam Hospital, West Bromwich.	Birmingham Regional Hospital Board.

HOLCON LIMITED
4, DRAPERS GARDENS, LONDON, E.C.2.

TELEPHONE: MONarch 4688.

HOLCO MULTI-CAVITY CONCRETE BLOCKS ● GRANITE AND MARBLE




BRIGHTSIDE *Conditioned* COMFORT

It will indeed be a Festival of Britain when Brightside Conditioned Comfort is everywhere realisable in office, factory and public building. The services which Brightside plan for right living comprise the fundamentals—hot and


cold water, equable indoor climate, clean fresh air in sufficient quantity. These are essential for profitable working, productivity and for indoor leisure, ministering alike to man's health, comfort, efficiency and happiness.

Send for this booklet:—
Heating and Air Treatment in Industry



THE BRIGHTSIDE FOUNDRY & ENGINEERING COMPANY LTD

Head Office: SHEFFIELD, and at BIRMINGHAM, BRISTOL, LIVERPOOL, LONDON, MANCHESTER, NEWCASTLE, PORTSMOUTH,
EDINBURGH, GLASGOW, BELFAST.



1865 . . .

Flats in Peabody Square, Islington, erected through the bounty of an American merchant and built by us to the design of Mr. H. A. Darbishire.

1950 . . .

Kerridge Court, Islington. Eight blocks of flats built by us in 1950 for the Islington Borough Council. The scheme comprises 130 flats and a communal laundry. Architects: Messrs. E. C. P. Monson, F/A.R.I.B.A.



Established in 1795

PATMAN & FOTHERINGHAM LIMITED

are always pleased to submit competitive tenders

15 ISLINGTON PARK STREET · LONDON · N.1

TELEPHONE: NORTH 1124



WEATHERFOIL HEATING

AT WHITMORE PARK SCHOOL

The heating in this, as in many recent schools, is by WEATHERFOIL. Air is blown at low velocity over hot water heat exchangers in concealed cabinets and fed into the classrooms and assembly halls through louvred grilles. Each WEATHERFOIL unit operates under individual automatic control, thus ensuring rapid response of the heating system to local conditions.

The WEATHERFOIL system of warm air heating has many advantages for schools. Installation costs are low because pipe runs and builders' work are greatly reduced. Economies are possible in running costs of the order of 30% over traditional heating systems. Accurate automatic control of the temperature in individual classrooms is ensured.

The need for exposed pipe runs or projecting radiators is eliminated. The neat, unobtrusive grilles in the wall are the only feature which is exposed to view.

Architects: Richard
Sheppard & Partners



Full particulars will be
sent on request, and a
discussion with one of our
technicians can easily be
arranged.

WEATHERFOIL HEATING SYSTEMS LTD., 185 BATH ROAD, SLOUGH, BUCKS. 'Phone: Slough 20269

LANDMARKS

in Fabric Design


Since 1870 Warners have been weaving furnishing fabrics which have always been renowned for their excellence in design, texture and colour.

A CONTEMPORARY WEAVE "GREEK KEY" ●


This modern damask, woven by power loom with crinkled cotton weft yarn, brings out the current vogue for texture.

"HAYDON" A MODERN DESIGN IN 1751

An example of a middle 18th Century brocade, woven in ● silk by hand loom.



"Greek Key"



By Appointment
Silk Manufacturers to
His Majesty The King

"Haydon"

WARNER

F A B R I C S


From all leading decorators

WARNER & SONS LTD.

77 WELLS STREET, OXFORD STREET, LONDON, W.1.

FACTORIES: BRAINTREE, ESSEX AND DARTFORD, KENT

CVS-117



Hygienette

Fully Automatic Electric TOILET INCINERATORS

are installed in the Ladies Toilet Rooms at

FESTIVAL EXHIBITION.

South Bank, London, S.E.

FESTIVAL GARDENS.

Battersea Park, London, S.W.

NEW GOVERNMENT OFFICES (Ministry of Works).

Whitehall, London, S.W.1.

and have been awarded the certificate of The Royal Institute of Public Health and Hygiene as evidence of merit.

The "HYGIENETTE" quickly and completely reduces soiled sanitary towels, surgical dressings, swabs, bandages, etc. to clean, dry ash.

HYGIENETTE MANUFACTURING CO.,

39, Victoria Street, London, S.W.1.

(ABBay 5175)



"SILVER FOX"
REGD. TRADE MARKS

"SILVER FOX" STAINLESS STEELS

are

STRONG

"Silver Fox" Stainless Steel is an alloy steel, possessing great strength as a structural material, as well as resistance to corrosion. It is therefore especially suited to transport applications, where its strength allows it to be used in thin sections which cannot be weakened by corrosion in use.

SHEETS · COLD ROLLED STRIP · WIRE · BARS · FORGINGS



SAMUEL FOX & COMPANY LIMITED

Branch of The United Steel Companies Limited

STOCKSBRIDGE WORKS · NR. SHEFFIELD · ENGLAND

(KB) F236


fire thought *is good* forethought

*Yet planning Fire Protection is so
often a tragic afterthought*

Every property owner should realise the need for properly planned protection against fire. Where new buildings or extensions are involved the Architect should be consulted in the early stages concerning the proper disposition of fire appliances and the planned accommodation for them. Happily to-day, the position is improving and Architects are more readily called upon to


PLAN FIRE PROTECTION BEFORE A BRICK IS LAID

We shall be pleased to co-operate with Architects, Surveyors and Contractors, without obligation, in offering impartial advice on fire protection equipment of every kind. Please write for fully illustrated particulars.



THE BEST KNOWN NAME IN FIRE PROTECTION.


THE PYRENE COMPANY LIMITED,
(Dept. A.R.8) 9, Grosvenor Gardens, London, S.W.1. Tel: Victoria 3401



Every Synchronome Master Clock is based on the Synchronome Free Pendulum at Greenwich. The Synchronome System, installed in hundreds of large industrial and commercial undertakings, consists of an electrical impulse master clock operating any number of "slave" dials, recorders or automatic time signals. Is independent of the mains. May be purchased outright, or installed under a rental scheme.

FOR INDUSTRY


Write for Technical Details.



and COMMERCE


SYNCHRONOME IMPULSE TIME SYSTEM

THE SYNCHRONOME CO. LTD., ABBEY ELECTRIC CLOCK WORKS,
MOUNT PLEASANT, ALPERTON, MIDDLESEX.



2 Festival Exhibits

by **SUGG**
WESTMINSTER



Among the street lighting exhibits accepted from SUGGS for the South Bank Exhibition is this example of modern gas lighting, the "Southport", now in use in some of the most important installations in the Country. Also exhibited is the Halcyon Domestic Space Heater, available in 2 models, each for flued or flueless operation, and as an Industrial model. Write for technical data sheets.

A Museum of Gas Lighting, in connection with the Festival, is open at Sugg's premises in Chapter Street, Westminster. An unusual opportunity. You are invited.

WM. SUGG & CO. LTD., CHAPTER ST.,
WESTMINSTER, S.W.1. VICTORIA 3211

SUGG

Estd.

1837



CHAMPION!

ACCRINGTON

'Nori' Bricks

THE ACCRINGTON BRICK & TILE CO. LTD.
ACCRINGTON, LANCs. PHONE: ACCRINGTON 2684

Strong...

Pressure proofed by patented process and tested at every stage. Only proven leads go into Venus Drawing Pencils

SMOOTH...


A patented colloidal process removes all grit and impurities—they must be smooth

ACCURATE...

Accurate through and through—graded and tested by experts, Venus Drawing Pencils make the right mark every time


THE PENCIL WITH
THE CRACKLE FINISH

VENUS
Perfect PENCILS



THE VENUS PENCIL CO., LIMITED, LOWER CLAPTON ROAD, LONDON, E.5

T.S.S. OCEAN MONARCH : THE CORAL CAFÉ



PUBLIC
BUILDINGS
HOSPITALS
HOTELS
THEATRES
CINEMAS
SHIP
FURNISHING
RESTORATION
ETC. ETC.

Architects:
Messrs. A. McINNES GARDNER & PARTNERS
Builders:
Messrs. VICKERS-ARMSTRONGS LIMITED,
NEWCASTLE
Owners:
Messrs. FURNESS WITBY & CO. LIMITED

Furnishing & Decoration
MAPLE & CO. LTD., with their subsidiary
H. H. MARTYN & CO. LTD., CHELTENHAM
have adequate facilities for undertaking large contracts under
architects' supervision. Many public buildings throughout the world
provide evidence in constructional work, furnishing and decoration

The Maple-Martyn Organisation

MAPLE
CONTRACT DEPARTMENT

MAPLE & CO. LTD., TOTTENHAM COURT ROAD, LONDON W.1.
PARIS · BIRMINGHAM · BOURNEMOUTH · BRIGHTON · BRISTOL · LEEDS · LEICESTER · NOTTINGHAM · BUENOS AIRES
GLASGOW OFFICE: 116 HOPE ST.

NUWAY

... the ideal matting for entrances and
foyers of all buildings... **WAS SELECTED FOR THE
FESTIVAL SHIP
'CAMPANIA'**

NUWAY stands up to all
weather conditions.


NUWAY is hard-wearing
under the heaviest traffic.

NUWAY is non-slip whether
wet or dry.

NUWAY deadens the sound
of noisy footsteps.

NUWAY is attractive in
appearance and clean in use.

NUWAY fibred-rubber link matting is avail-
able in any shape or size and is guaranteed
for 15 years.



A portion of the 13,000 sq. feet of Nuway matting on the flight deck of the Festival Ship
'Campania'—equivalent to a mile of matting 2' 6" wide.


NUWAY MANUFACTURING CO., LTD.
COALPORT · SHROPSHIRE

YOURS *for the Asking*


LEARN HOW TO:—
SPECIFY,
TEST,
USE,

SHERARDIZING

ZINC ALLOY
RUST PROOFING CO. LTD.
SHAKESPEARE STREET, WOLVERHAMPTON
TELEPHONE: WOLVERHAMPTON 20647-8
ALSO AT LONDON & ROCHDALE.



Contemporary Design at Reasonable Cost



Two drawer desk in Mahogany and Walnut 5'0" x 2'3", also made with double pedestals. Single pedestal can be fitted either on left hand side or right hand side.

The desk illustrated was designed by Robert & Roger Nicholson for *Hammers* and was first shown at the Council of Industrial Design, Hospitality in the Home Exhibition at the Tea Centre. It has been used with success in The Festival of Britain, South Bank and "Campania" Exhibitions.

Hammers personal service.

Church, Office, Library, Laboratory and School Furniture.
Special Architects' Joinery and Cabinet work.

GEO. M.
HAMMER
& CO. LTD.

Craftsmen in Woodwork since 1858
CROWN WORKS, HERMITAGE ROAD,
LONDON, N.4.
Stamford Hill 6691-2




Rosebank fabric No. 6656, 31" wide cretonne,
in red, blue, green or brown grounds.

Fabrics usually provide the
main notes in your colour themes—
why not solve your problem
by using the beautiful and durable
"Rosebank" range?

ROSEBANK

fabrics

TURNBULL & STOCKDALE LTD · MANCHESTER
London Office: Kent House, Market Place, Oxford Circus, W.1



A model example-

The model illustrated, an $\frac{1}{4}$ in. to 1 ft. scale, of the proposed Assembly Rooms and Little Theatre, Gloucester, made to the order of the Gloucester Corporation, is an example of Bassett-Lowke's co-ordination and craftsmanship.

Municipal Authorities and Industrial Companies who are considering planning and development are cordially invited to consult us for the production of their models and table-top layouts.

Bassett-Lowke also specialise in models of factories, plant and machinery, interiors, sectional models and working demonstration models.

Write for details contained in our brochure "Scale Models for Publicity & Exhibition" ref. SM/56 which will be gladly forwarded to executives or Purchasing Authorities free of charge.

BASSETT-LOWKE LIMITED


Head Office & Works:

NORTHAMPTON

Manchester:


28, Corporation Street

London Showrooms
112, High Holborn, W.C.1



Craftsmen

of many trades contribute to that prized possession, a Bratt Colbran fireplace: the cabinet makers, the marble masons, and the expert workers in metal. These men are artists who have real feeling for the fine materials they use. Many examples of their work can be seen at the address below.



Bratt Colbran Limited

THE 'HEAPED' FIRE • PORTCULLIS GAS FIRES • SOLECTRA ELECTRIC FIRES

10 MORTIMER STREET, LONDON W.1


Telephone MUSEUM 9411

Scottish Showrooms: A. Caldwell Young & Son, 200 St. Vincent Street, Glasgow, C.2

"Hailware"
REGD.
DC. 665 IN THE


ROYAL FESTIVAL HALL

Electrical
Contractors:
The Berkeley
Electrical
Engineering
Company,
Vincent Sq.,
London,
S.W.1.



This unit, of which several hundreds have been supplied to the Royal Festival Hall, is fitted with "Hailware" British made 3-ply Opal Glassware. Having concealed metalwork it presents a very clean and neat appearance, as can be seen from the top illustration. The patented safe, efficient and simple mechanism for securing the glassware can clearly be seen in the lower illustration. All parts of this are rustproof and there is no possibility of fouling the wiring.

Head Office: BEACON WORKS, MORLEY, YORKS.



Available in various sizes.
Write for Folder AR/CF151.

LIGHTING GLASS MANUFACTURERS AND ENGINEERS

HAILWOOD & ACKROYD LTD.

London & Export Sales Office:

18, LOWNDES STREET, LONDON, S.W.1

Tel: SLOane 0471/2




Illustration shows
Pattern No. M. 1006.
Other Patterns and
full particulars in
Catalogue A.R. 585.


HARCO PATENT METALACE

PRODUCED IN ROLLS OF 25'
TO 100' LONG BY 2'11" WIDE.

The artistic effect of Harco Patent Metalace renders it particularly suitable for use where care of design and appointment are of major importance. Architects will appreciate that it not only screens the unsightly, but allows free circulation of air. The patterns in which Metalace can be woven, make it the perfect selection for Lift Shaft Enclosures, Ventilating Panels, Radiator Covers, Electric Heater Covers, etc.

Harvey

G. A. Harvey & Co. (London) Ltd. Woolwich Road, London, S.E.7



FOR THE BIG OCCASION

The fact that Cox & Co. were selected to manufacture the Auditorium seating in the Royal Festival Hall, for the London County Council, is a recognition of their experience and skill in the field of tubular steel furniture fabrication.

This experience, extending over 25 years, is a guarantee that their standard products, whether for the automobile industry, the concert hall, office, or factory canteen, can be relied upon to give the same degree of fitness for purpose as the specialized installation made under the direction of the responsible architect.



FOR THE WORKADAY WORLD

Cox & Co. (WATFORD) LTD. WATFORD BY-PASS, WATFORD, HERTS 'Phone: WATFORD 5631 Grams: COXANCO, PHONE, WATFORD



Putting Back the Past

We have the finest craftsmen, trained in highly specialised methods of stone restoration and all work committed to our care is subject to expert supervision, technical and practical, by an experienced staff.

We also undertake the cleaning of buildings by steam, cold water and vacuum processes, as the case may demand.

Recent Contracts which we have carried out include

Bank of England, Worth Priory, Sussex,
Winchester, Canterbury and Chichester Cathedrals,
Lambeth Palace, Broadcasting House, Old
Charterhouse, London, All Saints Church, Hove.

REPARATIONS-DREYFUS

LTD

129 GREAT SUFFOLK STREET, LONDON, S.E.1

Telephone: HOP 2615

HEATON TABB & CO LTD

SPECIALISTS IN FURNISHING & DECORATION

HIGH CLASS JOINERY
FINE CABINET WORK
INTERIOR DECORATION
EXTERIOR PAINTING
UPHOLSTERY
SOFT FURNISHING
CARPETS
FLOOR COVERINGS

PUBLIC BUILDINGS
THEATRES & CINEMAS
HOTELS
LICENSED PREMISES
PRIVATE RESIDENCES
BANKS
BOARDROOMS & OFFICES
PASSENGER LINERS

ARCHITECTS' SCHEMES CARRIED OUT
DESIGNS, PERSPECTIVES & WORKING DRAWINGS
PROVIDED BY OUR OWN STUDIOS

55 Bold St.,
Liverpool, 1.

also at
Belfast & Glasgow

17 Grosvenor St.,
London, W.1.

Head Office: Adelphi Works, Cobbold Road, Willesden, N.W.10

FIREPROOF FLOORS

★ THE Smith Two-way reinforced fireproof floor can be employed for any flooring or roofing requirements.

ALL materials are available from stock.

THE employment of patent telescopic centers permits the immediate use of the floor with the additional advantage of their removal in the minimum of time.

WORKING space for other trades not obstructed by props and timber shuttering.

Midland Licensees:—Messrs. Parkfield Concrete Products Co. Ltd., St. Peter's Road, Netherton.
Phone:—Dudley 4315

WITH THE UNIQUE
TELESCOPIC CENTERING IN
ALL TYPES OF BUILDINGS



SMITH'S

FIREPROOF FLOORS LTD
IMBER COURT, EAST MOLESEY, SURREY
TELEPHONE: EMBERBROOK 3300

2 WAY REINFORCED FIREPROOF FLOORS



One of the products of the ATLAS STONE CO. LTD.


ROOFING UNITS

Durable, economical, and rot proof these simple units can be fitted and fixed to any type of roof construction by unskilled labour.

They are ideal for schools and industrial buildings.

In standard widths of 1' 6" and in lengths from 6' to 12', they can also, if necessary, be manufactured to Architects' and Builders' requirements at little extra cost. On smaller spans these units weigh only 17½ lb. per sq. ft.

Enquiries are invited from Architects, Surveyors, and Builders. Our design service is available for consultation at "the blue print stage."




TYPES

1. Flush soffit unit affording maximum insulation.
2. Standard trough section.
3. Combines the insulating qualities of Type 1 with the pleasing architectural features of Type 2.

ATLAS STONE COMPANY LIMITED

ARTILLERY HOUSE, ARTILLERY ROW, LONDON, S.W.1.
Works at MELDRETH GREENHITHE, STROOD.

Telegrams: London Offices: Atlastonco, Sowest. Telephone: Abbey 3081-2-3-4.
CAMBRIDGE, PARK ROYAL (LONDON) and SHORNE.



A new edition of

ENGLISH PANORAMA

by THOMAS SHARP, M.A., D.LITT.

INNUMERABLE BOOKS DESCRIBING THE English countryside have been published, particularly in the last twenty years. This is a very different sort of book: and it is, we believe, the first and only one of its kind. It is no mere description of beauty spots, but is a carefully-studied and original account of how the English scene in town and countryside has developed down the centuries, ending with a penetrating analysis of the problems of town and country planning with which we are faced today. When it was first published in 1936 it was described as "the most important contribution to the subject which has yet been made" (*Country Life*); "a large-visioned, well-balanced and uncommonly vital book" (*Manchester Guardian*); "as sound and clear as a bell" (*New Statesman*); and it has come to be regarded as something of a classic of its kind. It has been out of print for ten years; and for this new edition it has been in part revised, many new pages have been added, and it is almost entirely newly illustrated. All Thomas Sharp's dozen or more books have been praised for the quality of their writing, as well as for the ideas which they contain; and ENGLISH PANORAMA, along with the rest, though it contains much of interest for the specialist reader, is essentially a spirited and straightforward essay on a subject which should appeal to everyone who has eyes to see.

Bound in full cloth boards. Size 8½ in. by 5½ in.
148 pages, with over fifty half-tone and line illustrations.

12s. 6d. net. Postage inland 7d.

THE ARCHITECTURAL PRESS
9-13 Queen Anne's Gate, Westminster, S.W.1

★ **Fifty experts of national renown
have combined to make**

Modern Building Construction

Edited by **RICHARD GREENHALGH, A.I.Struct.E.**

The most up-to-date, comprehensive and reliable work available for craftsmen, builders, surveyors, architects, and specialists in professions allied to building. The three volumes contain a wealth of experience and data, given by experts who have learned from years of practical work the best way to do a job.

Send this coupon to-day

THE NEW ERA PUBLISHING CO. LTD.
Pitman House, Parker Street, London, W.C.2
 Please send me, free of cost or obligation, your illustrated brochure on **MODERN BUILDING CONSTRUCTION**, and particulars of your offer to deliver the complete work for a nominal first payment, the balance to be paid by a few further monthly instalments.

Name
 Address
 Date South African enquiries to
 (CENTRAL NEWS AGENCY, BOX 1033,) A.R.20
 JOHANNESBURG

Craftsmanship in Building
 Building Calculations
 Builder's Geometry
 Building Science
 Brickwork
 Training of Craftsmen and Specialists in the Building Industry
 Roof Coverings
 Plastering
 Painting and Decorating
 Paperhanging
 Glazing
 Plumbing
 Gas-Fitting
 Electrical Fitting
 Training and Opportunities of an Architectural Student
 History of Architecture
 Architectural Drawing
 Architectural Design
 Architectural Acoustics
 Architect's Office and Routine
 Structural Engineering
 Fire-resisting Construction

Concrete: Plain and Reinforced
 Masonry
 Joinery
 Carpentry
 Stairs and Handrails
 Shop Fronts and Fittings
 Builder's Office and Routine
 Book-keeping, Accounting, Costing
 Estimating
 Preliminary Operations
 Superintendence
 Drainage and Sanitation
 Heating
 Ventilation
 Prefabrication
 Land Surveying and Levelling
 Specifications and Quantities
 Building Law
 Royal Institute of British Architects
 Chartered Surveyors' Institution
 Institution of Structural Engineers

PRESENTED IN THREE PROFUSELY ILLUSTRATED VOLUMES WITH FIVE INSET COLOUR PLATES

Specify



"DURABLE REFLECTIVE ROOFING" is a scientific mastic roofing carrying a twenty year guarantee and very moderate in price. May we send you details?

Southern Depot:
 Great Testwood,
 Totton,
 Nr. Southampton.


Northern Depot:
 Gladstone Street,
 Huntingdon Rd.,
 York.

*Kimberley House,
 14/17, Holborn Viaduct
 E.C.1*

Durable Asphalt Co. Ltd.

*Asphaltic Flooring,
 Roofing, Tanking and
 Damp Course Work, and
 "Built-up" Felt Roofing*

*Telephones:
 City, 1456/7, 4553, 6271*



of London



● designed by Robin Day

shown at the **Festival of Britain**
and at the **Ninth Triennale, Milan**





S. HILLE AND COMPANY LTD., 439-451 LEA BRIDGE RD., LEYTON, LONDON, E.10. LEYtonstone 4466-7

The Colour and freshness of Spring-


Can be introduced to the dingiest of interiors, the whole year round by using "Arkamatte" Flat Oil Paint for Wall treatment and "R.K.Duro" Gloss Paint for woodwork etc. These "Kearsley" products make the ideal decorative scheme for Schools, Hospitals, Public and Private buildings. Shade books on request to:—

ROBERT KEARSLEY & CO. RIPON · YORKS

100 Years ..



of adjustability



and always
"ON THE LINE"



Best and Lloyd Limited

MAKERS OF FINE LAMPS SINCE 1840. Head Office and Works WATTVILLE ROAD, HANDSWORTH, BIRMINGHAM

Second large printing now ready

LONDON NIGHT AND DAY

a guide to where the other books don't take you

illustrated by OSBERT LANCASTER

edited by SAM LAMBERT


The whole of the contents of the special issue of The Architects' Journal for May 3, 1951 is now published in pocket-book form with a coloured cover designed by Osbert Lancaster. If you want copies for yourself or your friends, it is available in all bookshops, at the price of 3s. 6d.

This book is different from all other books, guides, encyclopaedias : it tells you what the others don't tell you ; it takes you where the others won't take you ; and it covers a wider range of subjects in its 100 close-set pages than any comparable volume—how to see a murder trial or a newspaper printed ; where to find a jazz club, a tartan kilt or a Turkish Bath ; City taverns and ducal homes to visit ; where to buy caviar or a hat, glass eyes or riding boots and a thousand other things. It has been compiled by a team of experts and research-workers, all ardent Londonophiles, writing factually but affectionately of the London of 1951, the greatest man-hive in the world. Its accent is personal and practical and the London it reveals is the hidden, secret, under-the-surface London, a place alive and to be enjoyed rather than the on-the-surface London of the standardised guides. Its presentation is, we think, original too in that it takes the reader round the 24 hours of the clock giving suggestions, where to go, what to do, for each hour of the day and night. And throughout its pages Osbert Lancaster supports our stream of good advice with drawings that eloquently evoke London's under-the-surface look.

Size : 5½" x 8½", bound in stiff card. 100 pages with over 40 drawings and a cover by Osbert Lancaster. Price 3s. 6d. net.

THE ARCHITECTURAL PRESS · 9 Queen Anne's Gate · London · S.W.1

★ *Selected for inclusion in the stock list as worthy examples of British Design & Manufacture.*



GENERAL PURPOSE
NESTING CHAIR

SCHOOL FURNISHING



Contractors to H.M. Government
County and Education Authorities




H·C·SHEPHERD & COMPANY LTD

Hersham Station Works WALTON on THAMES, Surrey. ★
MANUFACTURERS OF TUBULAR STEEL FURNITURE

WALTON ON THAMES 2314

THE COBURN SYSTEM



*Sliding
Door
Gear*

Specify the original and best
sliding door gear for all your
future jobs.

*Cold rolled steel tracks
Best grey cast-iron brackets
Maintenance-free trolleys*

Write for drawings, catalogue
and advice.

Obtainable from all Builders' Merchants

TELEPHONE: TELEGRAMS:
WATERLOO 4311 TROLTRACK, SEDIST,
(3 lines) LONDON

The **BRITISH TROLLEY TRACK CO**
COBURN WORKS, COPPERFIELD STREET
LONDON, S.E.1



If you have the
problem of seating a lot of
people and then have to

CLEAR OUT

the hall for another purpose Pel Nesting Furniture
will provide a quick answer. It will stack away
neatly in next to no time.

PEL CHAIRS TABLES NEST

The models shown are Chair RP.6 (Woodslats) and Table NT.2. There
are many different designs in strong, but light, tubular steel, either chro-
mium plated or rust proofed and stove enamelled. Ask for illustrated leaflet.



MADE BY PEL LTD • OLDBURY • BIRMINGHAM

London Showrooms: 15 Henrietta Place, London, W.1.



A COMPANY

Distributors throughout the Country.

raw/sot52

now ready

NEW WAYS of BUILDING


revised and enlarged edition, edited by • ERIC DE MARÉ, A.R.I.B.A.

THIS IS A NEW KIND of book on building construction. Its
purpose is to fill a gap by acting as an appendix, or post-graduate
course, to the standard publications used by architectural and
building students. As such it is designed to be of value to the
practising architect and to all others interested in contemporary
building, as well as to the student. The book is of a new kind in two
other ways; first, in being written, not by one author, but
by a group of men, each a specialist in his own subject, on whose
knowledge the general practitioner can rely; second, in
attempting to be something more than the usual dull textbook by
illustrating examples of buildings at home and abroad selected not
merely to inform on technique but to stimulate the designer's
visual imagination.

Bound in full cloth boards
Size 9½ by 7½ ins., 256 pages, over
200 photographs, plans and drawings
30s. net. • postage 8d.

contributors {
Dr. K. Hajnal-Kónyi • concrete
O. Bondy • steel
Phillip O. Reece • timber
K. Cheesman • glass
W. B. McKay • brickwork
Philip Scholberg • light metals and plastics
C. C. Handisyde • insulation

THE ARCHITECTURAL PRESS • 9-13 Queen Anne's Gate • SW1



SOUTH BANK TIME

To ensure accurate synchronization, all clocks at the South Bank exhibition are part of the same GIBSON MASTER CLOCK SYSTEM. The Master Clock controls the 133 slave clocks and Time Recorders in different parts of the exhibition, and batteries, charged from the mains, keep the system running in the event of a power cut. The slave clocks are designed to harmonize with the buildings in which they are installed.

The GIBSON system is used in many large buildings, office blocks and schools. From the point of view of economy the installation should be planned at the same time as the other services. BAUME & CO. LTD. are specialists in electrical time-indication and are always willing to make clocks to any design.

BAUME & CO. LTD.

LONDON AND LA CHAUX-DE-FONDS

CLOCK AND WATCH MAKERS FOR MORE THAN A CENTURY

The Gibson slave clock in the booking hall of the Festival underground station at Waterloo

BAUME
WATCHES

Longines
WATCHES

HEUER
TIMERS

Gibson
CLOCKS



OLYMPIA

EARLS
COURT

BIF

CASTLE
BROMWICH

SPACE APPLICATIONS URGENT

Intending exhibitors should apply for space without delay.

Manufacturers who have not received an application form should write at once—

FOR THE LONDON SECTION TO:

The Commercial Relations and Exports Department,
Board of Trade, Lacon House, Theobalds Road, London, W.C.1.
Telephone: CHANCERY 4411.

FOR THE ENGINEERING AND HARDWARE SECTION TO:

Birmingham Chamber of Commerce,
95, New Street, Birmingham, 2.
Telephone: Birmingham MIDLAND 5021.


BRITISH INDUSTRIES FAIR • MAY 5-16, 1952

TIDMARSH


*for Quality,
Craftsmanship
and Service*



**TIDMARSH
and SONS**
TRANSENNA WORKS
LAYCOCK ST. · LONDON N.1.



CONSERVATORIES FOR PUBLIC PARKS



CONSERVATORY ERECTED IN NORTH OF ENGLAND PARK

We have now resumed the building of green-houses and shall be pleased to receive enquiries

MESSENGER & Co., Ltd.

Horticultural Builders

LOUGHBOROUGH

London Office: 122 VICTORIA STREET, S.W.1

Always heard - seldom seen.

AMID the flowers, a microphone; behind the oak panelling, an amplifier; somewhere by each graceful pillar, a loudspeaker. In cathedral nave or stately banqueting room, Philips Sound Reproducing Equipment is indeed as unobtrusive as it is efficient.


In the planning of new buildings, or in the replanning of old, provision for clear, faithful sound reproduction is an essential. A church—a factory, a hospital, an ocean liner—for so many of these Philips installations are invariably chosen. In the solution of any acoustical problem, the Philips Organisation is always at your service.



PHILIPS ELECTRICAL LTD.

RADIO & TELEVISION RECEIVERS · TUNGSTEN, FLUORESCENT, BLENDED & DISCHARGE LAMPS & LIGHTING EQUIPMENT · 'PHILISHAVE' ELECTRIC DRY SHAVERS
CYCLE DYNAMO LIGHTING SETS · 'PHOTOFLUX' FLASHBULBS · HIGH-FREQUENCY HEATING GENERATORS · X-RAY EQUIPMENT FOR ALL PURPOSES · ELECTRO-
MEDICAL APPARATUS · ARC & RESISTANCE WELDING PLANT & ELECTRODES · ELECTRONIC MEASURING INSTRUMENTS · MAGNETIC FILTERS · BATTERY
CHARGERS & RECTIFIERS · SOUND AMPLIFYING INSTALLATIONS · CINEMA PROJECTORS · RECORDING APPARATUS.

PHILIPS ELECTRICAL LIMITED, DEPT. ELA AMPLIFIERS, CENTURY HOUSE, SHAFTESBURY AVENUE, LONDON, W.C.2.
(A851)



DRYAD FITTINGS

SELECTED
for many of the
**FESTIVAL
BUILDINGS**

by the
Council
of
Industrial
Design
and
Festival
Architects

DRYAD METAL WORKS LIMITED

40-42, SANVEY GATE, LEICESTER






London Distributors—A. J. BINNS LTD., 99, ST. PAUL'S RD., N.1
Ironmongery of Good Design, Construction and Finish



5,000 Pieces of Race Furniture
comprising 16 separate designs have been selected for exhibition
and for use in the Festival of Britain

Ernest Race Limited 22, Union Road, Clapham,
London, S.W.4

BITULACUM

prevents disintegration of walls and floors of concrete, plaster, cement
or brick . . . resists penetration of moisture,  petrol, oil,
grease and  paraffin . . . is equally suitable for use indoors
and out . . . is supplied in 15 standard colours, black, white and transparent,
matt or gloss finish . . . for walls  and floors of factories, workshops,
power stations, garages, canteens, aeroplane  hangars . . . for
exteriors of all buildings of brick, concrete and stone. 

*Bitulac Ltd., Collingwood Buildings, Newcastle upon Tyne, 1
London Office: 219/220 Dashwood House, Old Broad Street, London, E.C. 2*

BRITISH REPLIN LTD.

Suppliers to the New House of Commons

We are proud that our Replin fabric has been selected to cover seating accommodation in the new House of Commons. Our Gobelins type fabric is produced in plain, stripes, traditional and modern all-over designs and floral panels, coupling beauty with hard wearing quality.

We specialise in individual designs.

Factory:
AYR, SCOTLAND

Sales Office:
46 DORSET STREET, LONDON, W.1
Tel.: Welbeck 5384

P. & H. (Cabinet Makers) Ltd.

(Incorporating F. & J. Pilditch & Co.)

Specialists in well-made furniture for Directors' Offices, Board Room and Library furniture, etc.
Built-in and other furniture to Architects' specification.



19, ALL SAINTS' ROAD, LONDON, W.11

Telephone : PARK 9837.



High Victorian Design


a study of the exhibits of 1851

by NIKOLAUS PEVSNER

TO RUSKIN the Crystal Palace was no more than 'a greenhouse larger than ever greenhouse was built', to Tennyson the objects shown within it were 'shapes and hues of Art divine, all of beauty, all of use'. Today the exhibits are considered outrageous 'examples of the hideous and the debased', but the building cannot be too highly praised; it is 'a precept inspiring as the Parthenon, an exemplar vital as the Pont du Gard'.

This complete changeabout in taste, and the contrast in the reaction to the *architecture* as opposed to the *design* of 1851 amongst critics of 100 years ago is as puzzling as that amongst critics of today. Obviously there is a problem here, and it is that problem which Dr Pevsner, our most eminent critic of both architecture and design, attempts to solve in the present volume. He finds his solution in a penetrating and detailed examination of a selected 120 1851 exhibits. Why did, for instance, some of the most intelligent critics admire unreservedly the machine carving of Gothic ornaments on a church screen? What frame of mind can explain the Irish bog-oak chair with its two arms formed by wolf-dogs, one at ease and recumbent, the other infuriated and sitting up so that nobody could use the chair in comfort? In answering many such questions Dr Pevsner arrives at certain conclusions which go far in explaining the mentality of the mid-nineteenth century, not only in matters aesthetic, but also in many other matters.

Size, crown 8vo., bound in full cloth boards, with 162 pages containing over 120 illustrations, and with a jacket in colour designed by Gordon Cullen. Price 12s. 6d. net, postage 4½d.



From Dr Pevsner's book: the Irish bog-oak chair.

THE ARCHITECTURAL PRESS 9-13 QUEEN ANNE'S GATE WESTMINSTER SW1



JUST PUBLISHED

a pocket guide to **MODERN**
buildings in **LONDON**
by IAN McCALLUM

THIS IS A NEW GUIDE BOOK which neither practising architects nor serious students of architecture, nor, for that matter, the layman, can afford to ignore. In his introduction Mr. McCallum outlines the development of architecture over the past century. In the following ninety pages he illustrates and describes the most significant modern buildings to be seen within seven miles of the centre of London, from Crawford's Offices in Holborn (1929) to the Royal Festival Hall on the South Bank (1951) and including—among other types—department stores, flats, health centres, permanent and temporary houses, offices. The book is compiled and arranged in such a way as to enable readers to find their way easily to the buildings discussed. For their convenience it is divided into four sections: North-west London, North-east, South-east and South-west; and full details of bus and L.T. railway routes are provided. The book is completed by a bibliography and comprehensive index, listing more than ninety buildings worthy of careful study.

Bound in stiff board cover. Size 5½" by 4½". 128 pages with 36 illustrations, 5 maps, a bibliography and 3 indexes. Price 3s. 6d. net, postage 4d.

THE ARCHITECTURAL PRESS 9-13 QUEEN ANNE'S GATE WESTMINSTER SW1



SOLVE your fixing problems before construction is finished. Choose the machines and when they arrive—fix them fast, permanently and ready for instant use with Rawlbolts—no grouting-in—no cement to harden. Rawlplugs . . . speed the screw fixings with them! Switchgear, conduit, lighting, pipes and all similar fixtures—get them up quickly.

Use Rawlplug Fixing Devices where "speed is the essence of the contract"

RAWLPLUG
FIXING DEVICES

WRITE FOR TECHNICAL LITERATURE

B398

THE RAWLPLUG COMPANY LIMITED • CROMWELL ROAD • LONDON • S.W.7

JAMES make good METAL WINDOWS

W. JAMES & CO. LTD.
Hythe Rd. Willesden Junction
LADBroke 3611 N.W.10

The best from Scandinavia—



Fritz Hansens Eftl., Copenhagen.

imported by

FINMAR LTD


12-16 HOLBEIN PLACE, SLOANE SQUARE
LONDON, S.W.1 • Telephone Sloane 5565

Vent-Axia for Better Air Conditions




IN INDUSTRY
IN COMMERCE
IN AGRICULTURE
IN THE HOME

Simplest
form of controlled
ventilation



VENT-AXIA LTD. 9 VICTORIA STREET, S.W.1
ABBy 6441 (7 lines). Glasgow, Manchester, B'ham, Leeds

down to details?



then
it's
as well
to remember... that an important con-
tributory factor to the
safety and dependability
of any new building is the
use of ASHTON cables
and flexibles for all lighting and
power duties.

ASHTON cables and flex-
ibles are manufactured to
BSS. No. 7.1946, amend-
ment No. 3. August 1949
PD. 947.

ASHTON

CABLES & FLEXIBLES

AERIALITE LTD. CASTLE WORKS, STALYBRIDGE, CHESHIRE

*Honoured Sir,
To write well and legibly is to
show good manners and good sense
Nor is it difficult now as once it was . . .*

. . . Chancery Script is the beautiful style which made Sixteenth Century manuscripts so cultured in appearance and so delightfully readable. In recent years, a growing number of people have revived it as a delightful hobby — creative, easy to learn and inexpensive. Now, in response to increasing pressure from writers, Mabie, Todd have produced the new Swan Calligraph pen, with a nib specially ground in the shape of the old-time quill! Now everyone can learn the simple art of writing Chancery Script, to give themselves a fascinating pastime and enrich the grace of their handwriting.

Quill nib, hand cut,
in the heyday of fine
handwriting.



Swan Calligraph nib, cut
like a quill for writing
Chancery Script.



A Swan "Manuscript Ink" has been created for use in the new Swan Calligraph pen. It is delightfully even in flow and dries with the characteristic black which is so much part of the clarity and attractiveness of the Script.

41/- INCLUDING TAX · Ask your Stationer for particulars

THE
Swan Calligraph



Mabie, Todd & Co. Ltd. Swan House, Whitby Ave., Park Royal, N.W.10



for Bathrooms, Kitchens,
Canteens, etc.

Specify

VITROLITE wall-lining by

D.W. PRICE of NEASDEN

GLADSTONE 7811-5

N.W. 10

and at

PECKHAM

ENFIELD

TAUNTON



These gates with
pillars and over-
throw were recently
erected at Bailey's
Hotel, Gloucester Rd.,
Kensington.
Architects—Grace and
Farmer, London, W.1.

Craftsmen in Handwrought Ironwork

We offer original masterpieces of the past, but we also have the skill to copy or adapt beautiful antique work to modern purposes and the artistry to create graceful new designs. If you are interested in wrought iron, for any purpose, from a weather vane to the finest entrance gates, please write to:

HANCOCK INDUSTRIES LTD.,


London Office: 4, PARK MANSIONS ARCADE, KNIGHTSBRIDGE, LONDON, S.W.1. Tel. KEN. 3077. Works: CROWHURST ROAD, LINGFIELD, SURREY.



Registered Trade Mark

Reproduction,
Board Room,
Office, and
Fireside

Chairs
of
Distinction
by
Craftsmen



740

E. M. F. BROWN (QUALITY TOWN) LTD.

11 Duke Street, High Wycombe, Bucks

Telephone & Telegrams: High Wycombe 639

OAKWOOD ROOFING TILES

reduce "overhead" costs

OAKWOOD TILES LTD. BRADWELL WOOD,
TUNSTALL. STAFFS.

Country Buildings

*How to Appreciate Them
and How to Draw Them*

By
WILLIAM R. FINCH

THIS novel book has a twofold object—to capture the charm and character of country buildings, and to encourage those who would like to draw them. Numerous illustrations of small houses, cottages, farm buildings, barns, etc., are included in the book and all have been carefully selected to cover every important aspect of the particular subject treated. Traditional building materials and methods are also described and illustrated. Architectural students and all who are sensitive to charm in buildings will find this book one of exceptional interest and pleasure. **30/- net.**

A Pitman Book

Parker St. • Kingsway • London, W.C.2

PARK YOUR CYCLES THE ODONI WAY

(REGD. TRADE MARK).

with Odoni Patent "All Steel" BICYCLE STANDS

Types to suit all possible requirements for indoor or outdoor use—single or double sided, horizontal or semi-vertical.

Type 4 Odoni horizontal stand as supplied to the L.C.C.
ROYAL FESTIVAL HALL.

Full details from Sole Manufacturers and Patentees:

ALFRED A. ODONI & CO. LTD.

SALISBURY HOUSE, LONDON WALL, LONDON, E.C.2.
(Works: LONDON, N.W.)

Telephone: MONarch 8638-9. Telegrams: Odoni, Ave, London.




the Wellstood

*continuous-burning insulated cooker
with hot water boiler*

The Wellstood meets the demand for a modern cooker, with large boiling area and two ovens, suitable for coal or any solid fuel. Average weekly consumption, with day and night burning, $1\frac{1}{2}$ to 2 cwts. (coal). With daily lighting hotplate cooking temperatures are available in less than 30 minutes. Other features: Openable fire, hinged insulated hotplate cover, thermometer, towel rail, enamel finish. Reversible flue outlet for 5 in. pipe. Entirely self-contained. Approved by Ministry of Fuel and Power.

	Width	Depth	Height
Overall Size	33"	20"	32"
Top Oven	14"	15½"	12"
Lower Oven	14"	15½"	8"
Boiling Plate	22½"	7½"	—



*Write for Information
Sheet*

SMITH & WELLSTOOD LTD
Bonnybridge Scotland
London: 63 Conduit Street W.1

ST. PANCRAS WAY


Architects: Messrs. Norman & Dawbarn.

STEEL BALUSTRADING, PUBLIC & PRIVATE
BALCONY RAILINGS, DOORS TO REFUSE
CHAMBERS, PLAYGROUND ENCLOSURE &
SPECIAL LAMP STANDARDS.

LIGHT STEELWORK (1925) LTD.

HYPHE ROAD, WILLESDEN, N.W.10

Tel.: LADbroke 3674



Architectural Review
Photograph.



PRIMAVERA 149 SLOANE ST., S.W.1. SLO. 5779

Sea air and
kitchen steam and
city smoke are hard
on paint

**BROLAC
CAN
TAKE IT!**

— says Painter Bill



Brolac

THE DOUBLE PROTECTION PAINT
WITH THE ENAMEL FINISH

You will find MURAC, the matt oil finish made in the Brolac works, ideal for interior decoration. Send for the FREE Brolac colour scheme booklet to

JOHN HALL & SONS (BRISTOL AND LONDON) LTD • HENGROVE • BRISTOL 4




DC. 99

DAMP CANNOT RISE ABOVE THE ASTOS LINE

Charles House, Kensington
Architect: Major Arthur S. Ash, F.R.I.B.A.
Dampcourse: Standard Astos

The increasing specification of Astos Dampcourse for Commercial Buildings, Schools, Housing Schemes and Public Buildings is a sure indication of its popularity where quality is the first consideration. Fully described in leaflet No. 555. Standard or Lead-lined in all wall widths up to 36 inches. Rolls contain 24 lineal feet.



THE RUBEROID COMPANY LIMITED

104, COMMONWEALTH HOUSE, NEW OXFORD STREET, LONDON, W.C.1

Hoskins
METAL WINDOWS

The
"Hallmark"




of Quality

for **HOME
OFFICE
SCHOOLS and all
KINDS of
INDUSTRY,
NON-FERROUS for
SHIPBUILDING.**

HOSKINS & SEWELL LTD.
BORDESLEY
BIRMINGHAM 12 • England
Telephone: VICTORIA 2340

ALPHABETICAL LIST TO ADVERTISERS


	PAGE		PAGE		PAGE
Abraham, Robert, & Co. Ltd.	ciii	Fox, Samuel, & Co. Ltd.	cx	P. & H. (Cabinet Makers), Ltd.	cxxx
Accrington Brick & Tile Co. Ltd., The	cxiii	Franki Compressed Pile Co. Ltd., The	xi	Parnall, George, & Co. Ltd.	ci
Adamsee, Ltd.	xix			Patman & Fotheringham, Ltd.	cviii
Aerialite, Ltd.	cxxxii			Paul, W. H., Ltd.	xc
Allied Ironfounders, Ltd.	xvi	Gas Council, The	xcv	Pel, Ltd.	cxxxvi
Aluminium Union, Ltd.	v	Gaskell & Chambers, Ltd.	lxxxix	Phillips Electrical, Ltd.	cxxxviii
Armstrong & Co. (Wridale), Ltd.	xxxvii			Pilkington Bros., Ltd.	lxxiv, 143
Ascot Gas Water Heaters, Ltd.	lxvi, lxvii	Haden, G. N., & Sons, Ltd.	li	Pilkington's Tiles, Ltd.	xviii
Atlas Stone Co. Ltd.	cxxi	Hailwood & Ackroyd, Ltd.	cxviii	Pitman, Sir Isaac, & Sons, Ltd.	cxxxiv
Avery, J., & Co. Ltd.	lxxxii	Hall, John, & Sons (Bristol & London), Ltd.	cxxxv	Pollard, E., & Co. Ltd.	xc
		Hammer, Geo. M., & Co. Ltd.	cxvi	Pressure Piling Co. Ltd., The	lxix
Banister, Walton & Co. Ltd.	xlvi	Hammond & Champness, Ltd.	lvi	Price, D. W., & Son, Ltd.	cxxxiii
Bassett-Lowke, Ltd.	cxvii	Hancock Industries, Ltd.	cxxxiii	Primavera	cxxxv
Baume & Co. Ltd.	cxvii	Hardwood Flooring Manufacturers' Association, The	lxxxviii	Pugh Bros., Ltd.	xlili
Bayliss, Jones & Bayliss, Ltd.	civ	Harris & Sheldon, Ltd.	lxxi	Pyrene Co. Ltd., The	cxii
Best & Lloyd, Ltd.	cxvix	Harvey, G. A., & Co. (London), Ltd.	cxviii		
Bitulac, Ltd.	cxvix	Heal & Son, Ltd.	144	Race, Ernest, Ltd.	cxxxix
Boulton & Paul, Ltd.	xxxii	Heaton Tabb & Co. Ltd.	cxv	Rawplug Co. Ltd., The	cxxxix
Bowaters Building Boards, Ltd.	lxxvi	Heywood, W. H., & Co. Ltd.	xxv	Redpath Brown & Co. Ltd.	lii
Bradford, F., & Co. Ltd.	xl	Hille, S., & Co. Ltd.	cxviii	Rennis, Ltd.	lxi
Bratt Colbran, Ltd.	cxvii	Hills (West Bromwich), Ltd.	lx	Reparations-Dreyfus, Ltd.	cxix
Brightside Foundry & Engineering Co. Ltd.	xxx, cvii	Holcon, Ltd.	cvi	Rowe Bros. & Co. Ltd.	xcii, xciii
British Industries Fair	cxvii	Holland & Hannen and Cubitts, Ltd.	lxxiii	Ruberoid Co. Ltd., The	cxxxv
British Lead Mills, Ltd.	xxxix	Holophane, Ltd.	xxxvi		
British Reinforced Concrete Engineering Co. Ltd.	cxxxviii	Holoplast, Ltd.	l	Sanderson, Arthur, & Sons, Ltd.	xli
British Replint, Ltd.	cxv	Hope, Henry, & Sons, Ltd.	lxxxvi	Sankey, J. H., & Son, Ltd.	iv
British Trolley Track Co. Ltd., The	cxv	Horseley Bridge & Thomas Piggott, Ltd.	lvii	Scul, Arthur, & Son, Ltd.	xiv
Brown, E. M. F. (Quality Town), Ltd.	cxxxiii	Hoskins & Sewell, Ltd.	cxxxv	Sealanco (St. Helens), Ltd.	xliv
Bryant, C., & Son, Ltd.	xxi	Hygienette Mfg. Co.	cx	Semtex, Ltd.	xxii
				Shepherd, H. C., & Co. Ltd.	cxxxv
Carter & Co., Ltd.	lxxii	Ideal Boilers & Radiators, Ltd.	xlvi, lxxviii	Smith's Fireproof Floors, Ltd.	cxv
Celotex, Ltd.	xiii	International Paints, Ltd.	xxiv	Smith & Pearson, Ltd.	xxvii
Chance Bros., Ltd.	xcvi			Smith & Wellstood, Ltd.	cxxxvi
Chubb & Sons Lock & Safe Co., Ltd.	xx	James, W., & Co. Ltd.	cxxxii	Sterne, L., & Co. Ltd.	—
Clarke Ellard Engineering Co. Ltd.	lxxxiv			Stillite Products, Ltd.	liii
Copperad, Ltd.	lxii	Kearsley, Robert, & Co.	cxviii	Sugg, Wm., & Co. Ltd.	cxlii
Costain, Richard, Ltd.	lxxvii	Kingfisher, Ltd.	xciv	Synchronome Co. Ltd., The	cxii
Courtney Pope (Electrical), Ltd.	lxxxii	Kirk & Kirk, Ltd.	lxxx		
Cowper Penfold & Co. Ltd.	ix	Kwikform, Ltd.	xxxiv, xxxv	Taylor, Robert, & Co. (Ironfounders), Ltd.	lxxix
Cox & Co. (Watford), Ltd.	cxix			Thompson, John, Beacon Windows, Ltd.	xvii
Craigpark Electric Cable Co. Ltd., The	lxv	Laing, John, & Son, Ltd.	lii	Thorn Electrical Industries, Ltd.	xlvi
Crittall Manufacturing Co. Ltd., The	xxix	Light Steelwork (1925), Ltd.	cxxxiv	Tidmarsh & Sons	cxxxviii
C. S. A. Industries, Ltd.	viii	Line, John, & Sons, Ltd.	cv	Timber Development Association, The	xxviii
				Troughton & Young (Lighting), Ltd.	xcix
Dawnays, Ltd.	lxx	Mabie, Todd & Co. Ltd.	cxxxiii	Turnbull & Stockdale, Ltd.	cxvi
De La Rue, Thomas, & Co. Ltd.	145	Mallinson, William, & Sons, Ltd.	xlii	Twistell Reinforcement, Ltd.	cxxxvii
Dene Quarries (Derbyshire), Ltd.	lxxxiii	Maple & Co. Ltd.	cxiv		
Downing, G. H., & Co. Ltd.	xv	Marley Tile Co. Ltd., The	lxxxviii	United Paint Co. Ltd., The	cxxxvi
Drake & Gorham, Ltd.	146	Mather & Platt, Ltd.	xii		
Dryad Metal Works, Ltd.	cxvix	McAlpine & Co. Ltd.	cii	Val de Travers Asphalte Paving Co. Ltd.	xcvii
Dunlop Rubber Co. Ltd.	xxxi	Mellows & Co. Ltd.	lxxxvii	Vent-Axia, Ltd.	cxxxii
Durable Asphalte Co. Ltd.	cxvii	Messenger & Co. Ltd.	cxxxviii	Venus Pencil Co. Ltd.	cxiv
		Midland Electric Mfg. Co. Ltd.	xxiii	Via-Duct Heating & Ventilating Co. Ltd.	lxxv
Econa Modern Products, Ltd.	lix	Milners Safe Co. Ltd.	148		
Edison Swan Electric Co. Ltd., The	lviii			Walpamur Co. Ltd., The	x
Expandite, Ltd.	xcviii	National Federation of Clay Industries	xxxviii, xlvi	Warner & Sons, Ltd.	cx
		Neuchatel Asphalte Co. Ltd., The	c	Weatherfoil Heating Systems, Ltd.	cix
Farmiloe, T. & W., Ltd.	ii	Newalls Insulation Co. Ltd.	xxvi	White Allom, Ltd.	lxxxv
Faulkner Greene & Co. Ltd.	lxiii	New Era Publishing Co. Ltd.	cxvii	Whitehead, D., Ltd.	lv
Ferro-Concrete & Stone (North Notts), Ltd.	xxxiii	Newman, William, & Sons, Ltd.	liv	Williams & Williams, Ltd.	vi, vii
Fibreglass, Ltd.	147	Nuway Mfg. Co. Ltd.	cxv	Wood, Edward, & Co. Ltd.	lxix
Finch, B., & Co. Ltd.	xlx				
Finmar, Ltd.	cxxxii	Oakwood Tiles, Ltd.	cxxxiv	Zinc Alloy Rust Proofing Co. Ltd.	cxv
		Odoni, Alfred A., & Co. Ltd.	cxxxiv		



The modern economical treatment for the preservation and decoration of cement, stone, concrete, brick and plaster surfaces.

THE UNITED PAINT CO. LTD
 15, St. Helens Place, London, E.C.3

LIVERPOOL NEWCASTLE-ON-TYNE CARDIFF, ETC.




In times of shortage and difficulty it is essential for buyers to be able to rely on their suppliers. For this reason 'Twistee' were selected by contractors to supply fabric reinforcement to the South Bank site and 25,000 square yards of Wireweld were used.



LONDON: 43 UPPER GROSVENOR STREET, W.1. Tel: GROsvenor 1216. MANCHESTER: 7 OXFORD ROAD, MANCHESTER.1. Tel: Ardwick 1691
BIRMINGHAM: ALMA STREET, SMETHWICK, 40. Tel: Smethwick 1991.
GLASGOW: 146 ARGYLE STREET, GLASGOW. C.2. Tel: Central 4551

Reinforced Concrete is construction at its best



Reinforced concrete dockside warehouses have a long life, are verminproof, and have a high degree of resistance to fire and explosion. The monolithic construction ensures a large factor of safety against damage by overloading.

BRC

THE BRITISH REINFORCED CONCRETE ENGINEERING CO. LTD., STAFFORD
Specialists in Reinforced Concrete Design & Suppliers of Reinforcement
LONDON, BIRMINGHAM, BRISTOL, LEEDS, LEICESTER, MANCHESTER, NEWCASTLE, SHEFFIELD, CARDIFF, GLASGOW, DUBLIN, BELFAST